

T0007: The final CFHTLS release

P. Hudelot¹, Y. Goranova¹, Y. Mellier¹, H. J. McCracken¹,

F. Magnard¹, M. Monnerville¹, G. Sémaire¹,

J.-C. Cuillandre², K. Withington²

N. Regnault³, M. Betoule³

M. Schultheis^{1,4}

Hervé Aussel⁵

¹ Terapix/Institut d'Astrophysique de Paris


² Canada-France-Hawaii Telescope

³ LPNHE, CNRS-IN2P3 and Universites Paris 6 & 7

⁴ Observatoire de Besançon

⁵ AIM CEA CNRS, Saclay

September 10, 2012



1 Summary

This document describes the 7th and final release of the Canada-France-Hawaii Telescope Legacy¹, CFHTLS T0007. CFHTLS T0007, as in previous releases, comprises two components: “CFHTLS Deep”, four independent 1 deg² MegaCam pointings and “CFHTLS Wide” comprising 171 MegaCam pointings which, due to the limited overlaps between adjacent fields consists of ~ 155 deg² in four contiguous independent patches. The sky location of these fields is shown in Figure 1). This final release of the CFHTLS benefits greatly from vastly improved flat-fielding and photometric calibration techniques developed by the Supernovae Legacy Survey (SNLS) team and CFHT which allows us to significantly improve the precision of our photometric calibration compared to previous releases.

T0007 is derived from a parent sample comprising all validated images obtained during the survey, i.e., between May 26, 2003 and February 02, 2009, which successfully passed Elixir² de-trending observations. In addition, this release contains DDT (director’s discretionary time) observations targeted to fill missing half-CCDs caused by malfunctioning detectors over the course of five months in 2003. All science stacks have been visually inspected examined and quality control information is available for each of them.

Observations are made in u^*grz and either i or “y” (the “y” represents the replacement i -band filter, and is known as $i2$ at CFHT) filters. Stacks are delivered as MegaCam-size FITS image covering a field of view of 1 deg², with a pixel scale of 0.1860''. Each tile is located at each pre-defined center position listed in Table 32 for the Wide survey and Table 18 for the Deep. In addition, the Deep survey contains two sets of stacks, those comprising the 85% best-seeing images (D85) and those comprising the 25% best seeing images (D25).

The internal astrometric errors of the stacks are between 1/15 and 1/3 of pixel, in x and y . The external astrometric errors are between 0.20'' and 0.27'', and is limited by the reference catalogue accuracy. The astrometric offsets between the CFHTLS and the astrometric reference catalogue are negligible. They are smaller than $\pm 1/10$ of pixel in both axes and for all fields. Photometric errors have been estimated for all stacks using several independent methods. Based on comparisons with SDSS-DR8, we find that our absolute photometric accuracy is 1.5 % u^* and 1.0 % for all other bands.

In total there are 48 Deep stacks corresponding to u^*griy and z bands, 12 for each field. There are 855 Wide stacks, in u^*griy and z bands or 360, 125, 245, 125 for W1-W4. Over the 171 fields of the Wide, 141 are covered in i -band and only 30 in y .

For each stack catalogues have been produced using a gri -selected “chi2” as a detection image and an associated mask. These data sets are complemented by a series of *merged catalogues* that combine information for each source in all filters into one file in addition to many different types of quality control data (tables, plots, figures). In addition to the merged catalogues for each tile and for the four deep fields, four single merged “patch” catalogues are provided for each of the four Wide patches. Sources for overlapping tiles have been dealt with correctly and the parent tile information is recorded for each source. Aperture magnitudes, total magnitudes, and variable-aperture magnitudes (computed from the seeing for each tile) are provided for each source.

For a concise overview of survey, the reader should see Tables 7, 19 and 20. These tables provide all basic data on the survey coverage, seeing, exposure times, depth and completeness, astrometric and photometric errors. This release document is complemented by practical information at the Terapix T0007

¹<http://www.cfht.hawaii.edu/Science/CFHTLS/>

²<http://www.cfht.hawaii.edu/Instruments/Elixir/>




Figure 1: Location of the four Deep and four Wide CFHTLS fields on the sky.

release page xxx and the T0007 “synoptic table”³. All data sets are available directly from TERAPIX. In addition, searchable catalogues are made available the Centre de Données astronomiques de Strasbourg (CDS); in addition, the Canadian Astronomy and Data Center (CADC) provide all individual weight-maps, flat-fielded images, and final stacked tiles. For further information, the TERAPIX team can be contacted at terapix@iap.fr.

For users who prefer to produce their own stacks, a complete set of T0007 configuration files are listed in the Appendix A.2. In addition, a list of each images used in each Wide stack is given in Table 33. In addition weight maps and astrometric solution files are provided for each individual image. (The lists of images selected in each Deep stack can be supplied on request.) All T0007 data products are immediately available. Photometric redshifts are made available in separate release.

The CFHT, in collaboration with the CEA, has provided excellent MegaPrime/MegaCam support, ensuring the steady collection of data of uniform quality. CFHT’s provided data pre-processing and calibration (Elixir) and distribution (DADS). Overall survey integrity has been ensured by the CFHTLS Steering Group and oversight by CFHT Science Advisory Committee. Data have been archived and distributed by CADC. It is important these efforts be acknowledged in all works using the CFHTLS data. Following recommendations of the CFHT Director and the CFHT Board the following acknowledgement should be part of any publication using CFHTLS data:

“Based on observations obtained with MegaPrime/MegaCam, a joint project of CFHT and CEA/DAPNIA, at the Canada-France-Hawaii Telescope (CFHT) which is operated by the National Research Council (NRC) of Canada, the Institut National des Sciences de l’Univers of the Centre National de la Recherche Scientifique (CNRS) of France, and the University of Hawaii. This work is based in part on data products produced at TERAPIX and the Canadian Astronomy Data Centre as part of the Canada-France-Hawaii Telescope Legacy Survey, a collaborative project of NRC and CNRS.”

³http://terapix.iap.fr/cplt/T0007/table_syn_T0007.html

2 New features in T0007

The main focus of the T0007 release has been to improve the absolute and internal photometric calibration of the survey. This has been done by applying recipes adopted by the Supernova Legacy Survey Team (SNLS) for the deep fields to both the Deep and Wide fields of the CFHTLS. These recipes were used to generate a new set of flat-fields (known as “Elixir B5”) which have been used to re-preprocess all CFHTLS data. Consequently, for T0007 all individual weight-maps and object catalogues have been re-generated.

A new series of photometric calibration observations (“L99”) have been taken which “pave” the whole of the CFHTLS wide fields and which were bracketed by observations of SNLS tertiary standards fields (the deep survey fields). These observations allow the SNSLS deep field tertiary standards to be used for both the deep and wide-field core survey photometric calibration. The overall effect of these changes is that in *griz* bands, the absolute photometric calibration over the entire survey is at the 1% level or better.

For T0007 processing at Terapix several key have been revised or improved:

- A robust system has been implemented to correctly flag saturated objects at all stages of processing;
- For the deep fields, two sets of stacks are now provided, one generated using a sigma-clipped combination algorithm (which results in slightly higher signal-to-noise in the final stack) and one using a standard median-combination;
- In the merged catalogues, object flags have been revised and now provide information on object classification (star/galaxy), saturation and masking (in all bands);
- New seeing-scaled aperture magnitudes are **MAG_SNLS** and **MAG_IQ20** are provided;
- Finally, for each of the four Wide patches, merged catalogues have been generated which contain all unique objects (overlapping objects from adjacent tiles are correctly dealt with) have been generated.

Finally, ’holes’ in the CFHTLS wide survey created by partial CCD failures have been filled from additional observations taken during CFHT director’s discretionary time.

Taken together, these changes represent a significant improvement in the scientific potential of T0007 compared to previous releases.

Contents

1	Summary	ii
2	New features in T0007	iv
3	T0007 processing description	1
3.1	A note on CCD numbering and nomenclature	1
3.2	Detrending and CFHT pre-processing	1
3.3	Overview of T0007 processing at Terapix	3
3.4	Image evaluation and pre-selection	4
3.5	Astrometric calibration and initial photometric rescaling	6
3.6	Photometric calibration	9
3.6.1	Overview	9
3.6.2	Choice of magnitude measurement method for calibration	11
3.6.3	Measurement of IQ20 magnitudes	14
3.6.4	Quantifying the improvements using MAG_IQ20 compared to MAG_SNLS	15
3.6.5	SNLS standard star catalogue	16
3.6.6	Calibrating the Deep survey	16
3.6.7	Photometric calibration of the Wide survey	18
3.6.8	Vega-AB conversion	21
3.7	Production of the Wide and Deep stacks	22
3.8	Final catalogue production	22
3.9	Post-processing and quality control	23
4	Description of the CFHTLS T0007 Wide survey	25
4.1	Overview	25
4.2	Seeing and image quality	31
4.3	Depth and completeness limits	39
4.4	Photometric accuracy	40
4.4.1	Internal photometric errors of Wide stacks from simulations	40
4.4.2	Error estimation from overlapping Wide tiles	42
4.4.3	Systematic offsets between CFHTLS and SDSS	47
4.4.4	External photometric errors	53
4.4.5	CFHTLS Wide Photometric precision	53
4.4.6	Stellar color-color plots	54

4.4.7	Colour offsets between CFHTLS and SDSS	54
4.5	Astrometric accuracy	55
4.5.1	Astrometric calibration errors	56
4.5.2	Absolute astrometric accuracy of CFHTLS stacks	57
4.6	Outliers, stacks with exceptions or anomalies	59
5	Description of the CFHTLS T0007 Deep survey	66
5.1	Overview	66
5.2	Astrometric accuracy	67
5.3	Photometric accuracy	67
5.3.1	Comparison with SDSS	67
5.3.2	Internal photometric errors	73
5.4	Depth and completeness limits	76
6	Data products	80
6.1	Data set	80
6.2	Data types and file naming conventions	82
6.3	Content of CFHTLS source catalogues	87
6.4	The QualityFITS input and output products	93
6.5	Transfer to CADC and CDS(**tbd**)and data integrity check	98
7	Acknowledgements	99
A	CFHTLS T0007 Wide supplementary information	100
A.1	Complete list of wide stack coordinates, filters and exposure time	100
A.2	List of images in each Wide stack	103
A.3	CFHTLS T0007 Wide configuration files	118
A.3.1	SCAMP configuration files for T0007 Wide	118
A.3.2	SCAMP internal astrometric reference catalogue run (W1) :	118
A.3.3	S _{Warp} stack configuration file for T0007 Wide	126
A.3.4	S _{Warp} chi2-image configuration file for T0007 Wide	128
A.3.5	SExtractor .ldac catalogue configuration file for T0007 Wide	130
A.3.6	SExtractor DUAL MODE .cat catalogue configuration file for T0007 Wide	132
B	CFHTLS T0007 Deep supplementary information	135
B.1	SCAMP configuration files for T0007 Deep	135

B.1.1	S Warp stack configuration file for T0007 Deep	141
B.1.2	S Warp chi2-image configuration file for T0007 Deep	143
B.1.3	SExtractor .ldac catalogue configuration file for T0007 Deep	145
B.1.4	SExtractor DUAL MODE .cat catalogue configuration file for T0007 Deep	147

List of Figures

1	Location of the four Deep and four Wide CFHTLS fields on the sky.	iii
2	MegaCam readout layout and CEA-CFHT CCD numbering convention used in this report	1
3	Flow chart of the Terapix data processing pipeline for T0007.	5
4	The <i>youpi-QualityFITS</i> grading interface.	7
5	SCAMP photometric rescaling diagnostic plots	10
6	SCAMP photometric rescaling diagnostic plots (cont'd)	11
7	CFHTLS T0007 absolute photometric calibration	12
8	Distribution of the Seeing of the L99 images and the CFHTLS Wide stacks	12
9	Growth curve of the PSF models in the L99 r-band images	13
10	Aperture correction dependance with image quality	14
11	PSF shape in excellent and average seeing images	15
12	PSF models in the four quadrants of a CFHTLS Wide stack	16
13	Flowchart of the calibration of the CFHTLS-Deep images	17
14	Automatic determination of the saturation level	17
15	Deep photometric calibration using SNLS standard stars	18
16	Flowchart of the calibration of the CFHTLS Wide stacks	19
17	Matching L99 and CFHTLS-Wide objects	20
18	Positions and geometry of the CFHTLS Wide fields.	26
19	Positions, identification and naming conventions of stacks in the CFHTLS Wide survey. .	27
20	CFHTLS Wide pointings and dithering strategy.	29
21	W1 VIPERS-DT field coverage.	31
22	Distribution of exposure times over the Wide fields.	34
23	Seeing FWHM mapped over the input <i>i</i> -band image <i>743065p.fits</i> by QualityFITS-in	35
24	Distribution of the median seeing over the Wide tiles.	36
25	Maps of seeing (FWHM) in the cfhtls Wide.	37
26	PSF variations as function of the position and wavelength on MegaCam exposures . . .	38
27	Example completeness calculation for a W3 tile	39
28	Left panel: overall distribution of completeness on the wide fields. Right panel: completeness limit of Wide stacks as function of exposure time. A trend of increasing depth with increasing observing time is apparent. There is however a broad spread in depths at a given exposure time. due to other factors such as image quality, sky and weather conditions. The depth of some <i>z</i> -band stacks is also reduced by persistent residuals from the fringe subtraction.	41
29	Distribution of completeness	41

30	Left and right panels respectively: Stellar and extended-source completeness limit of Wide stacks as function of seeing FWHM. As expected, the point source completeness is a clear function of the image quality: the better the seeing, the deeper the image.	42
31	80% completeness limits maps in W1, W2, W3 and W4	43
32	Galaxy counts for the four wide patches in all bands.	44
33	Analysis of the internal photometric errors in CFHTLS_W_g_020241-041200_T0007 using simulations.	45
34	Analysis of the internal photometric errors in using stacks overlapping regions.	49
35	Distributions of photometric offsets, $\delta_{m=u^*,g,r,i/y,z}$, between CFHTLS Wide and SDSS for W1, W2, W3 and W4.	50
36	Maps of photometric offsets between CFHTLS Wide and SDSS R8.	52
37	Comaprison of one CFHTLS field with the Pickles stellar library (lower panel) and the Basel 3.1 stellar library using [Fe/H]=-1.0 (upper panel).	55
38	Mean RA-DEC offsets between the CFHTLS W1 and the 2MASS catalogues	60
39	Mean RA-DEC offsets between the CFHTLS W2 and the 2MASS catalogues (see comments on the caption of Fig. 38).	61
40	Mean RA-DEC offsets between the CFHTLS W3 and the 2MASS catalogues (see comments on the caption of Fig. 38).	62
41	Mean RA-DEC offsets between the CFHTLS W4 and the 2MASS catalogues (see comments on the caption of Fig. 38).	63
42	Comparison of the $(u^* - g)/(g - r)$ and $(g - r)/(r - i)$ stellar color-color tracks of the four Deep Dk-85 fields.	72
43	Estimation of the internal photometric accuracy in Deep stacks.	74
44	Weightmap images of the D2 field.	76
45	Locations of u^* -band pointings used to produced the D2- u^* stack.	77
46	Galaxy counts for the deep, sigma-weighted stacks in all bands for each of the four fields. The dotted lines show the 85% completeness for galaxies described in Section 5.4.	79
47	QFITS-out page of the W4 CFHTLS_W_i_222054+002300 stack.	95
48	QFITS-out page of the same field (cont'd).	96
49	QFITS-out page of the same field (cont'd).	97

List of Tables

1	Influence of the Aperture correction of the zeropoint calibration of the Deep-L99 exposures.	15
2	Deep images rescaling factors	18
3	AB offsets relative to tge SNLS3 calibration of MegaCam.	22
4	Overview of the CFHTLS Wide fields.	28
5	Mean properties of the CFHTLS Wide survey.	28
6	Description of the additional VIPERS-DT images.	30
7	Summary of the W1, W2, W3 and W4 mean survey parameters.	32
8	Summary of the W1, W2, W3 and W4 area covered by the survey in deg^2 ($arcmin^2$).	33
9	Internal photometric errors per magnitude bins derived for each CFHTLS Wide field.	46
10	Internal photometric errors derived from overlapping Wide survey tiles	47
11	Internal photometric errors per magnitude bins derived for each CFHTLS Wide field.	48
12	Mean/Median magnitude offsets, $\langle \Delta_{m=u^*,g,r,i/y,z} \rangle$, between the CFHTLS and the SDSS R8 surveys	51
13	External <i>rms</i> errors of the CFHTLS T0007 u^*i, g, r, i and z -band Wide surveys.	53
14	Mean RA and DEC differences between the external errors in each field and the mean external errors, averaged over the four Wide fields.	56
15	Mean astrometric position accuracy of each Wide stack. The Wide-averaged statistics is the ensemble average over all stacks of the mean CFHTLS-SDSS astrometric offset values computed for each stack (MegaCam mean), separately	58
16	CFHTLS Wide stacks with exceptions or anomalies.	64
17	CFHTLS Wide stacks with exceptions or anomalies (cont'd).	65
18	Overview of the CFHTLS Deep fields.	66
19	Summary of the 25% best-seeing stack parameters.	68
20	Summary of the 85% deep stack parameters.	69
21	Summary of the 25% best-seeing sigma-weighted stacks.	70
22	Summary of the 85% best seeing sigma-combined stacks.	71
23	Analysis of the internal photometric errors in the CFHTLS T0006 Deep data from the comparison of source pairs in D-25 and D-85.	75
24	Mosaicing of D-25- u^* and D-85- u^* stacks.	78
25	CFHTLS files, point-of-access and naming convention.	83
26	CFHTLS files, point-of-access and naming conventions (cont'd).	84
27	CFHTLS files, point-of-access and naming conventions (cont'd).	85
28	CFHTLS files, point-of-access and naming conventions (cont'd).	86
29	Description of parameters listed in T0007 catalogues.	90

30	Description of parameters listed in T0007 catalogues (cond't).	91
31	Description of parameters listed in T0007 catalogues (cont'd).	92
32	The CFHTLS T0007 Wide stacks coordinates, filters and exposure time.	100
33	Full list of CFHTLS input images included in each Wide stack	103




Figure 2: MegaCam readout layout and CEA-CFHT CCD numbering convention used in this report. Each rectangle represents a MegaCam CCD. When mounted on MegaPrime, North is at the top, East to the left and each CCD covers a field of view of about $7' \times 14'$. The dotted lines separate the two 1/2 CCDs read by each amplifier of a detector. The positions of the two amplifiers are indicated by A or B. Note the organisation of MegaCam into two sub-mosaics. They are separated by a large horizontal gap of $82''$ width.

3 T0007 processing description

3.1 A note on CCD numbering and nomenclature

In what follows, the naming of MegaCam CCDs follows the CEA-CFHT naming convention. The camera is composed of 36 CCDs numbered from CCD#00 to CCD#35 (Boulade et al., 2000). CCD#00 is at top-left (extreme North-East position) and numbers increase from left to right and top to bottom. When 1/2 missing CCDs are reported it means that one of the MegaCam output amplifiers did not work. In that case a 1/2-size CCD rectangle, as drawn in Fig. 2 has no data. These failures are very rare, representing less than 0.3% of the data and are listed on the MegaPrime failures page⁴.

These failures demand special handling in the pipeline, but they have almost no impact on the science. In this document a “MegaCam pointing”, or a “tile” denotes a $1 \times 1 \text{ deg}^2$ field corresponding to a target position of the Wide survey listed in Table32.

3.2 Detrending and CFHT pre-processing

Removing the instrumental signature from the raw MegaCam frames taken at CFHT under the Queued Service Observing system falls under the responsibility of the Elixir pipeline at CFHT (Magnier & Cuill

⁴<http://www.cfht.hawaii.edu/Instruments/Imaging/MegaPrime/megaprimehistory.html>

landre, 2004). Correcting that signature is called “detrending” in Elixir parlance since it goes beyond what basic pre-processing usually encompasses. The steps involve, in a single pass, applying a bad pixel mask, correcting for the two-dimensional structures of the overscan, subtracting a master bias frame, and applying a flat-field including the illumination correction that makes the photometric zero point uniform across the entire image at the better than 1% level. The i and z images go through an extra step to subtract a scaled master fringe pattern. Finally the images are astrometrically calibrated on a per-CCD basis and photometric zero points information is fed into the final MEF (36 extensions) file based on the observing run global photometric analysis. The following paragraph cover some details of these operations in the context of the T0007 release.

At the end of each MegaCam run, master twilight flat field frames and master fringe frames are built from all the exposures taken during the run, including non-CFHTLS data (which represents about half of the total dataset over the acquisition phase of the survey, 2003-2009). Elixir builds master flat-fields for each filter by stacking the individual twilight flat-field frames. Individual frames inadvertently contaminated by clouds or nearby moon light are rejected. They are identified by dividing each individual flat field exposure by the master flat, and inspecting the result visually. Typically, no more than one iteration is needed to reject the outliers and ensure consistent quality of this key calibration frame. In order to mitigate possible non-linearity residuals at the sub-percent level, individual flat field images are acquired in the 10,000 to 15,000 ADU range. After two weeks, the typical length for a MegaCam run, there are typically 40 to 60 usable frames that can be stacked into a final normalized frame equivalent to a single 400,000 ADU counts per pixels, reducing photon noise to negligible levels.

If one measures the photometry of the same star on an image flat-fielded from the twilight flat-fields, the flux varies by about 15% in the u band and 10% in the g -, r -, i -, and z -bands when moving the star from center to edges of the field of view. The variation is monotonic and essentially follows a circular pattern. It is caused by scattered light in the optics (a combination of indirect illumination and light reflections) and the inherent geometrical distortion of the image. A photometric flat-field, which ought to deliver uniform photometry across the field of view is then created by multiplying the master flat-field frame by the maps of the imager photometric response non-uniformities. This composite flat-field is the one used for flattening the science images of the entire run, and allows for all multiplicative effects in the image to be corrected at once.

The data released by CFHT for the six previous TERAPIX releases of the CFHTLS were based on photometric flat-fields which were affected by 4% peak-to-peak residuals. While this was adequate for most science goals of the CFHTLS, it was not satisfactory for the SuperNova Legacy Survey (Astier et al., 2006). As a consequence, the SNLS team and CFHT have collaborated since 2004 realise precision photometric measurements using MegaCam. The effort was instrumental in unlocking the potential of the SNLS survey (Regnault et al. (2009), Betoule et al, in preparation).

This new recipe makes possible better than 1% peak-to-peak residuals within an image in all filters. This Elixir recipe version is named “B5”(or “B5/SNLS” in reference to its origins). All individual Elixir processed frames, available at CADC, used to build the TERAPIX T0007 release have a header indicating the photometric recipe used (in general the newly processed images have Elixir version 3.0 or higher).

Fringe patterns are built by processing all i and z -band images corrected by the final flat-field. First the sky background is mapped at a large scale (100 pixels) and subtracted. Then, the exposures are scaled according to the fringe amplitudes measured on one hundred peak-valley pairs on each CCD. Since all CCDs see the same sky, a single scaling factor is derived from the 36 CCDs. The scaled exposures are stacked, and an iterative process similar to the one described above is carried out, with a visual control

allowing the rejection of frames containing extended astrophysical sources such as large galaxies. The fringe correction is challenging at times in the z -band and some images get only partially corrected due to the extreme behavior of the OH emission lines in the upper atmosphere which cause a signature too different from the run master fringe frame. (A different observing strategy such as the one adopted for the MegaCam Next Generation Virgo Survey (2009-2013) would have helped tremendously but was not available during CFHTLS observations.) Consequently the defringing recipe is unchanged for the T0007 data collection. All fringe patterns were however re-created since they must include the signature of the new photometric B5/SNLS flat-fields.

After these de-trending steps, Elixir processes all the images of the run, and derives an astrometric solution per CCD only, at the pixel scale level ($0.2''$). The goal at the Elixir level is to provide the users with a first order astrometric solution and no global solution over the mosaic is computed; this is a task handled by TERAPIX.

Following this step, all the frames containing Smith et al. (2002) photometric standards (the CFHT QSO “Q97” program) are identified and processed using **SExtractor**. A median zero-point for the entire run is derived for each filter, since not enough observing time is available to derive enough standard star observations per night to derive solid zero-point solutions. Again, the intention is to provide MegaCam users with a reliable photometric scaling, offering a precision at the 4% level in absolute. Since this default calibration was clearly not precise enough for the SNLS needs, the team developed in collaboration with CFHT new procedures to calibrate the images. This vast undertaking is the key to major improvements in T0007 major leap over T0006: all knowledge acquired for the SNLS survey has been passed to the Deep and the Wide survey. This calibration effort is described in detail in Section 3.6.

3.3 Overview of T0007 processing at Terapix

Our processing steps from the download of pre-processed CFHT images to the final stacked images and catalogues is illustrated in Fig. 3. The T0007 CFHTLS Elixir pre-processed images described in the previous section were transferred from CFHT and validated against the T0007 image lists. All queue observation flags archived at CFHT were also downloaded⁵.

For the T0007 release we use Elixir “B5” pre-reduced images. The images were first ingested and with the Terapix processing pipeline **Youpi**, producing weight-maps and input catalogues. We use quality grades from previous CFHTLS releases for images which were already in the database; new images from the “L99” photometric calibration program and the VIPERS directors discretionary time observations (described later) were graded using the **Youpi** grading interface, described below.

Images were then divided into each of the four Wide and four Deep fields and processed with **SCAMP** (Bertin, 2006) in order to derive the astrometric as well as the initial photometric calibrations. As explained below, as a consequence of the new calibration scheme based on L99 images, the astrometric and photometric calibrations were performed separately.

Once aligned astrometrically, images are co-added by **SWARP** (Bertin et al., 2002) using the **SCAMP** initial photometric rescaling. For the deep field, images lists are derived using seeing and photometric rescaling constraints. Two series of Deep stacks are produced using two images combination schemes: median and sigma-clipped, denoted throughout the current document as “MEDIAN” and “SIGWEI” stacks.

Because of the inherent limits in using a photometric calibration derived solely from the pre-existing CFHT survey photometric calibration (lists of observations previously flagged as photometric by the

⁵<http://www.cfht.hawaii.edu/Science/CFHTLS-DATA>

CFHT and photometric header calibration written by Elixir) in T007 we use a different approach to calibrating the survey. Both deep and wide stacks are tied to the SNLS photometric system using photometric standards which lie within the CFHTLS deep field (Regnault et al., 2009). For the deep fields, which contain the deep field calibrators, we can rescale images directly to the SNLS system, whereas for the CFHTLS Wide fields we use L99 short photometric exposures which are bracketed by observation of the deep fields containing the calibrators. These L99 observations are then used to rescale the Wide tiles. The original SNLS Vega photometric system is finally converted to the natural AB system which has been used in previous CFHTLS releases.

Several types of final catalogues are produced: individual catalogues for each image, merged catalogs with all filters for each tile, Wide-patch merged catalog (all tiles in all filters for each Wide patch). The objects are flagged according to the potential saturation in each filter and location in masked regions, object type (star or galaxy).

3.4 Image evaluation and pre-selection

In the first QualityFITS step (“QFTIS-in”), all individual CFHTLS input images are used to produce an input .1dac source catalogue (these are FITS binary tables containing an additional table derived from FITS header keywords present in the input images). This catalogue is used first for image quality assessment and subsequently in the astrometric and photometric calibration. QualityFITS also creates for each image a “confidence map” or weight-map image, which corresponds to the relative inverse variance of each pixel. This weight is derived from the flat-field and mask images produced by the ELIXIR pipeline (Magnier & Cuillandre, 2004) at CFHT. This weight map is also used during image combination.

Saturated pixels are also flagged. This saturation cut is much lower than the CCD limit provided in the FITS header (SATURATE FITS keyword) to remove all bright stars and enable star-galaxy separation. During this step we discovered a previously overlooked problem: for some images the analog-to-digital converter (ADC) encoding was set at 15 bits in one bank of the MegaCam CCD#27 → CCD#35 versus the normal 16 bits⁶. This resulted in different saturation levels across the MegaCam mosaic (32000 instead of 64000). We have modified the .1dac catalogues of the affected exposures outside QFTIS-in with a proper flagging of the two-level saturation without rejecting too many bright sources which are essential for photometric calibration.

After QFTIS-in, images are visually inspected and evaluated through the Youpi Youpi image evaluation interface⁷. For T0007, grades were preserved from previous survey releases, and only new images were graded. For each image, Youpi provides a link to a QFITS-in web page which summarises properties of each image. All QFITS-ed images are then graded “A”, “B” or “C”, after a visual inspection of each page (see Fig. 4), paying in particular special attention to the PSF and the seeing over the MegaCam field. Images with grade C are not within the CFHTLS specifications or show serious problems (such as missing CCDs or extensive scattered light over the whole MegaCam field, or obvious telescope guiding problems). “Grade B” represents acceptable images, within the specifications, but for which QFTIS-in revealed minor problems (such as unusual galaxy or stellar counts, or seeing values very close to the upper limit). The grading step is applied to all images having the “validated” flag produced by CFHT.

Based on the QualityFITS selection a initial selection of images is made by applying the following criteria:

⁶The problem was present during two observing runs in the winter 2004 before it was identified and corrected by CFHT. The source of this was a faulty video board which was subsequently replaced.

⁷<http://youpi.terapix.fr>




Figure 3: Flow chart of the TERAPIX data processing pipeline for T0007.

- Terapix class: A or B grades;
- Exposure time longer than 60 seconds ;
- FWHM less than $1.3''$, except for u^* ($< 1.4''$) ;
- Airmass less than 1.7;

Rejected images are removed from the processing pipeline. In subsequent steps, the QFITS-in catalogues of the remaining sample are used to derive the astrometric and photometric calibrations.

The images used in the Wide survey are essentially these images, except that in certain stacks with missing detectors, they are supplemented by supplementary observations already mentioned.

The selection of images used in the T0007 CFHTLS Deep survey starts from a pre-defined set of 85% best-seeing images which has been created in previous releases. It was verified that the seeing on these images (measured using a fit to the PSF with a Moffat function in PSFEx) was less than $1.1''$ in u^* and less than $1.0''$ in all other bands. In addition, any image which had a field-to-field photometric rescaling (explained in the next section) which was larger than 0.15 mag was also rejected. The resulting list corresponds to our “85%” list. For simplicity, the 25%-best seeing images were constructed from the 25% best seeing images *drawn from this list*. We verified that the effect of creating a list from the “best 25%” of all images, compared to the best seeing of 85% of the images, has minimal effect on the completeness of the final stacks.

3.5 Astrometric calibration and initial photometric rescaling

The T0007 astrometric solutions and the initial photometric calibration were computed using `Scamp`. The configuration files which were used are presented in Appendix A.3.1.

`Scamp` first reads all image headers and then splits the exposures into a series of astrometric “contexts”. Each context isolates blocks of observing epochs where the instrument focal plane is in a fixed and (mostly) stable position; for the CFHTLS these contexts can be selected using the CFHT QRUNID FITS header keyword. Special care is taken to correctly flag saturated objects in particular for images for which saturation levels change significantly across the mosaic (described in Section 3.4).

An approximate first-guess for the position of astrometric sources is derived by the cross-identification of sources in the QFITS-in .1dac catalogues with the 2MASS external reference catalogue (Skrutskie et al., 2006). As in previous releases, 2MASS was chosen because astrometric solutions were stable and more accurate than using the USNO. (We note that ultimately an SDSS-based calibration would have been preferable because of the higher surface density of sources in SDSS and the similarity of SDSS and CFHTLS filter sets; however the SDSS does not cover the whole CFHTLS survey; only W3 and D2 and D3 fields have complete coverage.)

To match CFHTLS and 2MASS catalogues we choose a source matching radius (CROSSID_RADIUS) of 2.0 arcsec for all Wide and Deep fields. A 3rd order polynomial distortion model is then derived by minimising a weighted quadratic sum of differences in positions between the 2MASS and the QFITS-in matched sources, and, internally, between different QFITS-in catalogues with overlapping regions of MegaCam images (see Fig. 20). `Scamp` then computes the astrometric internal errors from the differences of astrometric positions of sources inside the overlapping regions and the external errors from the comparisons of astrometric positions of MegaCam sources with the 2MASS catalogue.

History Statistics Advanced Search

Processing History

20 0 (20/15445)

Show all finished First Quality Evaluation processes

Show all images

Reset Start searching!

Page 1 2 3 4 5 6 7 ... 752 > page 1

15033 of 15033 images already graded

- First Quality Evaluation of 765143p
 Graded A
- First Quality Evaluation of 766155p
 Graded B
- First Quality Evaluation of 766153p
 Graded A
- First Quality Evaluation of 756524p
 Graded A
- First Quality Evaluation of 756522p
 Graded A
- First Quality Evaluation of 756520p
 Graded A

QualityFITS-In processing - 765143p.fits

2009-08-06 18:56:13
2009-08-06 19:18:30
0:22:17 on fcix2.clic.iap.fr

Job initiated by goranova
Exit status: SUCCESS A ★★★★ goranova

See full QFits web page

USER PERMISSIONS

goranova/Terapiax rw-r----- (640)

CONDOR JOB LOGS

Cluster Id: 1144.0 Condor out: --
Condor log: --
Condor error: --

QUALITYFITS-IN PROCESSING HISTORY (1)

Grade (x1)	Date	Host	User	Action
Graded A	2009-08-06 18:56:13 (0:22:17)	fcix2.clic.iap.fr	goranova	(Reprocess)

QUALITYFITS RUN PARAMETERS

Image: /data/fci4/raid/T0005-Tpx/release/01-data/images/dif765143p.fits
Flat: /data/fci5/raid11youpi-INPUT/CFHTLS/T0006-WideAll/flat/
Mask: /data/fci5/raid11youpi-INPUT/CFHTLS/T0006-WideAll/Mask/
Reg: --
Results output dir: /data/fci5/raid2/youpi-OUTPUT/PROD/goranova/fitsin/D1-ext/

IMAGE INFORMATION

Object: D1	Rund: 04BL01	Filter: i.MP9701
ExpTime: 360.1	Ingestion Date: 2008-09-28 21:13:17	Air Mass: 1.140
Phot_c header: .	Phot_c (custom): .	RA: 36.50612500
Dec: -4.49111100	UTC obs: 2004-10-09 00:00:00	Telescope: CFHT
Instrument: MEGACAM		

QUALITYFITS INFORMATION

RA offset: .	Dec offset: .	RA std dev: .
Saturation level: 50000.0000 ADU	Median background: .	Min PSF FWHM: 2.781 arcsec
Max PSF FWHM: 3.700 arcsec	Min PSF half-light diameter: .	Avg PSF half-light diameter: .
Min PSF elongation: 1.02	Avg PSF elongation: 1.21	Max PSF elongation: 1.46
Avg PSF chi2/d.o.f: 1.92	Max PSF chi2/d.o.f: 3.05	Min PSF chi2/d.o.f: 1.41
Max PSF residuals: 0.08	Min PSF asymmetry: .	Avg PSF residuals: 0.04
Min number of PSF stars: 48	Avg number of PSF stars: 60	Max PSF asymmetry: .
Previous Release Qfits-in Comment: .		Previous Release Qfits-in Grade: .

Toggle QFits config file view

Toggle QFits results ingestion log view

Previous Release Grade: Grading history (1): Your grade:
No Grade. ★★★★ A 2009-08-06 19:46:03 goranova
Comment unknown.

Your comment:
Grade: A ★★★★
Predefined: ---
Custom: []




Figure 4: The youpi-QualityFITS grading interface. The top panels show the youpi-QualityFITS main page which displays the status of QualityFITS evaluations of all images (left), and the QualityFITS evaluation of a user-selected image (right). On the top right panel the grading status for the selected image is displayed. In this case the QualityFITS page (bottom panel) is loaded by youpi and options to grade a new image or to update the grade of an image are displayed. Users can then examine the data shown on Fig. 47 to 49. The grading interface minimises the number of actions required to only three clicks per image. The youpi database preserves the evaluation history of all images and so it also archives the grades from previous releases. For the T0007 release, only new images have been graded.

Images are calibrated separately for each of the four Wide and four Deep fields. However, in order to take full advantage of L99 photometric images, processing is done in two steps:

- **Astrometric calibration** – this includes all types of images: science images, short and L99 photometric calibration images, astrometric anchor pre-survey exposures and supplementary VIPERS-DT (discretionary time) exposures for filling missing half-CCDs in W1.
- **Initial photometric rescaling** – this includes only science images and photometric bootstrapping (Q98) images and it uses the astrometric solution from the previous step. The primary goal of this step is to compute the relative rescaling of the individual images in each pointing before stacking. The absolute photometry is then anchored to the L99 exposures (see the procedure described in Section 3.6).

In addition, due to the large number of exposures in some of the fields the astrometric calibrations cannot be solved globally (due to memory requirements) and are additionally split by filter. For those fields the number of observing runs produces too many astrometric contexts which cannot be handled by `Scamp` using current TERAPIX computing resources. For this reason, the astrometric calibration is computed in a field-dependent way.

For the W1 field, for which the astrometric solution is derived with respect to a reference catalogue we use this procedure:

- We first combine $(r, i/y)$.1dac catalogues of the science exposures as well as the r -band Pre-Wide astrometric anchoring images and find an astrometric solution using the 2MASS reference catalogue and use this to produce an internal $(r, i/y)$ astrometric reference catalogue, calibrated with 2MASS;
- We then run `Scamp` on all W1 exposures using this internal reference catalogue on the (u, g) , (r, z) , and (i/y) samples separately. The homogeneity and consistency of the calibrations are ensured by the common r -band Pre-Wide data used for all samples.

For W2, W3 and W4 fields, the astrometric solution is calculated once for each field by considering all selected images simultaneously, regardless the filter, exposure type or epoch, using 2MASS. In this way all images of a given Wide field are calibrated globally and in a homogeneous way.

All Deep fields are calibrated with SCAMP in a similar way as W1. However, the image selection used to construct the internal reference catalogue is done differently:

- First a sub-set of only two images per QRUNID is drawn from all science r, i, y -band exposures and supplemented with a set of all i -band astrometric anchoring fields surrounding the deep pointing for D2, D3, and D4, and a sub-sample of W1 surrounding exposures for D1. The additional data sets are spread over many different observing periods and sample all QRUNIDs. As in W1, this internal reference catalogus are calibrated with respect to 2MASS;
- The astrometric solution for each filter is then calculated separately using the internal reference catalogue. The precision of the internal astrometric solution is assured by the common i -band astrometric anchoring exposures. In addition, due to the compact areas on the sky from which the Deep samples are drawn, the CROSSID_RADIUS for this step is reduced to 0.5 arcsec.

The astrometric solution for the Deep fields is derived using the same recipe for each field, thus improving the consistency of the calibrations between the four Deep fields.

Astrometric solutions have been verified by examining the large range of check-plots produced by `Scamp`, in particular the 1D and 2D internal and external astrometric solutions as a function of RA and DEC, the reduced chi-squared for the astrometric solution, and the field-to-field photometric offset. After an acceptable solution is calculated, this astrometric solution is written in a separate `.head` file for each input image.

In T0007, the initial photometric field-to-field rescaling is computed separately from the astrometric solution. Photometric flags are written in the `.ahead` files together with the new zero point provided by CFHT and derived from the astrometric solution computed in the previous step. As for the astrometric calibration, `Scamp` minimizes the quadratic sum of magnitudes using the overlapping regions between images. It then re-scales the flux of non photometric images accordingly (Fig. 5 and Fig. 6). After this step a “final” photometric rescaling is computed for each of the image tiles; this is described in detail in Section 3.6.

Finally, these astrometric and photometric solutions are combined into a single output `.head` file for each image (containing information for all of the 36 MegaCam extensions) which is then used for producing the Wide and Deep stacks using SWARP. All `SCAMP` output data including `.xml` tables, diagnostic plots, `.ahead` and `.head` files can be found in the T0007 synoptic table.

3.6 Photometric calibration

3.6.1 Overview

CFHTLS T0007 photometry is anchored to the SNLS photometric system (Regnault et al., 2009) using a catalogue of tertiary standard stars supplied in this paper. The method to tie the CFHTLS to the SNLS reference system follows the method described in Regnault et al.:

- First the fluxes of the SNLS tertiary standard stars used as calibrators are measured using the same photometric technique used to estimate the flux for science objects;
- Secondly zero-points are derived for each image by comparing the instrumental magnitudes of the tertiary standards with the calibrated magnitudes (appendix E);
- Lastly, the local “natural” magnitudes can be obtained by applying these zero-points to the science objects’ instrumental magnitudes.

The calibration process is different for the Wide and the Deep surveys.

The Deep stacks can be calibrated directly using SNLS tertiary standards inside the Deep fields. Zero-points can therefore be computed by comparing the instrumental magnitudes of the SNLS standard stars to the calibrated magnitudes published in Regnault et al..

However, as there is no complete coverage of SNLS tertiary standards within the Wide fields, a special set of observations (“L99”) were made. These observations comprise a sparse series of short exposures taken during photometrically stable conditions and completely cover the Wide patches.

Each Wide tile is covered by at least one L99 exposure which covers 25% of the MegaCam field of view. Additionally, each L99 observation is preceded and followed by an observation of a CFHTLS Deep field containing the SNLS tertiary standards.




Figure 5: Outputs of the SCAMP calibration process of the W4 field (cont'd). Photometric rescaling and calibration of W4 images.




Figure 6: Outputs of the SCAMP calibration process of the W4 field (cont'd). Internal photometric error as function of magnitudes of W4 images.

The photometric measurement method used to calibrate the Deep exposures taken before and after L99 observations follows the same procedure used for CFHTLS Deep stacks described above. The stable photometric conditions allows this zero-point to be used for the corresponding L99 exposures. In the last step, L99 images are used compute rescaling factors which can be applied to the CFHTLS Wide stacks thanks to the large overlaps (at least 25% of a MegaCam field-of-view).

3.6.2 Choice of magnitude measurement method for calibration

In general, in any photometric calibration process, the method used to measure fluxes of the calibrating sources should be identical to the method used to measure the flux of the science objects. It is challenging to follow this procedure precisely in the case of Regnault et al. for several reasons, none the least is that CFHTLS is a public survey which addresses many different science objectives, ranging from foreground stars to unresolved galaxies. In some cases, total magnitudes are important; in others, galaxy colours must be accurately measured. Ideally, the calibration process should introduce the smallest possible bias which should be documented and allow users to correct for this bias based on the kind of flux measurement they wish to perform.

A second important consideration comes from the intermediate step used to calibrate the CFHTLS Wide survey. The intermediate L99 photometric images have significantly different characteristics compared to the Wide stacks, as can be seen in Figure 8 which shows the distribution of seeing in L99 calibration images and in actual CFHTLS-wide images; the distribution of image seeing is quite different between the two kinds of images, with very large maximum values reported in the L99 stacks. Moreover, the exposure times are much shorter in the calibration images. The method chosen to measure magnitudes scheme should be insensitive to these kinds of variations in exposure time and image quality.




Figure 7: CFHTLS T0007 absolute photometric calibration. For the Deep fields, the calibration of the photometric zero-points can be made directly since the SNLS reference stars are inside the images. In the Wide, an intermediate set a photometric images (L99) is needed to apply the SNLS photometry to the stacks.




Figure 8: Seeing FWHM distribution for L99 individual exposures (top) and the CFHTLS-Wide stacks (bottom). In some specific pairs of overlapping images, the difference can reach $0.4''$.




Figure 9: Growth curves for PSF models in the L99 *r*-band exposures using **MAG_SNLS** and **MAG_IQ20** magnitudes to estimate the total magnitudes (left and right panels respectively). Each line corresponds to the difference in magnitude between the total flux and the flux at the stated aperture size (measured as a multiple of the FWHM) for each L99 exposure. When using **MAG_IQ20** the scatter at $40 \times \text{FWHM}$ is considerably reduced (right panel)

Since the calibration is carried out using stars, aperture magnitudes are a natural photometric measurement scheme (and is also fully consistent with the aperture magnitudes scheme used for the SNLS photometric calibration). This is because, in principle, the correction to total flux is the same for all calibrating sources (unlike resolved galaxies which may have vastly differing light profiles).

In this work, as in Regnault et al. we choose aperture magnitudes where the aperture diameter scales with the image seeing:

$$\text{MAG_SNLS} = \text{MAG_APER}(7.5 \times \text{FWHM}) \quad (1)$$

However instead of the factor of 7.5 used by Regnault et al., we choose an aperture 20 times large than seeing, hereafter “**MAG_IQ20**”. This is motivated by the following considerations.

Firstly, in extragalactic astronomy, one of the primary scientific aims of the CFHTLS, the pseudo-total **MAG_AUTO** (Kron, 1980) is the one of the most commonly used estimators of the total flux of galaxies. Ideally, we should use this technique to calibrate our photometry. Unfortunately, our tests have shown that **MAG_AUTO** measurements do not have the level of precision we require for our photometric calibration. But an alternative is to choose (more stable) aperture magnitudes which matches closely the magnitudes measured by **MAG_AUTO**.

This is demonstrated in the right and left panels of Figure 9 which shows “Growth curves” for PSF models in the L99 *r*-band exposures using **MAG_SNLS** and **MAG_IQ20** magnitudes to estimate the total magnitudes (left and right panels respectively). If we consider the “true” total flux as the measurement at $40 \times \text{FWHM}$, the SNLS flux underestimates the total flux by a factor of 3%. However, this is only 0.5% when the **IQ20** aperture is used. Furthermore, the scatter for the total flux derived using SNLS aperture magnitude is more than 3 times larger than with the **IQ20** aperture (5.1 mmag compared to 1.6 mmag).

Secondly, the choice of magnitude measurement scheme is doubly important when using the SNLS tertiary standards to calibrate the (non-overlapping) L99 calibration fields. For this to work, the flux inside the **IQ20** aperture must be as close as possible to a *constant fraction of the total flux of the star* whatever the shape and size of the PSF.




Figure 10: Aperture correction (defined as the magnitude difference between the flux in the SNLS and IQ20 apertures) as a function of image quality. In images of quality worse than 0.7'' the aperture correction is approximately constant; in better-seeing images the aperture correction show a clear trend. More flux falls outside the SNLS aperture in very good seeing images which results in a larger aperture correction.

To test this assumption, we computed an aperture correction (hereafter ApCorr) defined as the magnitude difference between MAG_SNLS and MAG_IQ20. This aperture correction is plotted against the image quality in Figure 10. It is important to note that the behaviour in the regime of very good image quality clearly departs from a constant aperture correction.

For images taken in excellent seeing, the SNLS aperture is too small to capture the same flux ratio to total flux than for larger image quality, which makes the SNLS aperture photometry not reliable for our calibration. Figure 11 shows the shape of the PSF for two different FWHM rebinned to the same size. One can clearly notice that the overall shape is different : a boxy shape at good IQ due to flux in the spikes and a very symmetrical shape at larger IQ. A possible explanation of the behavior of the aperture correction at low FWHM is the flux contained in the spikes which scaled differently than the bulk of the flux of the PSF.

3.6.3 Measurement of IQ20 magnitudes

Computing the flux inside a large aperture of $20 \times \text{FWHM}$ is not a trivial task in stacks where objects may be subject to crowding. To ensure a robust estimation of the IQ20 aperture magnitudes, first a pixel-based model of the PSF is constructed using the PSFEx software (Bertin, 2011) using a large set of stars. From this PSF model (which is produced as a FITS image) the fluxes inside a series of apertures are computed using SExtractor. The aperture correction (ApCorr) is defined as the magnitude difference between the flux inside the SNLS and IQ20 apertures:

$$\text{ApCorr} = -2.5 \times \log_{10} \frac{\text{Flux}(\text{Ap}_{\text{SNLS}})}{\text{Flux}(\text{Ap}_{\text{IQ20}})} \quad (2)$$

Since photometric rescaling from L99 to the CFHTLS stacks is carried out on only 25% of the MegaCam




Figure 11: PSF model from two images with $\text{FWHM} \sim 0.5''$ and $\sim 0.9''$ (right and left panels respectively). Both PSFs have been resampled to a FWHM of 3 pixels. The “good-IQ” PSF has more flux in the “spikes” outside the SNLS aperture.

Filter	u		g		r		i		z	
	-	ApCorr								
D1	0.003	0.002	0.007	0.005	0.006	0.002	0.001	0.001	0.005	0.001
D2	0.002	0.001	0.002	0.002	0.004	0.002	0.001	0.002	0.004	0.002
D3	0.006	0.008	0.014	0.001	0.004	0.001	0.001	0.002	0.000	0.001
D4	0.014	0.007	0.033	0.003	0.015	0.007	0.002	0.000	0.008	0.001

Table 1: Zero-point difference for deep field exposures before and after L99 observations, with and without the application of an aperture correction (left and right columns for each filter, respectively). In every case except D3-u the application the aperture correction reduces the difference.

field of view, a single PSF model is computed for each image quadrant. This approximation is motivated by the small variation of the PSF shape and size across the field of view compared to the (much larger) variations between the L99 images and the stacks.

3.6.4 Quantifying the improvements using **MAG_IQ20** compared to **MAG_SNLS**

Deep fields observations bracket L99 observations. Since L99 observations were taken in photometric conditions, the zero-points derived from the comparison of the instrumental magnitudes and the SNLS tertiary standards catalogs should not change. By comparing the zero-points in these pairs of Deep observations (before and after L99 observations) in Table 1, one can see that the **MAG_IQ20** is a more stable estimator than **MAG_SNLS**. stability improves even for Deep images with identical seeing. This result indicates that the scatter in the aperture correction at a given seeing seen in Figure 10 is captures real information on the varying PSF shape of identical size.

Furthermore, the variation of the aperture correction with the seeing shown in Figure 10 provides additional indication that the SNLS flux is not a valid proxy of the total flux (measured by the **IQ20** aperture photometry) when the images have a large spread in image quality. Finally the full calibration was performed with both magnitudes and the comparison with SDSS reference catalogues show a overall improvement of the field to field scatter of ZZ mag when using **IQ20** over SNLS photometry.




Figure 12: PSF model for the four quadrants of the CFHTLS-Wide stack CFHTLS_W_z_222054-003100_T0007. The circles represent the apertures used for the SNLS and IQ20 magnitudes.

3.6.5 SNLS standard star catalogue

Some words on the iy to i conversion ...

3.6.6 Calibrating the Deep survey

The calibration process for the deep fields is summarised in Figure 13. In the first step, an object catalogue is produced using SExtractor on the Deep images. This catalog is then used to produce a PSF model using PSFEx. The calibration magnitudes MAG_IQ20 are derived from this catalog and the PSF model. Next, saturated objects are flagged and are removed. The diagnostic plots used in this procedure are presented in Figure 14. The algorithm first locates the 45 degrees angled thin stellar branch in the MU_MAX (magnitude of the brightest pixel) against MAG diagram (left plot). The saturation level is identified in the MU_MAX axis from the broadening of the distribution along the MAG direction. The resulting saturation level is also plotted in the FLUX_RADIUS vs MAG scatter plot. This estimator quite robust but can still fail in around 1% of the fields for several reasons (such as heterogeneous seeing due to the stacking of images with different image quality or higher number of objects close to the saturation level which blurs the determination of the saturation limit). For this reason all plots are manually inspected. Finally to ensure the cleanest possible calibrating sample an additional 0.5 magnitude margin subtracted from the MU_MAX magnitude saturation limit.

Sources in the Deep stacks are matched with the SNLS standards using a nearest neighbour procedure with a 2'' matching radius. All stars with a non-zero SExtractor flags are discarded (to avoid blended objects with potentially corrupted photometry). Figure 15 shows the magnitude difference distribution as a function of reference magnitude after matching. The scatter is low, around 2% in average. The 2- σ clipping applied only removes a small fraction of objects (as can be seen in the right panel).




Figure 13: Photometric calibration process of the CFHTLS-Deep stacks and Deep calibration images used for L99.




Figure 14: Diagnostic plots used to determine the saturation level and to flag saturated objects. Blue points represent discarded objects, the green line shows the saturation limit.

Filter	u		g		r		i		y		z	
	D-25	D85	D-25	D85	D-25	D85	D-25	D85	D-25	D85	D-25	D85
D1-MED	0.015	0.016	0.013	0.011	0.026	0.023	0.023	0.032	0.034	0.013	0.015	0.019
D2-MED	0.027	0.005	0.010	0.010	0.021	0.016	0.028	0.032	0.017	0.031	0.019	0.018
D3-MED	0.026	0.026	0.005	0.007	0.012	0.016	0.029	0.021	0.016	0.020	0.010	0.011
D4-MED	-0.003	0.007	0.003	0.013	0.019	0.014	0.018	0.027	0.023	0.028	0.014	0.017
D1-SIG	0.026	0.027	0.023	0.026	0.035	0.035	0.037	0.039	0.036	0.032	0.028	0.032
D2-SIG	0.035	0.024	0.021	0.022	0.027	0.028	0.037	0.037	0.027	0.031	0.030	0.030
D3-SIG	0.030	0.035	0.019	0.023	0.026	0.028	0.039	0.036	0.027	0.028	0.026	0.024
D4-SIG	0.014	0.017	0.016	0.023	0.023	0.026	0.032	0.035	0.030	0.033	0.026	0.027

Table 2: Magnitude offsets, δ_{SNLS} , between SNLS tertiary standards and CFHTLS stacks. These magnitude offsets are used to compute a rescaling factor using Equation 4.




Figure 15: Calibration of deep photometric stacks using the SNLS standard stars catalog. Stellar sources are cross-matched with SNLS catalogues and outliers are removed using an iterative two-pass 2σ clipping is applied. The median of the magnitude difference of the remaining objects is used as the rescaling factor.

The final estimator used is the median offset after an iterative two-pass 2σ clipping. A linear regression used to verify that the estimator does not depend strongly on the magnitude of the selected objects (which would a sign systematic biases in our magnitude measurement schema).

The list of rescaling factors are given Table 2. Images are rescaled to keep a final zero-point of 30.0s^{-1} in Vega magnitudes. Given a magnitude offset of δ_{SNLS} ,

$$\delta_{\text{SNLS}} = \text{Median_Clipped}(\text{MAG_IQ20}_i - \text{MAG_SNLS}_i) \quad (3)$$

We can compute a pixel scaling factor of F_{SNLS} as follows:

$$F_{\text{SNLS}} = 10^{0.4 \times \delta_{\text{SNLS}}} \quad (4)$$

3.6.7 Photometric calibration of the Wide survey

The flowchart of the photometric calibration procedure for the CFHTLS-Wide stacks is presented in Figure 16. The key aspect of this procedure is the use of the L99 calibration observations to “transfer” the




Figure 16: Photometric calibration process of the CFHTLS-Wide stacks.

photometry from the SNLS standard stars to the Wide stacks. The L99 fields are observed “bracketing” observations immediately proceeded and followed by an exposure on the Deep survey field closest on the sky. The zero-point of the Deep exposures are calculated in the exact same procedure than described in previous section. Assuming a perfect stability of the photometric conditions during the series of L99 and Deep observations, the zero-points are used to calculate the corresponding zero points for the L99 images (taking into account airmass differences).

The zero points for each L99 image is computed from the mean value of the bracketing Deep fields. In the next step, catalogues with MAG_IQ20 are extracted from both the L99 calibrated images and the Wide stacks. As before, saturated objects are carefully flagged and only stellar objects for which MAG_IQ20 can be reliably measured are selected. The catalogs of overlapping L99-Wide pairs are then matched with the following object selection:

- Magnitude ranges (u:15.0-20.5, g:15.0-21.5, r:15.5-21.5, i:15.5-20.5, z:15.0-20.0)
- Stellar objects: **SExtractor CLASS_STAR > 0.95;**
- Unblended objects: **SExtractor FLAGS==0;**
- Object with good signal-to-noise : **SExtractor MAG_ERR < 0.02;**

From this clean sample rescaling factors from the mean, median or weighted mean. This is illustrated in Figure 17. The resulting median offset, used for the rescaling, is shown as the dashed red line in the

T0007 z-band: W1–72 / L99–037
 mag_aper limits=[(16.67) 16.68, 18.49]; n_tot stars: 1887




Figure 17: Matching between one L99 image and a CFHTLS-Wide tile (stacks are represented by a simplified notation). Upper panel and inset: magnitude difference between W1 and L99; lower panels, magnitude errors and FLUX_RADIUS measurements for both stacks; right panel, histogram of differences. Grey and black dots represent all objects and those used for computation of statistics and rescaling factors respectively. Visual inspection of these control plots allow one to ensure that the sample for final statistics is drawn from non-saturated stars with unblended photometry in both catalogues, following the selection criteria outlined in the text.

main panel of Figure 17. The inset panel shows a linear fit to the bin-averaged statistics (red dots) of the clean sample. Each plot for each L99 – wide pair is manually inspected to ensure that a clean calibration sample.

When several L99 overlap with a single Wide stack, the final rescaling factor is a simple average of each separate rescaling factor. The comparison of the individual factors on a Wide stacks is a useful quality assessment of the quality of the calibration and will be discussed in the photometric accuracy section.

For practical reasons since all objects in a given L99-Wide pair share the same aperture correction, the rescaling offset is computed using SNLS magnitudes (instead of IQ20) and the final rescaling offset includes both the matching offset and the two aperture corrections of the L99 and the Wide catalogs. The final rescaling in magnitude is therefore given by :

$$\delta = \delta_{\text{L99-Wide}} - \text{ApCorr(L99)} + \text{ApCorr(Wide)} \quad (5)$$

After calibration, image pixels are first rescaled to a zero-point of Vega 30.00 s^{-1} using the SNLS rescaling factors. In a second step, these pixels are scaled to a zero-point of 30.0 in AB.

3.6.8 Vega-AB conversion

The SNLS photometric system to which the CFHTLS is anchored is Vega-based. Since all previous releases of the CFHTLS have been in the AB system, in the final processing step all images to the AB system by scaling the pixel values using Vega to AB conversion factors. The conversion offsets have been derived by the SNLS Team and are described in the Appendix. They are summarised in Table 3.

Regnault et al.’s calibration system is linked to the HST white dwarf system through the primary spectroscopic standard star BD+17 4708. The Vega magnitudes (at an airmass of 1) for a star of spectral energy distribution (SED) ϕ can be calculated as:

$$m_{|x_0} = -2.5 \log_{10} \frac{\int \lambda T(\lambda) \phi(\lambda) d\lambda}{\int \lambda T_{x_0}(\lambda) \phi_{bd17}(\lambda) d\lambda} + m_{BD17} \quad (6)$$

where $T_{x_0}(\lambda)$ is the effective filter passband, ϕ_{bd17} is the SED of the photometric standard BD+17 4708 and m_{bd17} is the magnitude of BD+17 4708 in the MegaCam instrumental system.

From the definition of the AB system (Oke, 1974), the broadband AB magnitude of a star of SED $\phi(\lambda)$ is :

$$m_{ab} = -2.5 \log_{10} \frac{\int \lambda T(\lambda) \phi(\lambda) d\lambda}{\int \lambda T(\lambda) \phi_{ab}(\lambda) d\lambda} \quad (7)$$

where

$$\phi_{ab}(\lambda) = 10^{-48.6/2.5} c \lambda^2 \quad (8)$$

It follows that the AB offsets required to bring SNLS magnitudes to AB system, $\delta_{ab} = m_{ab} - m_{|x_0}$, are :

$$\delta_{ab} = -2.5 \log_{10} \frac{\int \lambda T(\lambda) \phi_{bd17}(\lambda) d\lambda}{\int \lambda T(\lambda) \phi_{ab}(\lambda) d\lambda} - m_{bd17} \quad (9)$$

filter	u	g	r	i.MP9701 (i)	i.MP9702 (y)	z
m_{ab}	10.186	9.592	9.343	9.253	9.256	9.241
m_{bd17}	9.769	9.691	9.218	8.914	8.947	8.774
δ_{ab}	0.442	-0.098	0.125	0.339	0.309	0.467

Table 3: Offsets between AB magnitudes and the SNLS Vega-based MegaCam calibration.

The pixels in the images are scaled following this relation:

$$p_{AB} = p_{VEGA} \times 10^{0.4 \times \delta_{AB}} \quad (10)$$

3.7 Production of the Wide and Deep stacks

Each stack comprises all images located inside a radius of 3' with respect to a tile center position. The shifts between each exposure in observing sequence ensures that gaps between the CCDs are filled in the stacked image. Note that in the case of Wide images, the overlapping pixels of nearest neighbor tiles are used for the field-to-field calibration but are not used during the combination process. (In the deep D2- u^* field, additional data from the COSMOS survey is used to make the final stacks).

The T0007 images and weight-maps are combined using the option `COMBINE_TYPE` “MEDIAN” in `SWarp` for the Wide and Deep surveys. The weight-maps correspond to `SWarp`’s image type `MAP_WEIGHT` which correspond to maps of relative inverse variance. Images are resampled using Lanczos-3 interpolation kernel. All resulting tiles and weight-maps have 19354×19354 pixels of 0.186”, corresponding 1 deg \times 1 deg.

Additionally, for the deep fields, a second set of stacks is produced using a sigma-clipping pixel combination algorithm, selected by setting `COMBINE_TYPE` “SIGWEI” in our modified version of `SWarp` supplied by S. Foucaud. The clipping parameter is set to $\pm 3.0\sigma$.

The complete list of images used in each Wide tile is presented in the Appendix A.2. For the deep fields, similar lists can be made available on demand. For the deep fields, images with seeing $< 1.3''$ in u^* , and $< 0.95''$ in $griyz$, are selected for the stack production. From the lists, secondary lists are created containing the 85% and 25% best-seeing images.

All stacks have a zero-point of 30^{-1} s in AB magnitudes. The magnitudes of objects in these stacks are computed as follows: $m = 30 - 2.5 \log(\text{counts})$. The `SWarp` configuration file is presented in Section B.1.1.

Once the g , r and i band data are available they are combined into a “chisquare” or chi2 image which has the same position, scale and input size as the g , r and i images. This chisquared image has been shown to be the optimal way to create a detection image from a series of images taken with different filters (Szalay et al., 1999). The `SWarp` configuration file for the production of the T0007 chi2 images is given in Section B.1.2.

3.8 Final catalogue production

In the Wide and Deep surveys, a .ldac `SExtractor` source catalogue is produced immediately after the final rescaling of the stacks (using L99 images for the Wide and the SNLS standard star catalogue for

the Deep). The T0007 Wide and Deep .1dac source catalogues have been produced using a 128 pixels mesh size to derive the local sky background (BACK_SIZE parameter in **SExtractor**). These catalogs are the inputs of the QFITS-out processing. The **SExtractor** configuration file for the production of the T0007 .1dac catalogues are presented in Appendix B.1.3 and Appendix A.3.5 for wide and deep respectively.

After the production of the chi2 image, **SExtractor** is run in dual-image mode on the u^*, g, r, i, y and z stacks using the chi2 image as reference. The Wide and Deep chi2 .cat catalogues are produced with a using a background mesh size in **SExtractor** of 256 pixels. All catalogues contain parameter values for all quantities listed in Tables 29, 30 and 31. For each source, aperture magnitudes are computed within 27 (26+SNLS) apertures, following same procedure as for the previous T0006 release. The **SExtractor** configuration file used for the production of the T0007 .cat dual-image mode catalogues is listed in the Appendix B.1.4 and Appendix A.3.6 for Deep and Wide surveys respectively.

Additionally, for each survey pointing, the following data products are produced:

- a ($u, g, r, i/y, z$) Wide or (u, g, r, i, y, z)-merged Deep catalogues that includes a restricted number of parameters. These catalogues are produces in two versions with either MAG_AUTO, MAG_SNLS and MAG_IQ20 magnitudes. They also contain the $E(B - V)$ value at each source position derived from dust map images (Schlegel et al., 1998) and the dk cell number (see CFHT preprocessing section for more details).
- a ($u, g, r, i/y, z$)-merged Wide, or (u, g, r, i, y, z)-merged Deep multi-aperture (.ape) extended catalogue that only includes the data concerning the 27 MAG_APER informations in all filters.
- four ($u, g, r, i/y, z$) Wide-patch merged catalogues (one for each Wide patch). These catalogues are produced by matching the objects from the previous multi-aperture merged catalogues in right ascension and declination. The matching is done across each patch of the wide with the following constraints:
 - Objects closer than 250 pixels from the tile edges are discarded. This helps to remove spurious objects and is small enough to ensure that the complete area is covered without holes.
 - The matching tolerance is set to 1.5 arcsec
 - When an object is detected in more than one tile, the object which is kept is the one with the highest signal to noise ratio (defined as the i -band FLUX_AUTO/FLUXERR_AUTO ratio.)

3.9 Post-processing and quality control

Finally, a series of quality assessments are made for:

- each single $u^*, g, r, i/y, z$ Wide or u, g, r, i, y, z Deep stack,
- all $u^*, g, r, i/y, z$ Wide tiles,
- all Wide patches, W_k ($k=1-4$), and
- the whole Wide survey.

The QFITS-in, Scamp, QFITS-out output files are part of the overall quality assessments. Other assessment files which are generated include completeness limit plots, stellar color-color tracks, three-color stacked images, survey maps, Stellar Locus Regression (SLR) color fitting plots and all are available from the T0007 synoptic table.

4 Description of the CFHTLS T0007 Wide survey

4.1 Overview

The T0007 release of the Wide survey covers 171 MegaCam pointings (or tiles) divided into the W1, W2, W3 and W4 fields and is complete in all filters. In total there are 855 u^* , g , r , i/y and z stacks and 171 chisquared images (2052 including the weight-maps). The positions and geometry of the four wide fields comprising T0007, namely W1, W2, W3 and W4, are shown on Fig. 18 and summarised in Table 4. Table 8 lists the effective area, after masking, of the four wide patches in each of the filters.

The image selection criteria applied to the 6410 CFHTLS *Validated* images for the production of the T0007 CFHTLS Wide survey are the following:

- CFHTLS L02 and L05 Wide observation period: between May 26, 2003 and February 02, 2009;
- TERAPIX selection of CFHT *Validated* images, with QualityFITS grade A or B (images within the survey specifications);
- exposure time > 60 s;
- airmass < 1.7;
- images with missing data on more than one entire CCD have been removed from the parent sample. However, all images with missing data on only half of CCD detectors have been preserved;
- all pre-Wide survey images and all photometric short exposures. They will be included in the set of images used for the SCAMP astrometric/photometric calibration process;
- images with seeing (FWHM⁸) < 1.4" in u^* , and < 1.2" in g , r , i and z are selected for the calibration process;
- images with seeing (FWHM) < 1.3" in u^* , and < 0.95" in g , r , i and z , are selected for the stack production;

The parent sample of images after observing period and QualityFITS selections is composed of 1004 u^* , 1062 g , 1490 r , 1063 i , 295 y and 1240 z -band images. 25% of the sample are short photometric or Pre-Wide exposures that are only used for calibration but are not combined into stacks.

All stacks have the same pixel scale and cover exactly 1×1 deg² (19354×19354 pixels of 0.1860"). The stacks only combine images that are part of a CFHTLS Wide observing sequence and that are within 3 arcminutes of the CFHTLS pre-defined stack centre

Each stack comprises a sequence of short exposure of a few hundred seconds. After each exposure the telescope is shifted a small amount (typically a few arcseconds, see the right panel of Fig. 20) to fill the gaps between CCDs, to enable a better sky-subtraction and rejection of bad pixels and cosmic rays during subsequent processing steps.

The adjacent fields have an overlapping region of several arcminutes width to constrain the field-to-field astrometric and photometric calibrations. The size of the overlaps is 4 arcmin in DEC and 3 arcmin in RA (see Fig. 20). The overlaps between fields reduce the sky coverage of the 171 CFHTLS Wide tiles to about 155 deg².

⁸As defined in Section 4.2




Figure 18: Positions and geometry of the CFHTLS Wide fields. The black thick contours show the total field of view composing the $u^*, g, r, i/y$ and z stacks of the T0007 release. The fields located outside these regions are supplementary astrometric calibration data but are not included in the stacks. W1, W2, W3 and W4 do not cover the same field of view, so the four Wide regions are not shown with the same scale in this figure. The blue squares show a typical MegaCam field of view and indicate the positions of the reference center field. The MegaCam images included in the release are in green. They reveal the tiling and mosaicing of each CFHTLS wide area. The small rectangles indicate individual MegaCam CCDs. These plots have been produced by SCAMP during the calibration step of W1, W2, W3 and W4.




Figure 19: Positions, identification and naming conventions of stacks in the CFHTLS Wide survey. The figure shows the positions of each “tile” (blue square corresponding to the field of view of Megacam) covering the W1 and W2 Wide fields. Each tile is labelled by its Cartesian name on top (see <http://terapix.iap.fr/cplt/oldSite/Descart/summarycfhtlswide.html>) and the official CFHTLS below. Field W*(0,0) (in red) at the approximate center field of each survey patch, before the survey strategy changes.

CFHTLS field name	Reference center RA [J2000]	Reference center DEC [J2000]	Total pointings [n×p]	Total sky coverage [deg ²]	Filters	Comment
W1	02:18:00	-07:00:00	9×8	8.5×7.5	$u^*, g, r, i/y, z$	16 y
W2	08:57:49	-03:19:00	5×5	4.8×4.7	$u^*, g, r, i/y, z$	New center; 2y
W3	14:17:54	+54:30:31	7×7	6.7×6.6	$u^*, g, r, i/y, z$	7 y
W4	22:13:18	+01:19:00	25	23.3	$u^*, g, r, i/y, z$	SE-NW elongated; 7 y

Table 4: Overview of the CFHTLS Wide fields. The pointings “n×p” refer to the numbers of tiles along the horizontal and vertical axes of MegaCam (*i.e.* the E-W and N-S axes). Sky coverage is expressed along RA and DEC axes.

Filter	Median number of exposures	Median exposure time [s]	Mean limiting magnitude [MegaCam AB system]	Mean seeing [”]
u^*	5	3000	25.53	0.846
g	5	2500	25.89	0.785
r	4	2000	25.38	0.714
i/y	7	4300	25.14	0.642
z	6	3600	24.23	0.678

Table 5: Mean properties of the CFHTLS Wide survey. The i and y are not split into two sub-samples. The Mean limiting magnitude corresponds to the 50% completeness limit for a point-like source. The Mean seeing is the mean FWHM of stellar sources over the whole MegaCam field.




Figure 20: Offsets between adjacent pointings (left) and dithering (right) inside a pointing of the CFHTLS Wide survey. Each pointing (or tile) overlaps along the RA and DEC directions with its nearest neighbours. In addition to the large offsets, the observations at each CFHTLS Wide reference position (“Ref” and green filled circles) are split into an observing sequence of exposures, with a small dither between each. The dithering pattern depends on the number of exposure per sequence and is different for each filter (see Table 5). In all configurations the dithered positions (black filled circles) are among those located inside a $30'' \times 180''$ ellipse centered at the reference position of a Wide pointing. This is illustrated on the right hand of the figure (drawn from the CFHTLS dithering pattern plot: <http://www.cfht.hawaii.edu/Instruments/Imaging/MegaPrime/specsinfo.html>). The details of this figure are given at this URL). The offsets and the dithers along the DEC direction are sufficiently large to fill the central $82''$ horizontal gap between the CCDs (see Fig. 2) with a fraction of exposures of each sequence. The dash-dot blue squares on the left show the positions of Pre-Wide images. They are shifted by a half-MegaCam field of view, in both directions, in order to provide very large overlaps between pointings and ease the astrometric calibration and the field-to-field flux rescaling. The Pre-Wide images are short exposures (3 mn) only done in r -band.

Each tile is centered at a well-defined position. The coordinates of a stack centre position are identical for all filters. W1, W2, W3 and W4 are therefore composed of a complete set of u^* , g , r , i , y and z adjacent square tiles of 1 deg² each.

The integer part of the centre position of each tile is used to name the final stacks and other data products. (This naming convention was agreed by CADC, TERAPIX and the CFHTLS Steering Group and is valid for all releases). Each release is identified by the extension T000n, where n is the release number.

In addition to the official astronomical CFHTLS naming convention, Terapix defined in 2002 a shorter naming convention based on a Cartesian grid coordinate system, where the increment unit is a MegaCam-size field and the center positions of the grid points are the center positions of the tiles⁹.

The reference center of each Wide field of view is defined as the reference W[1, 2, 3, 4](0,0) and the Cartesian field names increase toward the East and North. The tiling and field naming conventions are drawn on Fig. 19 and the complete list of the T0007 Wide stacks is given on Tables 32.

The total exposure time per filter is approximately the same for each tile (see Table 32 and the synoptic table). It produces in very sharp exposure time distributions for all filters (see Fig. 22). Some observations have been adjusted to take into account unexpected events (like absorption by clouds/cirrus or technical problems). There are a few fields that have deeper u^* -band and z -band exposures which explains the small tails shown in the inset of Fig. 22. These longer exposures were taken before it was decided to cut the u^* and z exposure times by a factor of two.

In addition to the original CFHTLS exposures, the VIPERS consortium took complementary exposures to fill in the holes in W1 which were caused by malfunctionning CCDs. These images (distributed in 6 pointings and three filters u, g and y) have been added to T0007. As a result, these pointing are deeper than the rest of the survey. A detailed description of the added VIPERS images can be found in Table 6. Their position on the W1 patch are shown in Figure 21.

Wide position	Filter	Exposure time (per image)	Number of exposures
		[s]	
W1+2+2	u.MP9301	600	6
W1+4+2	g.MP9401	290	7
W1+3+1	g.MP9401	290	5
W1+3+1	g.MP9401	290	5
W1+4+1	g.MP9401	290	5
W1+2+1	i.MP9702	300.096	7
W1+3+2	i.MP9702	300.092	5

Table 6: Description of the 40 additional VIPERS images.

All r -band stacks combine data taken during two epochs separated by at least two years and totalling 2×500 s each. In all filters except u^* , observations were carried out only when the seeing (FHWM) was below 0.95''. For the u^* -band, this rule was relaxed to 1.3''.

⁹<http://terapix.iap.fr/cplt/oldSite/Descart/summarycfhtlswide.html>




Figure 21: Position of the additional VIPERS exposures used to fill in the holes in the survey. Top left: u -band, top-right: g -band, lower left: y -band. lower-right: filter mask coverage of the W1 Wide patch (See Section 6 for the meaning of the flags). Seven fields still have holes in one or more filters due to malfunctioning CCDs. These anomalies are listed in Tables 16 and 17.

The complete list of CFHTLS input images that were combined into the Wide stacks is given in the Appendix A.2, in Table 33.

The global properties of the CFHTLS Wide survey are summarized in Table 5 and in more detail in Table 7. Overall, they meet survey specifications, but the homogeneity of the survey over a Wide patch scale must be assessed carefully. The Wide field-to-field and MegaCam tile-to-tile scatters will be explored in detail in the following sections. The depth, the seeing, the photometric errors analyses are presented in the next parts of the document.

Finally, the complete set of configuration files used for the T0007 release is presented in the Appendix. They are intended for users who would prefer to re-process the preprocessed or the stacked images with better tuned parameters for their own scientific projects. The configuration files are available on request from TERAPIX.

4.2 Seeing and image quality

All seeing values reported in this document and in tables are computed using PSFEx (Bertin, 2011). The seeing is measured from a two-dimensional Moffat model of the PSFm and the FWHM is defined from the ellipticity parameters of the PSF as $\text{FWHM} = \sqrt{a b}$, where a and b are the size of the major and

Field	Parameter	u^*	g	r	i	y	z
W1	Nb stacks	72	72	72	56	16	72
	Seeing ["]	0.84 ± 0.11	0.77 ± 0.10	0.70 ± 0.07	0.65 ± 0.08	0.66 ± 0.10	0.69 ± 0.13
	80% Compl. (stellar)	25.27 ± 0.21	25.52 ± 0.18	25.03 ± 0.16	24.73 ± 0.18	24.82 ± 0.22	23.90 ± 0.26
	80% Compl. (extended)	24.45 ± 0.15	24.67 ± 0.14	24.00 ± 0.10	23.69 ± 0.13	23.78 ± 0.20	22.91 ± 0.15
	Int. astrom. err.	((0.031",0.029")	((0.031",0.029")	(0.025",0.022")	(0.020",0.017")	(0.020",0.017")	(0.025",0.022")
	Ext. astrom. err.	((0.237",0.227")	((0.254",0.244")	(0.259",0.247")	(0.252",0.243")	(0.272",0.254")	(0.260",0.247")
	Mag. err. [mag.]	0.05 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.04 ± 0.01
	CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.020 ± 0.015	+0.003 ± 0.006	+0.041 ± 0.014	+0.000 ± 0.007	-0.002 ± 0.008	+0.015 ± 0.011
W2	Nb stacks	25	25	25	23	2	25
	Seeing ["]	0.88 ± 0.10	0.79 ± 0.08	0.72 ± 0.09	0.64 ± 0.08	0.59 ± 0.05	0.72 ± 0.09
	80% Compl. (stellar)	25.16 ± 0.20	25.51 ± 0.18	25.04 ± 0.18	24.81 ± 0.13	24.96 ± 0.15	23.88 ± 0.16
	80% Compl. (extended)	24.36 ± 0.17	24.66 ± 0.16	24.00 ± 0.13	23.76 ± 0.10	23.84 ± 0.09	22.94 ± 0.11
	Int. astrom. err.	((0.024",0.021")	((0.024",0.021")	(0.024",0.021")	(0.024",0.021")	(0.024",0.021")	(0.024",0.021")
	Ext. astrom. err.	((0.183",0.186")	((0.208",0.211")	(0.211",0.213")	(0.207",0.210")	(0.224",0.228")	(0.211",0.212")
	Mag. err. [mag.]	0.05 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.04 ± 0.01
	CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.040 ± 0.011	-0.008 ± 0.005	+0.007 ± 0.004	-0.007 ± 0.005	-	+0.018 ± 0.012
W3	Nb stacks	49	49	49	42	7	42
	Seeing ["]	0.85 ± 0.11	0.81 ± 0.09	0.75 ± 0.08	0.66 ± 0.08	0.59 ± 0.08	0.67 ± 0.09
	80% Compl. (stellar)	25.20 ± 0.22	25.48 ± 0.16	24.99 ± 0.15	24.67 ± 0.16	24.95 ± 0.15	23.93 ± 0.22
	80% Compl. (extended)	24.35 ± 0.21	24.64 ± 0.12	23.98 ± 0.10	23.63 ± 0.12	23.89 ± 0.11	22.92 ± 0.17
	Int. astrom. err.	((0.036",0.035")	((0.036",0.035")	(0.036",0.035")	(0.036",0.035")	(0.036",0.035")	(0.036",0.035")
	Ext. astrom. err.	((0.235",0.225")	((0.248",0.242")	(0.258",0.249")	(0.246",0.242")	(0.275",0.269")	(0.258",0.250")
	Mag. err. [mag.]	0.05 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.04 ± 0.01
	CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.012 ± 0.009	+0.003 ± 0.004	+0.010 ± 0.005	-0.013 ± 0.004	+0.000 ± 0.004	+0.001 ± 0.005
W4	Nb stacks	25	25	25	18	7	25
	Seeing ["]	0.81 ± 0.11	0.75 ± 0.06	0.67 ± 0.07	0.61 ± 0.07	0.59 ± 0.06	0.64 ± 0.10
	80% Compl. (stellar)	25.22 ± 0.21	25.57 ± 0.17	25.02 ± 0.16	24.81 ± 0.19	24.97 ± 0.11	23.91 ± 0.20
	80% Compl. (extended)	24.35 ± 0.17	24.71 ± 0.15	23.94 ± 0.12	23.73 ± 0.19	23.88 ± 0.08	22.90 ± 0.13
	Int. astrom. err.	((0.023",0.020")	((0.023",0.020")	(0.023",0.020")	(0.023",0.020")	(0.023",0.020")	(0.023",0.020")
	Ext. astrom. err.	((0.193",0.186")	((0.218",0.213")	(0.222",0.217")	(0.217",0.215")	(0.221",0.217")	(0.214",0.212")
	Mag. err. [mag.]	0.05 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.03 ± 0.01	0.04 ± 0.01
	CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.030 ± 0.009	+0.009 ± 0.003	+0.010 ± 0.007	-0.001 ± 0.006	-	+0.022 ± 0.005

Table 7: Summary of the W1, W2, W3 and W4 mean survey parameters. The i and y data have been combined. "80% Compl." is the 80% completeness limit. The seeing is the median FWHM and the errors is the field-to-field scatter. Astrometric errors are given along the two (x,y)=(NS,EW) axes. The internal astrometric errors are from the (global) astrometric calibration errors step; the external astrometric errors are from the (ensemble average) astrometric accuracy of CFHTLS stacks. The "CFHTLS-SDSS $\langle \delta_m \rangle$ mag." denotes the mean magnitude offset between the CFHTLS and the SDSS surveys, averaged over a Wide field. It is derived from a sample of common stars to both surveys in W1, W3 and W4 (no data for W2). The "Mag. err." is estimated from the external and internal magnitude errors discussed in the document. For W2, it is based on the internal mag. error and extrapolated from the W1, W3 and W4 CFHTLS-SDSS comparisons.

Field	Parameter	u^*	g	r	i	y	z	$ugriz$ coverage
W1	Nb stacks	72	72	72	56	16	72	72
	Raw observed area	–	–	–	–	–	–	64.16
	Final unmasked area	58.47 (210500)	58.41 (210267)	58.49 (210581)	45.41 (163490)	13.08 (47096)	58.47 (210504)	58.33 (209975)
W2	Nb stacks	25	25	25	23	2	25	25
	Raw observed area	–	–	–	–	–	–	22.22
	Final unmasked area	18.60 (66952)	18.51 (66624)	18.60 (66952)	17.19 (61878)	1.43 (5152)	18.60 (66952)	18.50 (66622)
W3	Nb stacks	49	49	49	42	7	42	49
	Raw observed area	–	–	–	–	–	–	41.91
	Final unmasked area	37.04 (133351)	37.04 (133351)	37.04 (133351)	31.74 (114277)	5.56 (20018)	37.04 (133351)	37.04 (133340)
W4	Nb stacks	25	25	25	18	7	25	25
	Raw observed area	–	–	–	–	–	–	22.09
	Final unmasked area	19.66 (70777)	19.66 (70777)	19.66 (70777)	14.10 (50754)	5.62 (20218)	19.66 (70777)	18.50 (66622)
Wide	Nb stacks	171	171	171	129	32	171	25
	Raw observed area	–	–	–	–	–	–	22.09
	Final unmasked area	133.77 (481580)	133.616 (481019)	133.795 (481661)	108.44 (390399)	25.69 (92484)	133.78 (481584)	132.38 (476559)

Table 8: The raw observed area is the surface covered by the MEGAPrime Focal plane on the sky. The Final unmasked area is the surface observed by the CFHTLS which is not masked (due to foreground star and instrumental defects). The surface is given in square degrees and square arcminutes.




Figure 22: Distribution of exposure times over the Wide fields. The inset is a close-up view of the long exposure tails.

minor axes derived from the model. For single CFHTLS input images, the seeing is sampled over a CCD ($\sim 7' \times 14'$, see Fig. 23), and for T0007 stacks it is sampled over a $5' \times 5'$ grid. (Note that in T0005 and anterior releases, the seeing was measured from the radius enclosing half the object flux.)

The PSF model of each stack (Wide and Deep) is determined using stellar sources selected by PSFex. All unsaturated and sufficiently bright stellar sources identified over the entire MegaCam field are used. The median seeing values of the survey are given in Table 5 and Table 7.

Overall, the CFHTLS Wide is within or better than expectations, thanks to the high ranking of the program which meant that most observations were made in good-seeing conditions. The histograms drawn in Fig. 24 show the median seeing increases from z to u^* . However, more than 98% of g, r, i, y, z and more than 70% or u^* band stacks have seeing better than $0.9''$. Note that the histograms show the distributions of seeing over the whole period of the survey. They merge together data obtained before (Dec. 4, 2004) and after the flip of the L3 lens of the MegaPrime Wide Field Corrector. The flip produced a spectacular improvement of the image quality and our merging of the pre-flip and post-flip periods contribute to the large scatter of the seeing distributions. Despite this extra-scatter term, the image quality of the CFHTLS Wide survey is excellent and unique compared to other current wide field surveys.

Figure 25 shows maps of the spatial distribution of seeings in all Wide stacks and for each filter. No bias is observed, the median seeing of each stack appears randomly distributed over the four Wide fields.

Due to the optical distortion of the MegaPrime wide field corrector, image quality is not constant over the field. This well-known problem is responsible for a significant degradation of the PSF from the center to the edge of the MegaCam field of view (see Fig. 23).

Figure 26 shows the seeing fluctuations on MegaCam. The seeing is averaged over a CCD field of view and compared to the mean seeing over the whole MegaCam field. The statistics is based on 6043 input images used for the CFHTLS Wide T0007 release. For CCDs at the edges of the detector, the differences




Figure 23: (Top Left) Seeing (FWHM) mapped over the input *i*-band image `743065p.fits` by `QualityFITS-in`. This image was taken before the MegaPrime optics were optimized (fall 2004) to deliver a uniform PSF across the entire field. It is used as an illustration of the image quality issue on MegaCam from May 2003 to Nov. 2004. Each spot shows an image of the PSF computed by PSFEX from a model of stars detected on the CCD. The optical distortion of the wide field corrector is clearly visible from PSF variation over the field. The median seeing over the MegaCam field is 0.692'', but it is 0.642'' at the center, on CCD#22 (spot 23 from the top left corner), and 0.795'' at the bottom left corner. (Top Right) Seeing (FWHM) mapped over the input *i*-band image `980090p.fits` by `QualityFITS-in`. This image was taken after the MegaPrime optics were optimized (fall 2004). The lower part shows the improvement in the PSF shape over the lower left CCD obtained with the addition of the optic corrector.




Figure 24: Distribution of the median seeing over the Wide tiles. The seeing is the FWHM= $\sqrt{a \cdot b}$ derived with PSFEX, from the fitting of a 2-dimension Moffat model of the PSF. The mean seeing value over the MegaCam field of each stack is available at http://terapix.iap.fr/cplt/T0007/table_syn_T0007.html.

are important but never exceed 0.065'', and the maximum peak-to-peak amplitude is less than 0.1''. This upper limit is acceptable. It still preserves the mean seeing over the whole MegaCam field of view below one arcsecond for all input images that will be combined into stacks.

In addition to the smearing, the PSF elongation also increases with radial distance to the center field (Figure 23). It results in a non-isotropic degradation of the mean seeing at the extreme boundary of the field that can be as large as 0.25'', to rise up by 20% at radial distance beyond 40' from the center of the MegaCam field. The median seeing values and the shape of the PSF quoted in this report are therefore not correct at the very edge of MegaCam. We recommend using the T0007 masks to discard the sources located in these extreme regions.




Figure 25: Maps of seeing (FWHM) in the CFHTLS Wide. Each small square represents a median seeing value over a $1^{\circ} \times 1^{\circ}$ tile (or a stack) of the wide survey. The panels show, from left to right: W1, W2, W3 and W4; from top to bottom: the u^* , g , r , i/y and z CFHTLS stacks.




Figure 26: PSF variations as function of the position on MegaCam (CCD positions) and wavelength (filters), produced by the optical distortion of the MegaPrime Wide field corrector. These statistics are based on 935 u^* , 978 g , 1669 r , 1064 i and 1177 z -band images (the 220 y -band images have been discarded). The variations are estimated from the comparison between the mean seeing (FWHM) averaged over the MegaCam field of view and the mean seeing averaged over a CCD field of view. The statistics are computed over the 36 CCDs composing the mosaic. The CCDs are numbered using the CEA-CFHT CCD reference number laid out on the central figure. The left panel show the difference $\langle \text{FWHM} \rangle_{\text{CCD}} - \langle \text{FWHM} \rangle_{\text{Megacam}}$ expressed in arcseconds. The horizontal axis is the CEA-CFHT CCD reference number. One can see that for the CCDs at the edges of the detector, the differences never exceed 0.065'', and the highest peak-to-peak amplitude is less than 0.1''. The right panel shows the seeing contrast $\frac{\langle \text{FWHM} \rangle_{\text{CCD}} - \langle \text{FWHM} \rangle_{\text{Megacam}}}{\langle \text{FWHM} \rangle_{\text{Megacam}}}$. The contrast is always lower than 10% and the highest peak-to-peak contrast amplitudes are always less than 15%. Overall, the range of seeing values over the MegaCam field of view is acceptable. However, at the corners of MegaCam, the seeing difference with the mean value can be as large as 0.25''. Only the most extreme positions have a large PSF degradation and images that no longer meet the specifications of the surveys. We discard these regions by adding extra polygons to the T0006 .reg files that mask the edges of all stacks. The fraction of the MegaCam field discarded is less than 3%.




Figure 27: Completeness calculation for the W3 stack CFHTLS_W_i_142939+514231. Left panel: The blue and red lines shows the completeness for point-like and extended sources respectively. The green dots show the best fitting functions which are used to derive the completeness values. Right panel: galaxy counts derived automatically by QualityFITS from this stack. The red line shows the expectations for the MegaCam *i*-filter. The green line is the 80% completeness limit of extended objects.

4.3 Depth and completeness limits

The depth of the survey tile is measured by the completeness limit. It is determined for each stack and each filter separately. The depth is also checked by using the galaxy counts computed after the production of each stack, as part of the QualityFITS analysis. All completeness galaxy count plots are available from the T0007 synoptic table¹⁰.

To compute the completeness limit, we used image simulations produced by SkyMaker(Bertin, 2009). Noiseless images of point-like (stars or galaxy bulges) and disk-like (spiral galaxies) sources have been simulated by combining spheroid and disk models, using de Vaucouleur and exponential light profiles, respectively. The star and galaxy number densities of simulated sources correspond to the expectations for typical CFHTLS exposure times. Their slope and normalisation are based on realistic luminosity function in a standard Λ -CDM cosmology (for galaxies), and are produced according to the transmission of MegaPrime filters.

The sources are then convolved by a PSF that takes into account the pupil of the CFHT telescope (mirrors and arms) and other components of the PSF. The PSF is built by using the diffraction and the simplest aberration components of the CFHT telescope, as well as the typical atmospheric contributions that degrade long exposures. A set of simulations are produced with PSF FWHM ranging from $0.4''$ to $1.3''$. For each stack, the simulated images with the closest PSF in FWHM size is then used to compute the final completeness. This “adaptive FWHM” method gives rise to larger dispersion in the completeness distribution compared to T0006. The T0007 completeness encompass both the exposure time and depth effect, as well as the image quality. The point source completeness is therefore more affected than the extended objects one.

The completeness limit is then derived from the averaged completeness value over the central 10000×10000 MegaCam fields. The statistics is computed in each fields separately and for each filter. The output is the fraction of sources detected and measured as function of magnitude. The magnitudes at 80% and 50%

¹⁰http://terapix.iap.fr/cplt/T0007/table_syn_T0007.html

completeness are given for point-like (star or bulge) and for extended (disks) sources.

The 80% and 50% completeness values are calculated from an automated fitting process applied to the catalogues of real and simulated sources without tuning. The limiting magnitudes are derived automatically by an empirical two parameter ($x_0; \alpha$) fitting function

$$y = 100.0 \times \left(1 - \frac{\text{erf} [x - x_0]^\alpha + 1.0}{2.0} \right) \quad (11)$$

where x_0 provides the turn-over position of the completeness function and α is the function slope at x_0 . The parameters ($x_0; \alpha$) are found from a standard χ^2 minimization. The 50% and 80% completeness limits are derived from a linear interpolation. An example of fit is given in Fig. 27. In some cases, the fit and the interpolation are not good and the completeness value is then poorly estimated.

The completeness distributions over the whole Wide fields and inside a wide field are presented in Table 7. The left panel of Figure 28 shows the completeness distribution for the entire Wide survey for all four fields. Figure 29 shows the completeness distributions for each of the four Wide patches.

The histograms together with a detailed inspection of the data show that the mean scatter in completeness is ± 0.20 magnitudes, with significant variations from filter to filter. The completeness distribution in z -band is broader than other filters, with a tail which extends over one magnitude. In contrast, the r band distribution is narrower (± 0.15 mag.).

Figure 31 shows a series of completeness maps over the entire wide fields. The maps are produced for each Wide field and for each filter.

The left and right panels of Figure 30 shows that the completeness distribution are dominated by Seeing effet, both for point sources and extended objects : The better the image quality, the deeper the image. Compared to the Seeing contribution, the exposure time (even with double exposure time) has a smaller influence on the final Depth measurement. For the z band data the scatter in the completeness limits is probably affected the fringe subtraction residuals on some images. For the u^* band, the range of limiting depth is likely broadened by the diversity of observing conditions (Moon, extinction, seeing). Nevertheless, (other than exposure time) the main factor affecting image completeness is the Seeing FWHM.

Finally, Figure 32 shows the galaxy counts for the four Wide patches.

4.4 Photometric accuracy

In this Section we attempt to make a robust estimate of the internal photometric errors of the CFHTLS using a variety of methods. Although `Scamp` provides an estimate of the internal photometric error (between individual MegaCam images), we instead focus on the photometric errors in the final tiles. In this way, initial calibration errors and any other subsequent source of errors, inside each stack and field-to-field are better taken into account, leading to a more realistic estimation of the errors.

4.4.1 Internal photometric errors of Wide stacks from simulations

The internal photometric errors are derived using the same simulations used in the completeness analyses described in Section 4.3. The use of simulations enables a better control of the input and output sources and ensures that all Wide stacks are evaluated consistently. As before, simulated sources are added to the real T0007 Wide stacks and processed the same way as real sources. Their photometry is then compared




Figure 28: Left panel: overall distribution of completeness on the wide fields. Right panel: completeness limit of Wide stacks as function of exposure time. A trend of increasing depth with increasing observing time is apparent. There is however a broad spread in depths at a given exposure time. due to other factors such as image quality, sky and weather conditions. The depth of some z -band stacks is also reduced by persistent residuals from the fringe subtraction.




Figure 29: Distribution of 80% stellar completeness over the Wide fields. The horizontal axes are MegaCam AB magnitudes.




Figure 30: Left and right panels respectively: Stellar and extended-source completeness limit of Wide stacks as function of seeing FWHM. As expected, the point source completeness is a clear function of the image quality: the better the seeing, the deeper the image.

to the input simulated values. The simulated sources are added within the central 10000×10000 pixel and consequently are expected to be free from edge effects.

This procedure has been applied to the 855 Wide stacks, using simulated stars generated on a grid of FWHM in steps of $0.05''$ using the Skymaker software (Bertin, 2009). In each case, stars with a FWHM closest to the stack in question are selected. For each sample, the magnitude difference between the input and the output simulated sources as function of magnitude is computed and the FWHM of the magnitude distribution is derived after 3σ clipping. The internal error is then given by $\sigma_{mag} = \text{FWHM}/2.35$.

Error estimates are computed for sources selected with signal-to-noise ratios of 10, 30 and 100, respectively, or as a function of magnitude Fig. 33 shows an example result for internal photometric analysis of the CFHTLS T0007 Wide stack CFHTLS_W_g_020241-041200_T0007. The statistics compare the MAG_AUTO magnitude calculated by SExtractor for several thousands of stellar sources. It is interesting to note that the results are very stable down to signal-to-noise values of 10. Note that the difference between the input and output magnitudes as function of magnitude is not flat, but tilted. The tilt may artificially increase the dispersion inside a magnitude bin and may contaminate the internal error estimates, if the bin is large. The mean inside a bin is then corrected from the tilt prior to deriving an errors or FWHM.

The internal errors per magnitude bin are listed in Table 9.

4.4.2 Error estimation from overlapping Wide tiles

An estimation of the internal photometric errors of the Wide survey can also be made using common sources in overlapping tiles. Since each tile is shifted by $56''$ in RA and $57''$ in DEC with respect to its nearest tiles overlap regions are stripes of $4' \times 60'$ or $3' \times 60'$ (see Fig. 20). We use the u^* , g , r , i and z -band MAG_IQ20 stars located in these regions to compare the photometry of sources detected in two adjacent stacks. The analysis is restricted to stars to avoid the specific issues involved in the use of MAG_AUTO for galaxies. Furthermore, it can only be applied on thin strips located at the edges of images where sources have lower signal-to-noise due to the adopted dithering strategy; therefore, this analysis should be regarded as complimentary to our previous simulation-based estimations.




Figure 31: Maps of 80% completeness limits in W1, W2, W3 and W4 (from left to right). Each colored square represents a $1 \times 1 \text{ deg}^2$ tile. Square colour indicates the seeing value, with darker squares have poorer seeing. From top to bottom: u^* , g , r , i , y and z bands.




Figure 32: Galaxy counts for the four wide patches in all bands.

The first estimate of internal errors is derived by calculating for each pair of overlapping tiles the median of the magnitude differences of all source pairs in the overlapping regions. This value is the *field to field photometric offset* between the two contiguous tiles. For a complete Wide patch, the standard deviation of these field to field offsets is a estimator of the field to field scatter. The values for each field and filter are listed in Table 10. To compare these errors with estimators calculated from a comparison to a reference catalog use din Section 4.4.3 a hypothesis has to be made on the distribution of this random variable. If we assume that photometric measurement are Gaussian-distributed around the “true” photometry with a dispersion of σ , then the dispersion of the field to field offsets is a Gaussian with a dispersion $\sqrt{2}\sigma$. The values of Table 10 must be divided by $\sqrt{2}$ to be compared with the field to field estimations of Table 13. The errors are larger in u^* and z bands for several reasons: the residuals from fringe subtractions in z , the image degradation in u^* and at the edges of the stacks, and the residuals from the internal calibration errors. Considering the factor of $\sqrt{2}$, these errors are completely consistent with an overall photometric field to field scatter of 1% in g, r and i and 1.5% in u^* and z .




Figure 33: Analysis of the internal photometric errors in CFHTLS_W_g_020241-041200_T0007 using simulations of stars. The top panels are analysed without clipping and the bottom panels after a 3σ clipping. The figures show the results for three sub-samples selected from signal-to-noise ratio (not magnitudes): S/N=10 (black), 30 (red) and 100 (green). Each panel is split into two plots. On the left the magnitude differences between the *true* input and the *measured* output magnitudes of simulated sources are drawn as function of magnitude. The sub-samples are shown in green, red and black colors. On the right, the normalised distributions for the three sub-samples are shown. The FWHM, errors, $\sigma = \text{FWHM}/2.35$, in table 9 are derived from the histograms. Note that a magnitude dependant offset has been corrected prior to compute the FWHM and the errors inside a magnitude bin quoted in Table 9.

Wide Field	Magnitude range [MegaCam AB]	u^* [mag.]	g [mag.]	r [mag.]	i [mag.]	y [mag.]	z [mag.]
W1	[19.0 – 20.0]	0.002	0.002	0.003	0.006	0.003	0.008
	[20.0 – 21.0]	0.005	0.003	0.010	0.007	0.007	0.017
	[21.0 – 22.0]	0.008	0.009	0.011	0.016	0.014	0.043
	[22.0 – 23.0]	0.020	0.015	0.025	0.037	0.035	0.098
	[23.0 – 24.0]	0.046	0.035	0.061	0.089	0.083	0.159
W2	[19.0 – 20.0]	0.002	0.002	0.003	0.003	-	0.009
	[20.0 – 21.0]	0.004	0.004	0.005	0.007	-	0.018
	[21.0 – 22.0]	0.009	0.009	0.012	0.016	-	0.041
	[22.0 – 23.0]	0.020	0.016	0.027	0.038	-	0.097
	[23.0 – 24.0]	0.050	0.038	0.067	0.087	-	0.161
W3	[19.0 – 20.0]	0.002	0.001	0.002	0.003	0.002	0.008
	[20.0 – 21.0]	0.004	0.003	0.005	0.007	0.007	0.018
	[21.0 – 22.0]	0.008	0.007	0.011	0.017	0.015	0.040
	[22.0 – 23.0]	0.020	0.015	0.025	0.039	0.034	0.095
	[23.0 – 24.0]	0.049	0.035	0.060	0.094	0.084	0.140
W4	[19.0 – 20.0]	0.002	0.001	0.002	0.003	0.003	0.009
	[20.0 – 21.0]	0.004	0.003	0.005	0.007	0.007	0.019
	[21.0 – 22.0]	0.008	0.007	0.013	0.017	0.015	0.044
	[22.0 – 23.0]	0.020	0.015	0.028	0.041	0.035	0.098
	[23.0 – 24.0]	0.049	0.035	0.057	0.094	0.088	0.142

Table 9: Internal photometric errors per magnitude bins derived for each CFHTLS Wide field. The simulated sources include only stars and are detected and analysed in the same was as real sources. The errors are the FWHM/2.35, as shown in Fig. 33. They are corrected from the amplitude of the tilt from horizontal of the difference between of the input and output magnitudes as function of magnitude inside the bin. The magnitude ranges quoted in the table only comprise bins with all sources below the completeness limits and with all sources having a signal-to-noise ratio larger than 10. The W2 y -band is not quoted because it only concerns two stacks and the statistics are meaningless for these fields.

The second estimate of internal photometric errors which can be determined from the analysis of objects observed in multiple tiles is the measurement error. Providing that the images are photometrically flat (see illumination section), the dispersion of the magnitude offsets around the mean field-to-field shift of objects detected in multiple tiles is dominated by statistical measurements errors. This dispersion as a function of magnitude is plotted as the vertical error bars in Figure 34 for each of the four Wide patches and is listed in Table 11. In this analysis, both stars and galaxies are included; magnitudes are estimated using MAG_AUTO to yield a realistic estimate of measurement errors for both stars and galaxies. We also note the plots are broadly similar for each of the four patches, confirming the homogenous nature of the survey. The z -band errors are several times higher than other bands; for these longer wavelengths fringing residuals become important.

The dispersion distributions are fitted with third order polynomials. To compare these values to the direct estimation of measurement errors in the simulations, one has to assume a gaussian distribution (dispersion σ_M) of measured magnitude around the true magnitude. The distribution of the magnitude

Wide field	σ_{u^*} [mag.]	σ_g [mag.]	σ_r [mag.]	σ_i [mag.]	σ_z [mag.]
W1	0.020	0.010	0.015	0.013	0.020
W2	0.020	0.010	0.012	0.011	0.023
W3	0.025	0.010	0.015	0.011	0.019
W4	0.016	0.009	0.008	0.013	0.016

Table 10: Internal field-to-field photometric errors in the T0007 CFHTLS Wide release derived from sources in adjacent tiles. These internal errors are computed from the T0007 “merged source catalogues” (M-SC, see Section 6.3) which contains `mag_IQ20` for sources detected on the u^* , g , r , i/y , z and chi2 images. They are derived from the mean of the absolute magnitude differences of source pairs, averaged over overlapping regions of neighboring stacks. Only bright stars are used to derive a robust field-to-field offset for each contiguous tile pair. The limiting magnitudes are $u < 19, g < 22, r < 20, i < 21, z < 19$. These values should be regarded as an upper estimate in the errors as they are calculated using the stack edges which have lower signal-to-noise due to dithering.

differences is then a Gaussian distribution with a dispersion equal to :

$$\sigma_{\text{diff}} = \sqrt{2} \times \delta_M \quad (12)$$

These errors are listed in Table 11.

Comparing these errors with the errors derived from the simulations shows that the errors from the overlaps are larger than the errors from the simulations. This is to be expected and can be explained by several reasons: the statistics on the objects in the overlaps rely on sources detected at field edges where image quality and signal-to-noise is lowest due to PSF elongation at the field edges and dithering. Furthermore, the flatness of the photometry across the field of view show a departure from the reference central photometry on the edges. This effect is non-symmetric (as documented in section ...) and affects the reliability of the magnitude measurements at the field edges. Therefore these error estimates should be considered as upper limits and contain residual systematic effects which add to the pure statistical flux measurement errors.

4.4.3 Systematic offsets between CFHTLS and SDSS

External photometric error estimates cannot be reliably measured from the photometric output of SCAMP given the different wavelength coverage of the CFHTLS and 2MASS.

The SDSS-R8 catalogue is a better candidate to compute photometric errors. Unfortunately, it only partially overlaps with CFHTLS; only 115 Wide fields amongst 171 have sources common with SDSS. External photometric accuracy and errors computed using these overlaps are discussed in this section, first by comparing directly with the SDSS sub-samples and secondly by an analysis of stellar color-color tracks.

As in T0004, T0005 and T0006 releases, the photometric calibration has been verified by comparing the CFHTLS and SDSS bright sources in regions where the SDSS R8 overlaps with the W1, W2, W3 and W4 fields. Compared to the previous releases, DR8 now covers (at least partially) all four Wide patches.

The CFHTLS photometry is first transformed into the SDSS system using the equations derived by

Wide Field	Magnitude range [MegaCam AB]	u^* [mag.]	g [mag.]	r [mag.]	i [mag.]	z [mag.]
W1	[19.0 – 20.0]	0.013	0.007	0.009	0.010	0.025
	[20.0 – 21.0]	0.016	0.008	0.013	0.016	0.054
	[21.0 – 22.0]	0.024	0.014	0.023	0.031	0.112
	[22.0 – 23.0]	0.039	0.026	0.043	0.062	0.210
	[23.0 – 24.0]	0.065	0.046	0.078	0.114	0.359
W2	[19.0 – 20.0]	0.010	0.006	0.010	0.009	0.020
	[20.0 – 21.0]	0.014	0.009	0.015	0.015	0.045
	[21.0 – 22.0]	0.024	0.016	0.025	0.030	0.100
	[22.0 – 23.0]	0.043	0.027	0.047	0.059	0.195
	[23.0 – 24.0]	0.074	0.044	0.083	0.108	0.344
W3	[19.0 – 20.0]	0.011	0.007	0.009	0.010	0.023
	[20.0 – 21.0]	0.016	0.009	0.013	0.016	0.049
	[21.0 – 22.0]	0.025	0.014	0.022	0.033	0.101
	[22.0 – 23.0]	0.040	0.023	0.043	0.066	0.189
	[23.0 – 24.0]	0.062	0.036	0.079	0.123	0.324
W4	[19.0 – 20.0]	0.008	0.006	0.008	0.010	0.019
	[20.0 – 21.0]	0.012	0.008	0.013	0.016	0.044
	[21.0 – 22.0]	0.023	0.013	0.024	0.031	0.097
	[22.0 – 23.0]	0.044	0.022	0.046	0.061	0.189
	[23.0 – 24.0]	0.079	0.036	0.083	0.111	0.332

Table 11: Internal photometric errors per magnitude bins derived for each CFHTLS Wide field. The magnitudes of the objects detected in two stacks are compared. For each pair of stacks, a mean offset and dispersion is calculated from the magnitude differences of each pair of objects. Assuming a gaussian distribution of errors, the listed values are estimated as the dispersion divided by $\sqrt{2}$.

Regnault et al. (2009) (and updated to the latest calculation of the SNLS Team) for u^* , g , r , i and z , and from CFHT (private communication) for the y band:

$$\begin{aligned}
 u_{\text{CFHTLS}} - u_{\text{SDSS}} &= -0.189 \times (u - g)_{\text{SDSS}} - 0.099 , \\
 g_{\text{CFHTLS}} - g_{\text{SDSS}} &= -0.158 \times (g - r)_{\text{SDSS}} + 0.024 , \\
 r_{\text{CFHTLS}} - r_{\text{SDSS}} &= -0.071 \times (r - i)_{\text{SDSS}} + 0.000 , \\
 i_{\text{CFHTLS}} - i_{\text{SDSS}} &= -0.102 \times (r - i)_{\text{SDSS}} + 0.024 , \text{ for the } i \text{ (i.9701) filter,} \\
 y_{\text{CFHTLS}} - y_{\text{SDSS}} &= -0.020 \times (r - i)_{\text{SDSS}} + 0.032 , \text{ for the } y \text{ (i.9702) filter, and} \\
 z_{\text{CFHTLS}} - z_{\text{SDSS}} &= +0.069 \times (i - z)_{\text{SDSS}} + 0.030 .
 \end{aligned} \tag{13}$$

These equations are mean transformation equations that apply over the MegaCam camera. Note that they are different from those used in the previous T0006 release. The CFHTLS and SDSS sources have been cross-identified using the public SDSS catalogue (Data Release DR8; <http://www.sdss.org>) and the `MAG_AUTO` magnitudes of the CFHTLS M-SC catalogue. The CFHTLS and SDSS photometry data have been compared using a well-defined common sample bright stars in unmasked regions of CFHTLS stacks. For W1, W2 and W3, only unsaturated stellar objects with $17 < i < 21$ (i.e the limiting




Figure 34: Magnitude errors as a function of magnitude derived from sources from overlapping regions for W1, W2, W3 and W4 (top left and top right and bottom left and bottom right fields respectively).

magnitude for a clear star/galaxy separation) located inside a cross-identification radius of 2" have been used. For W4, which is more contaminated by very bright stars, we only used stellar sources ranging within $17 < i < 20$.

The mean offset for the m -band inside a MegaCam field, δ_m , is calculated using a weighted mean :

$$\delta_m = \frac{\sum_i w_i (m_{\text{CFHTLS}_i} - m_{\text{SDSS}_i})}{\sum_i w_i}, \text{ with } w_i = \frac{1}{\sigma_{\text{CFHTLS}_i}^2 + \sigma_{\text{SDSS}_i}^2}, \quad (14)$$

where i is the index for each common star, m_i denote the magnitudes, and σ_i the magnitude errors as listed in the CFHTLS and the SDSS catalogues. Note that the offsets calculated here are averaged over a full MegaCam field. As shown by the SuperNovae Legacy Survey (SNLS) team, these offsets can vary from CCD to CCD and produces some residuals on CCD scale (refer to section XXX for more detailed analysis on the illumination).

From this star sample, we define two different mean magnitude offset values, depending on the angular scale over which the offset is averaged:

- the 115 mean offsets, $\delta_{m=u^*,g,r,i/y,z}$, averaged over a MegaCam field. They are computed for all stacks with common stars between CFHTLS and SDSS. The offset values are listed in the appendix as well as in the synoptic table; PUT THE BIG TABLES IN THE APPENDIX




Figure 35: Distributions of photometric offsets, $\delta_{m=u^*,g,r,i/y,z}$, between CFHTLS Wide and SDSS-DR8 for W1, W2, W3 and W4.

- the W1, W2, W3 and W4 offsets, averaged over each wide field, $\langle \delta_{m=u^*,g,r,i/y,z} \rangle$. They are summarized in Table 7 and in the histograms of Figure 35;

The external photometric errors are then derived by applying the 115 mean offset values for each tile tiles and by computing the *rms* of the distribution. The results are presented in the next section following the discussion of magnitude offsets.

Fig. 35 separates W1, W2, W3 and W4. There is no large visible difference between the four fields. In particular the histograms confirm that the *g* and *r* mean and *rms* offset values are small and stable from field to field. We therefore consider that *the g and r band offsets as most reliable and the i/y as reliable, although in all cases, the g, r and i/y offsets are small and close to the rms internal photometric errors.*

The distribution of photometric offsets with SDSS-DR8 are similar in all bands and closer to gaussians than in the previous releases. This is an indication of the errors being dominated by statistical dispersion from magnitude measurements. As expected the distributions are broader in *u** and *z* bands than in *g, r, i/y* bands. The *u*-band distributions show a significant variation of the mean offset. It is confirmed from the offset reported in Table 7.

The spatial distribution of mag. offset are shown on the maps of Fig. 36. They do not reveal significant systematic gradients over the Wide fields, in any filters.

In summary, the T0007 Wide photometric data show a small, marginally significant, offset between the CFHTLS and SDSS magnitudes in *g* and *r* bands, a small offset in *i* and *y* that seems more significant than for the *g* and *r* filters, a significant offset in *z*-band, and a significant offset in *u**. The patch-to-patch

Wide field	External magnitude offsets with respect to SDSS				
	δ_{u^*} [mag.]	δ_g [mag.]	δ_r [mag.]	δ_i [mag.]	δ_z [mag.]
W1	-0.044/-0.038	0.000/0.000	0.013/0.012	-0.012/-0.014	0.020/0.020
W2	-0.064/-0.066	-0.008/-0.009	0.006/0.006	-0.007/-0.004	0.019/0.021
W3	-0.038/-0.037	0.003/0.004	0.010/0.010	-0.013/-0.013	0.001/0.001
W4	-0.055/-0.053	0.009/0.010	0.010/0.012	-0.001/0.000	0.022/0.021

Table 12: Mean magnitude offsets, $\langle \Delta_{m=u^*,g,r,i/y,z} \rangle$, between the CFHTLS and the SDSS R8 surveys, using the whole sample of common stars found in W1, W2, W3 and W4. The mean offsets for W1, W3 and W4 are also given in Table 7, The distribution over the 115 fields are shown on Fig. 35.

and tile-to-tile scatters of the offset values are large in u^* and z bands.

The larger variation in the u^* -band offset is a direct consequence of the calibration method. When comparing the magnitudes of the SNLS standard stars on the two fields where they overlapp with the SDSS-DR8, (D2 and D3) similar offsets are seen (see Deep calibration) :

- less than 1% offset in $g, r, i,$
- 0.055/0.033 offset in u^*
- -0.011/0.001 offset in z

On the only field covered by SNLS, SDSS and Wide, the calibration are in good agreement with a maximum offset of 1% in i -band.

The origin of the scatter in the mean offset in u^* -band seen both on SNLS and in the CFHTLS remains unclear. The color equation between SDSS and SNLS is the less tested from all filters. It contains the largest color term and could be more sensible to the stellar populations chosen for the photometric comparison. As shown in the next section, stellar population variations (in metallicity) can induce rather large (several percent) differences in colours.




Figure 36: Maps of photometric offsets between CFHTLS Wide and SDSS R6, based on stars common to both surveys (115 Wide stacks). Each square represents a $1^{\circ} \times 1^{\circ}$ tile (or a stack) of the CFHTLS Wide. The top panels show, from left to right, the u^* , g , r , i/y and z magnitude offsets for W1. The middle panels are the same for W3, and the bottom for W4. The offsets being derived from CFHTLS-SDSS color transformations averaged over a MegaCam field, there are some residuals on CCD scales because the CCDs do not have exactly the same response. The residuals are documented in the illumination correction section,

Wide field	External <i>rms</i> errors with respect to SDSS				
	σ_{u^*} <i>rms</i> [mag.]	σ_g <i>rms</i> [mag.]	σ_r <i>rms</i> [mag.]	σ_i <i>rms</i> [mag.]	σ_z <i>rms</i> [mag.]
W1	0.016	0.008	0.009	0.006	0.010
W2	0.011	0.005	0.004	0.005	0.012
W3	0.009	0.005	0.005	0.004	0.005
W4	0.009	0.003	0.007	0.006	0.005

Table 13: External *rms* errors of the CFHTLS T0007 u^*, g, r, i and z -band Wide surveys. They are derived from the variance of the magnitude offset distributions between the SDSS R6 and the CFHTLS, in the W1, W3 and W4 fields. The error estimates only use 115/171 wide fields. In contrast with the internal errors, most common source locii are outside the noisy overlapping regions, and the selected stellar sources used for the CFHT-SDSS comparison are brighter.

4.4.4 External photometric errors

The external photometric errors are derived from the *rms* of the mean CFHTLS-SDSS magnitude offset values, $\delta_{m=u^*,g,r,i/y,z}$, in each Wide field separately. They are measured by adding the 115 offsets to CFHTLS-SDSS common sources of each relevant tile

and then by computing the *rms* of the CFHTLS-SDSS residual over the tile.

The external errors are quoted for each Wide in Table 13. As expected the g , r and i -bands are on the average better than the u^* and z . W1 seems slightly worse than W2, W3 and W4, probably due to contamination by several outliers reported in the previous section. The overall external field to field calibration is around 1.5% in u^* and z , and below 1.0% in g, r and i/y .

4.4.5 CFHTLS Wide Photometric precision

The systematic photometric precision in the CFHTLS-Wide T0007 calibration (or field to field scatter) can be measured using :

- the dispersion of the tile magnitude offsets with SDSS (section 4.4.4 and table 13)
- the dispersion of the the magnitude offsets between adjacent fields measured in the overlapping regions (section 4.4.2 and table 10)

These two measurements are in good agreement and show field to field scatters of :

- 1.5% in u^* and z bands
- 1% in g, r and i/y bands

WRITE A PARAGRAPH ON MEASUREMENT ERRORS ON STARS

4.4.6 Stellar color-color plots

The nearly blackbody emission spectra of stars places them in a narrow line in optical and infrared color-color space. Under the assumption that stellar locii in the $ugriz$ color space are intrinsically universal, one can identify this locus and use it to calibrate the colors (and magnitudes) of the CFHTLS sources. As in previous releases, a comparison between the CFHTLS point-source colours and stellar model tracks have been used in order to assess the stability of survey photometry from tile to tile and across the whole Wide area.

The stellar color-color locii are derived from a sample of well-defined bright stars selected from the T0007 merged catalogues. Only unsaturated objects with $17 < i < 21$ and located in unmasked regions are considered (i.e. objects with $\text{FLAG}==1$. The MAG_AUTO as well as the MAG_SNLS magnitudes of the sources are plotted in the $(u * -g)/(g - r)$, $(g - r)/(r - i)$ and $(r - i)/(i - z)$ color-color diagrams with the color tracks of the stellar models (Pickles, 1998).

We would like to remind the reader that the Pickles stellar library is not complete in the $(T_{eff}, \log g)$ stellar parameter space, especially in the $\log g$ range. In addition, the stellar library covers only stars with *solar metallicity*. As shown in Schultheis et al. (2006), the CFHTLS fields are a mixture of different stellar populations with different metallicities, i.e. the thin disc, the thick disc and the halo population. The effects of metallicity is largest in the $(u - g)$ colour and therefore systematic offsets compared to Pickles are to be expected. Sesar et al. (2011) studied the metallicities of the CFHTLS Wide fields and they found clearly a mean metallicity below solar ($[\text{Fe}/\text{H}] = -1.5$). However, the metallicity variation over the Wide fields is still to be determined.

To illustrate the effect of metallicity, Figure 37 shows the Basel 3.1 model track (Westera et al., 2002) with $[\text{Fe}/\text{H}] = -1.0$ (i.e. low metallicity) in comparison to the Pickles models (bottom panels) with solar metallicity. While we see clearly an offset in $(u - g)$ and $(g - r)$ from the Pickles stars, this offset is completely disappears using the Basel 3.1 $[\text{Fe}/\text{H}] = -1.0$ track. We therefore conclude that these offsets seen with respect to the Pickles stars do not represent a photometric calibration problem but can be explained from metallicity variations. Furthermore, realistic models of the galaxy indicate that the variations in metallicity expected in fields of size comparable to the CFHTLS wide patches could correspond to displacements in colour-colour space of a few percent or larger,

4.4.7 Colour offsets between CFHTLS and SDSS

In the previous CFHTLS release (T0006), the stellar locus in the Wide tiles has been used to recalibrate the photometry and improve the final field to field scatter. The differences between the locii of CFHTLS and SDSS stars in colour-colour tracks can be used to determine the color offsets, $\Delta_{m-m'}^{SLR}$ between the two surveys. However, as we have seen in the previous Sections, the expected percent-level photometric precision of the CFHTLS Wide survey now exceeds the metallicity-induced field-to-field variations in colour which we would expect in a survey the size of the CFHTLS. Consequently, this raises doubts concerning the ability of the “Stellar Locus Regression” (SLR) fitting techniques to enable further reductions in the photometric scatter of the CFHTLS wide.

To test this, we checked the potential improvement on the color offsets compared to SDSS using the SLR recalibration. First, we computed the color offsets with respect to the SDSS reference catalog $\delta_{m-m'}$. We then computed the correcting color offsets from the SLR method as described in the T0006 documentation $\Delta^{\text{SLR}_{m-m'}}$. We finally compared the RMS of the color offsets across the Wide patch compared to SDSS before and after the application of the SLR corrections. Before re-calibration, the scatter in $(u - g)$, $(g - r)$, $(r - i)$ and $(i - z)$ with respect to the transformed SDSS stellar locus is 0.011, 0.005, 0.008




Figure 37: Comaprison of one CFHTLS field with the Pickles stellar library (lower panel) and the Basel 3.1 stellar library using $[Fe/H]=-1.0$ (upper panel).

and 0.008 respectively; after the application of the SLR regression, this becomes 0.014, 0.011, 0.010 and 0.008.

The use of SLR clearly makes no improvement to our W3 photometric calibration, and demonstrates in our case the SLR calibration is limited to a precision larger than 1%. Without a detailed knowledge of the stellar population variations across the Wide patches, it is difficult to see how this could be improved further. Considering the lack of improvement in the recalibration of W3 using the SLR, we chose not to use this method in T0007.

4.5 Astrometric accuracy

The astrometric accuracy is measured in two different ways.

- Firstly, at the end of the global astrometric calibration process, by comparing the astrometric positions of sources in all single CFHTLS images with sources in an internal and an external reference catalogue. This *astrometric calibration error* represents the upper limit for the astrometric accuracy of the survey.
- Secondly, by comparing position of sources inside each CFHTLS Wide stack with respect to an external reference catalogue. This *astrometric accuracy of CFHTLS stacks* measures the final absolute astrometric accuracy of each stack and their corresponding catalogues.

Field	RA diff. ["]	DEC diff. ["]
W1	+0.014	+0.010
W2	-0.035	-0.025
W3	+0.011	+0.010
W4	-0.026	-0.023

Table 14: Mean RA and DEC differences between the external errors in each field and the mean external errors, averaged over the four Wide fields.

The astrometric calibration of the Wide survey is described in Section 3.5.

4.5.1 Astrometric calibration errors

The mean internal astrometric calibration errors are derived using the cross-identifications of sources inside the overlapping regions of adjacent fields (see Fig. 20). All single input MegaCam Wide, Pre-Wide (see Fig. 20) and short photometric exposures images remaining after selection are included. The cross-identifications and the internal errors are obtained during the SCAMP calibration process. The calibrations outputs of the Wide fields W1, W2, W3 and W4 are available from the synoptic table.

Over the whole survey, the mean internal *rms* error is

$$\sigma_{\text{RA}} = 0.0279'' \pm 0.0049'', \text{ and , } \sigma_{\text{DEC}} = 0.0256 \pm 0.0057'', \quad (15)$$

where the reported errors are not the SCAMP internal errors, but the mean absolute difference of the internal errors between the four Wide fields and the mean error values. Since the four fields are calibrated independently, the errors quoted above are approximate; the internal errors for W1, W2, W3 and W4 are given in Table 7.

For each field, the mean *rms* external RA and DEC errors of the astrometric solution are derived during the SCAMP calibration process, using the cross-identification of sources inside each single CFHTLS Wide image with the 2MASS catalogue. The mean external calibration errors over the whole survey are $\sigma_{\text{RA}} = 0.239''$ and $\sigma_{\text{DEC}} = 0.232''$. They roughly correspond to the internal errors of the 2MASS catalogue.

The mean scatter from one Wide field to another is uncertain, because the CFHTLS is comprises only four independent fields. It can be estimated from the offsets of the mean external errors of each field separately with respect to the mean value over the four fields. The offsets are listed in Table 14. The amplitudes are very close to the internal astrometric calibration errors of the Wide fields, so we conclude that the internal astrometric accuracy for the CFHTLS wide does not have significant field-to-field scatter. These errors values are lower then the astrometric internal errors, so we do not expect significant differences in the astrometric calibrations from field to field.

4.5.2 Absolute astrometric accuracy of CFHTLS stacks

The astrometric accuracy inside each stack is measured by comparing the source positions in the final CFHTLS catalogues produced from all stacks with the 2MASS source catalogue. The results are given in the QualityFITS-out (QFITS-out) evaluation web pages. The mean external astrometric errors inside each stack are given by the *rms* of the the positions of each source inside a stack with respect to an external reference catalogue (2MASS). The results are listed in Table 15. They are in excellent agreement with the external errors from the internal astrometric calibration.

To control whether systematic offsets of source coordinates are present inside each Wide catalogue, we inspected and averaged over all stacks composing each Wide field the mean offsets $\langle \Delta RA_{CFHTLS-2MASS} \rangle$ and $\langle \Delta DEC_{CFHTLS-2MASS} \rangle$, between the the CFHTLS and 2MASS positions inside a stack. The significance of the offsets is given by comparing the *rms* of the average of the mean offset value with the *rms* of the mean external errors, averaged over the number of field per Wide tile (72 for W1, 25 for W2, 49 for W3 and 25 for W4). The results are listed in Table 15 and detailed in Fig. 38, 39, 40, and 41, for the four Wide patches, globally and as function of filter. All fields with the exception of W1 show small offsets. They are perceptible in both amplitude and direction and in all filters, but vary from a Wide tile to another. The amplitude is nevertheless small (about 1/10 of the CFHTLS pixel size) and never larger than the $1-\sigma$ *rms* offset error, the $1-\sigma$ *rms* error of the external error or the mean internal astrometric errors of the Wide astrometric calibration. Furthermore, we do not see significant chromatic effects.

Figures 38 to 41 also shows fewer outlier stacks with large astrometric offsets with respect to the 2MASS source positions. The most extreme fields are listed in the next sections. However, the number of outliers with an amplitude of the deviation of more than $3-\sigma$ deviations in at least one direction is close to Gaussian expectations (9/360 for W1, 1/245 for W3, 0/125 for W2 and W4).

Wide Field - Filter	Wide-averaged MegaCam-mean astrometric offset with respect to 2MASS	$\langle \Delta \text{RA}_{\text{CFHTLS-2MASS}} \rangle$ ["]	$\langle \Delta \text{DEC}_{\text{CFHTLS-2MASS}} \rangle$ ["]	σ_{RA} ["]	σ_{DEC} ["]	Wide-averaged MegaCam mean external <i>rms</i> astrometric error
W1 - all bands	0.009 ± 0.028	0.004 ± 0.029	0.253 ± 0.019	0.242 ± 0.021		
W1 <i>u</i> -band	0.006 ± 0.028	-0.004 ± 0.029	0.237 ± 0.019	0.227 ± 0.023		
W1 <i>g</i> -band	0.013 ± 0.028	0.002 ± 0.029	0.254 ± 0.016	0.244 ± 0.019		
W1 <i>r</i> -band	0.009 ± 0.028	0.008 ± 0.029	0.259 ± 0.014	0.247 ± 0.016		
W1 <i>i</i> -band	0.011 ± 0.027	0.006 ± 0.028	0.252 ± 0.014	0.243 ± 0.017		
W1 <i>y</i> -band	0.002 ± 0.028	0.015 ± 0.027	0.272 ± 0.014	0.254 ± 0.020		
W1 <i>z</i> -band	0.008 ± 0.027	0.007 ± 0.028	0.260 ± 0.017	0.248 ± 0.019		
W2 - all bands	-0.006 ± 0.018	0.015 ± 0.013	0.204 ± 0.014	0.207 ± 0.013		
W2 <i>u</i> -band	-0.008 ± 0.017	0.014 ± 0.014	0.183 ± 0.009	0.186 ± 0.011		
W2 <i>g</i> -band	-0.005 ± 0.018	0.015 ± 0.014	0.208 ± 0.008	0.211 ± 0.007		
W2 <i>r</i> -band	-0.005 ± 0.019	0.015 ± 0.012	0.211 ± 0.009	0.213 ± 0.008		
W2 <i>i</i> -band	-0.004 ± 0.019	0.016 ± 0.013	0.207 ± 0.007	0.210 ± 0.006		
W2 <i>y</i> -band	-0.004 ± 0.020	0.020 ± 0.008	0.224 ± 0.009	0.228 ± 0.010		
W2 <i>z</i> -band	-0.007 ± 0.019	0.013 ± 0.013	0.211 ± 0.008	0.212 ± 0.008		
W3 - all bands	-0.002 ± 0.018	-0.013 ± 0.024	0.250 ± 0.017	0.242 ± 0.016		
W3 <i>u</i> -band	-0.003 ± 0.018	-0.005 ± 0.022	0.235 ± 0.014	0.225 ± 0.014		
W3 <i>g</i> -band	-0.002 ± 0.019	-0.011 ± 0.022	0.248 ± 0.015	0.242 ± 0.012		
W3 <i>r</i> -band	-0.002 ± 0.018	-0.016 ± 0.023	0.258 ± 0.013	0.249 ± 0.012		
W3 <i>i</i> -band	-0.002 ± 0.018	-0.016 ± 0.022	0.246 ± 0.014	0.242 ± 0.013		
W3 <i>y</i> -band	0.008 ± 0.018	-0.047 ± 0.020	0.275 ± 0.016	0.269 ± 0.012		
W3 <i>z</i> -band	-0.002 ± 0.018	-0.014 ± 0.023	0.258 ± 0.012	0.250 ± 0.012		
W4 - all bands	0.015 ± 0.019	0.010 ± 0.018	0.213 ± 0.015	0.209 ± 0.017		
W4 <i>u</i> -band	0.014 ± 0.019	0.009 ± 0.017	0.193 ± 0.012	0.186 ± 0.015		
W4 <i>g</i> -band	0.015 ± 0.020	0.010 ± 0.018	0.218 ± 0.010	0.213 ± 0.012		
W4 <i>r</i> -band	0.017 ± 0.019	0.010 ± 0.018	0.222 ± 0.011	0.217 ± 0.013		
W4 <i>i</i> -band	0.014 ± 0.020	0.010 ± 0.021	0.217 ± 0.011	0.215 ± 0.014		
W4 <i>y</i> -band	0.020 ± 0.015	0.006 ± 0.014	0.221 ± 0.009	0.217 ± 0.010		
W4 <i>z</i> -band	0.012 ± 0.018	0.011 ± 0.018	0.214 ± 0.012	0.212 ± 0.013		

Table 15: Mean astrometric position accuracy of each Wide stack. The Wide-averaged statistics is the ensemble average over all stacks of the mean CFHTLS-SDSS astrometric offset values computed for each stack (MegaCam mean), separately

4.6 Outliers, stacks with exceptions or anomalies

Several images show unusual properties with respect to the bulk sample of stacks. This is the case for the 32 *y*-band stacks that are expected to have slightly different (photometric) properties compared to the other 139 *i*-band tiles.

The most common technical anomaly is an amplifier failure during an observing sequence. Since all CCDs have two outputs, several images show missing data from a half or a full CCD area. Usually, each observing sequence is done only once, so the data from the missing CCD cannot be recovered. However, since the CCD failures are intermittent, the *r*-band observations which have been split into two observing sequences normally do not experience this missing data problem. We note furthermore that many of the pointings originally affected by this problem have been re-observed by in Director's Discretionary Time. (Images with more than one full CCD missing have been rejected during the image selection stack.)

Problematic T0007 stacks are listed in Tables 16 and 17, with a short description. None of these problems are critical for the scientific exploitation of the survey, but there are some CCD-size regions of the CFHTLS Wide where one or two filters are missing.




Figure 38: Mean RA-DEC offsets between the CFHTLS W1 and the 2MASS catalogues. The offset is derived from the ensemble average over all Wide W1 stacks of the mean offset inside each W1 stack. The top left plot shows the offset using all filters together (360 stacks). The other plots show the offsets in each filter (72 stacks per filter). The red dots show the mean offset in each stack. The green dot show the ensemble average of all stacks. The magenta square shows the MegaCam pixel size (0.186'').




Figure 39: Mean RA-DEC offsets between the CFHTLS W2 and the 2MASS catalogues (see comments on the caption of Fig. 38).




Figure 40: Mean RA-DEC offsets between the CFHTLS W3 and the 2MASS catalogues (see comments on the caption of Fig. 38).




Figure 41: Mean RA-DEC offsets between the CFHTLS W4 and the 2MASS catalogues (see comments on the caption of Fig. 38).

W Cartesian Ident name	CFHTLS Ident name	CFHTLS Special filter	VIPERS images	Comments
W1(-4 - 4)	020241-104400	y-band observations	y-band exp. time is 7380 s.	
W1(-3 - 4)	020631-104400	y-band observations		
W1(-2 - 0)	021021-070000	y-band observations		radial astrometric offset around 0.090" in all bands
W1(-2 - 4)	021021-104400	y-band observations		
W1(+2 - 0)	022539-070000	y-band observations		
W1(+2 + 1)	022539-060400	y-band observations		
W1(+2 + 2)	022539-050800	y-band observations		
W1(+2 + 3)	022539-041200	y-band observations		u^* -band and z -band: CCD#03 missing ;
W1(-1 - 4)	021410-104400	y-band observations		
W1(-1 - 4)	021800-104400	y-band observations		
W1(+1 - 4)	022150-104400	y-band observations		
W1(+1 - 1)	022150-075600	y-band observations		
W1(+1 + 1)	022150-060400	y-band observations		
W1(+1 + 3)	022150-041200	y-band observations		i -band : two 1/2 CCD missing (CCD#07 and CCD#11) u^* -band radial astrometric offset 0.084"
W1(+2 - 4)	022539-104400	y-band observations		
W1(+3 - 4)	022929-104400	y-band observations		
W1(+3 - 0)	022929-070000	y-band observations		g -band and i -band : CCD#03 missing ;
W1(+3 + 1)	022929-060400	y-band observations		
W1(+3 + 2)	022929-050800	y-band observations		g -band, y -band
W1(+3 + 3)	022929-041200	y-band observations		g -band and i -band : CCD#03 missing
W1(+4 - 4)	023319-104400	y-band observations		g -band and i -band : CCD#03 missing ;
W1(+4 - 0)	023319-070000	y-band observations		u, g and i -band radial astrometric around 0.079"

Table 16: CFHTLS Wide stacks with exceptions or anomalies.

W Cartesian Ident name	CFHTLS Ident name	Special filter	VIPERS images	Comments
W1(+4 + 1)	023319-060400	g-band		
W1(+4 + 2)	023319-050800	g-band		
W1(+4 + 3)	023319-041200			<i>i</i> -band : CCD#03 missing
W2(-1 + 3)	085011-012700			<i>g</i> -band : CCD#03 missing
W2(+1 + 1)	085749-031900	y-band observations		
W2(+3 + 1)	090526-031900			<i>g</i> -band : CCD#03 missing
W2(+3 + 2)	090526-0222300			<i>g</i> -band : CCD#03 missing
W2(+3 + 3)	090526-012700			<i>g</i> -band : CCD#03 missing
W2(+2 + 2)	090137-0222300	y-band observations		
W3(-3 + 1)	135846+552631	y-band observations		
W3(-2 - 0)	140525+543031			
W3(-2 - 1)	140540+533431	y-band observations		
W3(-2 + 1)	140509+552631	y-band observations		
W3(-2 + 3)	140433+571831	y-band observations		
W3(-1 + 3)	141113+571831	y-band observations		
W3(-0 - 1)	141754+533431			<i>y</i> -band radial astrometric offset 0.077"
W3(+3 - 1)	143615+533431	y-band observations		<i>g</i> -band seeing anomaly: 1.045"
W3(+3 + 2)	143728+562231	y-band observations		
W4(+1 - 1)	221706+002300			
W4(-1 - 1)	220930+002300	y-band observations		
W4(-1 + 1)	220930+021500	y-band observations		
W4(-1 + 2)	220930+031100	y-band observations		
W4(-1 + 3)	220930+040700	y-band observations		
W4(-2 + 2)	220542+031100	y-band observations		
W4(-2 + 3)	220542+040700	y-band observations		
W4(-3 + 3)	220154+040700	y-band observations		

Table 17: CFHTLS Wide stacks with exceptions or anomalies (cont'd).

Field name	Reference center		Comment
	RA (J2000)	DEC (J2000)	
D1	02:25:59.00	-04:29:40	
D2	10:00:28.00	+02:12:30	COSMOS u^* data included
D3	14:19:27.00	+52:40:56	
D4	22:15:31.00	-17:43:56	

Table 18: Location of the CFHTLS Deep fields. All fields cover 1 deg^2 and are taken in all six filters.

5 Description of the CFHTLS T0007 Deep survey

5.1 Overview

The CFHTLS deep survey is composed of four independent MegaCam pointings in the D1, D2, D3 and D4 fields (see Table 18), in all six MegaCam filters. It is composed of 48 u^* , g , r , i , y and z stacks and 8 chi2 images (that is 112 images including the weight-maps). There are two types of stacks per Deep field; the 85% best seeing images (hereafter the Dk -85 sample, $k = 1 - 4$) and the 25% best seeing images (Dk -25). The two Dk series of stacks have exactly the same centre positions.

The image selection criteria applied to the 10632 CFHTLS images for the production of the CFHTLS Deep survey has already been described in Section 3.4. Note that in addition to the CFHTLS L1 and L04 images taken between May 26, 2003 and May 26, 2003, the D2- u^* field contains images taken by the COSMOS consortium (Capak et al., 2007).

The T0007 CFHTLS Deep survey contains 8876 images. The number of images in each stack are 8504 Deep images are combined into T0006 stacks; 617 u^* , 1437 g , 1902 r , 1979 i , 682 y and 1887 z .

All stacks have the same pixel scale and cover exactly $1 \times 1 \text{ deg}^2$ (19354×19354 pixels of $0.1860''$). For all fields with the exception of D2- u^* the stacks are only composed of images that are part of a CFHTLS Deep L01 and L03 observing sequence and that are within a radius of 3 arc-minutes with respect to the CFHTLS Deep center fields. For the D2- u^* , we included all u^* -COSMOS that passed the selections, without restriction on the radial distance.

The Deep stacks combine sets of images obtained during sequences of short exposures (few hundreds of seconds). Each exposure is followed by a small shift of the telescope in order to better subtract the sky background during the image processing steps and to fill the physical gaps between CCDs. The shifts are within a box of $4'$ in DEC and 3 arcminutes in RA. The D2- u^* stacks COSMOS data that are shifted by $30'$ in both RA and DEC directions in order to pave the $1.4 \times 1.4 \text{ deg}^2$ of the COSMOS survey. These images are combined with CFHTLS D2- u^* observations and cut to provide the $1 \times 1 \text{ deg}^2$ centered on the CFHTLS D2.

The centre position each stack is predefined. The coordinates of a stack center position are given in Table 18, and are exactly the same for all filters. D1, D2, D3 and D4 are therefore composed of a complete set of u^* , g , r , i , y and z images of 1 deg^2 each.

Tables 19 and 20 summarise the properties of Deep median-combined stacks; the characteristics of the sigma-combined stacks are given in Tables 21 and 22. (Note that the exposure time u^* -band does not

accurately express the integration time per pixel because most COSMOS images are shifted by $30'$ and only fill one quadrant of the u^* -band stacks. The D2- u^* corresponds to the innermost regions of Fig. 45, delimited by the black contours. Table 24 describes each sub-field in more detail).

5.2 Astrometric accuracy

The astrometric accuracy is derived in the same way as for the Wide survey. We refer to the beginning of Section 4.5 for a description of the method. The Deep analysis is however simpler than the Wide because there is only one single position per field. The astrometric calibration of the Deep fields is detailed in Section 3.5, so we only focus on the accuracy in this section.

The results of the internal and external error analyses are given in Tables 19 and 20. The internal errors have been measured by SCAMP, from the astrometric solutions of each Deep field, for each filter separately. In contrast, the external errors quoted in Tables 19 and 20 are not the values derived from the astrometric solutions. They are computed separately as well, but after the production of the Deep images, in order to get the true astrometric errors of sources in each stack. The reference external catalogue is 2MASS, and the external errors found are very similar to the Wide survey.

On the average, the mean internal astrometric *rms* errors in the Deep fields are

$$\sigma_{\text{RA}} = 0.056'' \pm 0.011'', \text{ and , } \sigma_{\text{DEC}} = 0.056 \pm 0.011'', \quad (16)$$

and the mean external errors

$$\sigma_{\text{RA}} = 0.283'' \pm 0.017'', \text{ and , } \sigma_{\text{DEC}} = 0.232 \pm 0.014'', \quad (17)$$

where, the dispersions are the *rms* errors. Since the four fields are calibrated independently, the values quoted above are just rough estimates; the errors for D1, D2, D3 and D4 are given in Tables 19 and 20. The rather large scatter in the internal errors is due to the different ways each Deep field has been calibrated (either using an internal catalogue based on the i band data, or using the external 2MASS catalogue, see Section 3.5). The external astrometric errors are similar to the Wide survey and correspond to the expectations, considering the astrometric errors in the 2MASS reference catalogue.

5.3 Photometric accuracy

5.3.1 Comparison with SDSS

Wherever possible, magnitude offsets between common stars in CFHTLS and SDSS have been measured. SDSS magnitudes are first converted into the CFHTLS system using the MegaCam-SDSS color transformation equations of Regnault et al. (2009).

The offsets are quoted in Tables 19 and 20 and in the synoptic table. Only fields D2 and D3 have sources in common with SDSS, so the interpretation of these data in terms of systematic offsets between the two surveys should be made carefully. Nevertheless, the offsets are indeed similar to the means $\langle \Delta_{m=u^*,g,r,i/y,z} \rangle$ (Table 12) or $\langle \delta_{m=u^*,g,r,i/y,z} \rangle$ (Table 7) found for the Wide fields. In both Deep and Wide fields, the CFHTLS-SDSS comparisons are made using stars with $17 < i < 21$. The signal-to-noise ratio of all common stars on the Deep fields is much higher than for the Wide, so it is reassuring to find that the offsets in all filters are similar between the Deep and Wide. The consistency between the Deep and Wide offsets is an indication there may be a small systematic residual in the photometric calibration.

Field	Parameter	u^*	g	r	i	y	z
D1-25	Nb images	29	96	134	138	37	142
	Exp. time [s]	19142	23106	42429	66490	13961	51129
	Seeing ["]	0.72	0.66	0.62	0.62	0.52	0.56
80% Compl. (stellar)	26.24 ± 0.10	26.31 ± 0.10	25.92 ± 0.10	25.43 ± 0.10	25.39 ± 0.10	25.11 ± 0.10	
80% Compl. (extended)	25.43 ± 0.10	25.48 ± 0.10	24.94 ± 0.10	24.57 ± 0.10	24.32 ± 0.10	23.98 ± 0.10	
Int. astrom. err.	(0.042",0.042")	(0.049",0.048")	(0.048",0.048")	(0.047",0.047")	(0.041",0.040")	(0.050",0.050")	
Ext. astrom. err.	(0.25",0.23")	(0.26",0.25")	(0.25",0.24")	(0.25",0.24")	(0.27",0.25")	(0.26",0.24")	
Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.02	0.03
D2-25	Nb images	128	83	114	107	60	104
	Exp. time [s]	~25000	18680	34208	51808	24483	37446
	Seeing ["]	0.75	0.64	0.58	0.57	0.57	0.56
80% Compl. (stellar)	26.26 ± 0.10	26.31 ± 0.10	25.91 ± 0.10	25.51 ± 0.10	25.65 ± 0.10	25.14 ± 0.10	
80% Compl. (extended)	25.55 ± 0.10	25.42 ± 0.10	24.93 ± 0.10	24.63 ± 0.10	24.55 ± 0.10	24.07 ± 0.10	
Int. astrom. err.	(0.070",0.068")	(0.068",0.065")	(0.065",0.063")	(0.062",0.060")	(0.054",0.052")	(0.024",0.024")	
Ext. astrom. err.	(0.21",0.21")	(0.23",0.22")	(0.22",0.22")	(0.22",0.22")	(0.23",0.22")	(0.21",0.22")	
Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.02	0.03
CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.051	-0.005	+0.010	+0.003	-0.004	+0.004	
D3-25	Nb images	29	96	134	138	37	142
	Exp. time [s]	19806	20717	36623	64425	19209	45023
	Seeing ["]	0.75	0.67	0.63	0.61	0.61	0.54
80% Compl. (stellar)	26.12 ± 0.10	26.29 ± 0.10	25.76 ± 0.10	25.48 ± 0.10	25.42 ± 0.10	25.07 ± 0.10	
80% Compl. (extended)	25.30 ± 0.10	25.44 ± 0.10	24.90 ± 0.10	24.58 ± 0.10	24.46 ± 0.10	23.94 ± 0.10	
Int. astrom. err.	(0.060",0.058")	(0.065",0.064")	(0.065",0.064")	(0.064",0.063")	(0.054",0.053")	(0.075",0.074")	
Ext. astrom. err.	(0.23",0.23")	(0.25",0.25")	(0.25",0.25")	(0.25",0.25")	(0.26",0.25")	(0.25",0.25")	
Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.02	0.04
CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.042	-0.002	+0.014	+0.003	-0.001	-0.004	
D4-25	Nb images	31	96	118	123	29	120
	Exp. time [s]	20462	23345	39066	57088	11561	43207
	Seeing ["]	0.74	0.70	0.60	0.57	0.57	0.55
80% Compl. (stellar)	26.01 ± 0.10	26.14 ± 0.10	25.76 ± 0.10	25.42 ± 0.10	25.45 ± 0.10	25.06 ± 0.10	
80% Compl. (extended)	25.22 ± 0.10	25.33 ± 0.10	24.93 ± 0.10	24.60 ± 0.10	24.28 ± 0.10	23.87 ± 0.10	
Int. astrom. err.	(0.053",0.054")	(0.063",0.062")	(0.061",0.060")	(0.060",0.060")	(0.046",0.054")	(0.067",0.066")	
Ext. astrom. err.	(0.22",0.21")	(0.23",0.23")	(0.23",0.22")	(0.22",0.22")	(0.24",0.23")	(0.23",0.22")	
Mag. int. err. [mag.]	0.04	0.02	0.02	0.02	0.02	0.02	0.03

Table 19: Summary of the 25%-best-seeing stack parameters. “80% Compl.” is the 80% completeness limit. The seeing is the median FWHM. Astrometric errors are given along the two (x,y)=(NS,EW) axes. The internal astrometric errors are derived from SCAMP calibrations, and the external errors are QualityFITS-out outputs, from the comparison of source positions on each stack with the 2MASS astrometric positions. The “Mag. int. err.” are the mean internal photometric errors from the mean of the three magnitude ranges of Table 23. The CFHTLS-SDSS $\langle \delta_m \rangle$ mag. denotes the mean magnitude offset between CFHTLS and SDSS surveys, averaged over a Deep field.

Field	Parameter	u^*	g	r	i	y	z
D1-85	Nb images	113	382	528	551	148	553
	Exp. time [s]	74590	89334	1'1876	264804	61768	199116
	Seeing ["]	0.87	0.83	0.77	0.76	0.71	0.72
80% Compl. (stellar)	26.44 ± 0.10	26.07 ± 0.10	25.61 ± 0.10	25.33 ± 0.10	25.38 ± 0.10	24.99 ± 0.10	
80% Compl. (extended)	25.72 ± 0.10	25.33 ± 0.10	24.75 ± 0.10	24.40 ± 0.10	24.48 ± 0.10	24.16 ± 0.10	
Int. astrom. err.	(0.042",0.042")	(0.049",0.048")	(0.048",0.048")	(0.047",0.047")	(0.041",0.040")	(0.050",0.050")	
Ext. astrom. err.	(0.26",0.23")	(0.26",0.25")	(0.26",0.24")	(0.25",0.24")	(0.26",0.25")	(0.25",0.23")	
Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.02	0.03
D2-85	Nb images	282	332	449	422	235	410
	Exp. time [s]	~45000	74723	135875	199655	99176	147628
	Seeing ["]	0.84	0.80	0.75	0.72	0.69	0.68
80% Compl. (stellar)	26.42 ± 0.10	26.08 ± 0.10	25.66 ± 0.10	25.30 ± 0.10	25.51 ± 0.10	25.01 ± 0.10	
80% Compl. (extended)	25.77 ± 0.10	25.33 ± 0.10	24.74 ± 0.10	24.49 ± 0.10	24.54 ± 0.10	24.15 ± 0.10	
Int. astrom. err.	(0.070",0.068")	(0.068",0.065")	(0.065",0.063")	(0.062",0.060")	(0.054",0.052")	(0.024",0.024")	
Ext. astrom. err.	(0.21",0.22")	(0.22",0.22")	(0.22",0.22")	(0.22",0.22")	(0.23",0.23")	(0.21",0.22")	
Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.03	
CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.056	-0.006	+0.011	+0.007	-0.008	-0.004	
D3-85	Nb images	118	361	483	527	192	500
	Exp. time [s]	77904	80977	146374	249016	82276	180097
	Seeing ["]	0.88	0.85	0.78	0.76	0.78	0.69
80% Compl. (stellar)	26.26 ± 0.10	26.11 ± 0.10	25.58 ± 0.10	25.32 ± 0.10	25.54 ± 0.10	25.03 ± 0.10	
80% Compl. (extended)	25.63 ± 0.10	25.29 ± 0.10	24.69 ± 0.10	24.39 ± 0.10	24.46 ± 0.10	24.13 ± 0.10	
Int. astrom. err.	(0.060",0.058")	(0.065",0.064")	(0.065",0.064")	(0.064",0.063")	(0.054",0.053")	(0.075",0.074")	
Ext. astrom. err.	(0.24",0.24")	(0.25",0.25")	(0.25",0.25")	(0.24",0.25")	(0.26",0.26")	(0.25",0.25")	
Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.04	
CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.042	-0.004	+0.016	+0.001	-0.003	-0.004	
D4-85	Nb images	121	382	472	490	116	471
	Exp. time [s]	77269	89541	155609	235153	45767	169588
	Seeing ["]	0.89	0.82	0.73	0.69	0.69	0.66
80% Compl. (stellar)	26.14 ± 0.10	25.99 ± 0.10	25.61 ± 0.10	25.35 ± 0.10	25.40 ± 0.10	25.09 ± 0.10	
80% Compl. (extended)	25.53 ± 0.10	25.34 ± 0.10	24.85 ± 0.10	24.49 ± 0.10	24.45 ± 0.10	24.17 ± 0.10	
Int. astrom. err.	(0.053",0.054")	(0.063",0.062")	(0.061",0.060")	(0.060",0.060")	(0.046",0.054")	(0.067",0.066")	
Ext. astrom. err.	(0.22",0.22")	(0.23",0.23")	(0.23",0.22")	(0.22",0.22")	(0.24",0.23")	(0.22",0.22")	
Mag. int. err. [mag.]	0.04	0.02	0.02	0.02	0.02	0.03	

Table 20: Summary of the 85% deep stack parameters. "80% Compl." is the 80% completeness limit. The seeing is the median FWHM. Astrometric errors are given along the two (x,y)=(NS,EW) axes. The internal photometric errors are from the SCAMP calibrations, and the external errors are QualityFITS-out outputs, from the comparison of source positions on each stack with the 2MASS astrometric positions. The "Mag. int. err." are the mean internal photometric errors from the mean of the three magnitude ranges of Table 23. The "CFHTLS-SDSS $\langle \delta_m \rangle$ mag." denotes the mean magnitude offset between the CFHTLS and the SDSS surveys, averaged over a Deep field.

Field	Parameter	u^*	g	r	i	y	z
D1-25	Seeing ["]	0.71	0.67	0.63	0.61	0.54	0.56
80% Compl. (stellar)	26.43 ± 0.10	26.36 ± 0.10	25.86 ± 0.10	25.55 ± 0.10	25.43 ± 0.10	25.23 ± 0.10	
80% Compl. (extended)	25.61 ± 0.10	25.54 ± 0.10	24.95 ± 0.10	24.63 ± 0.10	24.41 ± 0.10	24.14 ± 0.10	
Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.02	0.03
D2-25	Seeing ["]	0.76	0.64	0.60	0.58	0.58	0.55
80% Compl. (stellar)	26.43 ± 0.10	26.34 ± 0.10	25.94 ± 0.10	25.59 ± 0.10	25.44 ± 0.10	25.22 ± 0.10	
80% Compl. (extended)	25.74 ± 0.10	25.51 ± 0.10	24.99 ± 0.10	24.60 ± 0.10	24.58 ± 0.10	24.21 ± 0.10	
Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.02	0.03
CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.057	-0.005	+0.011	+0.004	-0.009	-0.009	+0.010
D3-25	Seeing ["]	0.76	0.68	0.65	0.62	0.62	0.53
80% Compl. (stellar)	26.24 ± 0.10	26.34 ± 0.10	25.84 ± 0.10	25.49 ± 0.10	25.46 ± 0.10	25.14 ± 0.10	
80% Compl. (extended)	25.49 ± 0.10	25.47 ± 0.10	24.97 ± 0.10	24.64 ± 0.10	24.56 ± 0.10	24.11 ± 0.10	
Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.02	0.04
CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.041	+0.004	+0.015	+0.007	-0.012	-0.012	-0.001
D4-25	Seeing ["]	0.72	0.68	0.60	0.56	0.56	0.54
80% Compl. (stellar)	26.28 ± 0.10	26.27 ± 0.10	25.86 ± 0.10	25.51 ± 0.10	25.50 ± 0.10	25.20 ± 0.10	
80% Compl. (extended)	25.49 ± 0.10	25.43 ± 0.10	25.00 ± 0.10	24.69 ± 0.10	24.43 ± 0.10	24.03 ± 0.10	
Mag. int. err. [mag.]	0.04	0.02	0.02	0.02	0.02	0.02	0.03

Table 21: Characteristics of the 25% best-seeing sigma-combined stacks. "80% Compl." is the 80% completeness limit. The seeing is the median FWHM. Astrometric errors are given along the two (x,y)=(NS,EW) axes. The "Mag. int. err." are the mean internal photometric errors from the mean of the three magnitude ranges of Table 23. The "CFHTLS-SDSS $\langle \delta_m \rangle$ mag." denotes the mean magnitude offset between the CFHTLS and the SDSS surveys, averaged over a Deep field.

Field	Parameter	u^*	g	r	i	y	z
D1-85	Seeing ["]	0.84	0.81	0.77	0.74	0.71	0.72
	80% Compl. (stellar)	26.51 ± 0.10	25.98 ± 0.10	25.62 ± 0.10	25.32 ± 0.10	25.47 ± 0.10	24.98 ± 0.10
	80% Compl. (extended)	25.87 ± 0.10	25.32 ± 0.10	24.71 ± 0.10	24.37 ± 0.10	24.54 ± 0.10	24.22 ± 0.10
	Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.03
D2-85	Seeing ["]	0.82	0.78	0.74	0.72	0.70	0.66
	80% Compl. (stellar)	26.56 ± 0.10	26.05 ± 0.10	25.56 ± 0.10	25.22 ± 0.10	25.48 ± 0.10	25.15 ± 0.10
	80% Compl. (extended)	25.95 ± 0.10	25.32 ± 0.10	24.72 ± 0.10	24.46 ± 0.10	24.55 ± 0.10	24.28 ± 0.10
	Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.03
CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.057	-0.004	+0.011	+0.002	-0.011	+0.010
	Seeing ["]	0.87	0.84	0.78	0.75	0.77	0.69
	80% Compl. (stellar)	26.51 ± 0.10	26.06 ± 0.10	25.54 ± 0.10	25.20 ± 0.10	25.51 ± 0.10	25.14 ± 0.10
	80% Compl. (extended)	25.86 ± 0.10	25.26 ± 0.10	24.66 ± 0.10	24.35 ± 0.10	24.46 ± 0.10	24.20 ± 0.10
D3-85	Mag. int. err. [mag.]	0.03	0.02	0.02	0.02	0.02	0.04
	CFHTLS-SDSS $\langle \delta_m \rangle$ [mag.]	-0.040	+0.005	+0.016	+0.000	-0.012	-0.004
	Seeing ["]	0.86	0.81	0.72	0.69	0.66	0.65
	80% Compl. (stellar)	26.44 ± 0.10	25.95 ± 0.10	25.53 ± 0.10	25.31 ± 0.10	25.53 ± 0.10	25.16 ± 0.10
D4-85	80% Compl. (extended)	25.79 ± 0.10	25.32 ± 0.10	24.82 ± 0.10	24.48 ± 0.10	24.47 ± 0.10	24.26 ± 0.10
	Mag. int. err. [mag.]	0.04	0.02	0.02	0.02	0.02	0.03

Table 22: Characteristics of the 85% best-seeing sigma-combined stack parameters.




Figure 42: Comparison of the $(u^* - g)/(g - r)$ (left) and $(g - r)/(r - i)$ (right) stellar color-color tracks of the four Deep Dk-85 fields. The tracks are shown in different colours to make shifts between fields easier to see. Green, blue red and magenta points are D1-85, D2-85, D3-85 and D4-85. The agreement is excellent. All points overlap and the distinction between the color-color tracks is difficult. The left panel show D4-D3-D2-D1 over-plotted, in that order, so D4 (magenta) is background, and D1 (green) is foreground. The right panel is the opposite.

Note that the small offset found in the Deep D-25 and D-85 z -band stacks confirm this is close to zero, as pointed out in Section 4.4.3 from the inspection of the Wide fields.

The stellar color-color tracks of the four fields are remarkably similar. No color offsets can be measured between D1, D2, D3 and D4. This is illustrated on Fig. 42. It shows a superimposition of the $(u^* - g)/(g - r)$ and $(g - r)/(r - i)$ color-color plots for the four D-85 stacks together.

5.3.2 Internal photometric errors

The internal errors have been measured by comparing the photometry of common sources in the D-25 and D-85 stacks. The D-25 and D-85 parent samples comprise all source pairs listed in the merged catalogues of the four Deep fields. The selected sources must have magnitudes measured in all filters (no objects with magnitude/mag_err = 99.0 in any u^*, g, r, i, y and z filters, for both the D-25 and D-85 catalogues), with a SExtractor extraction flag FLAGS=0 (objects with good photometry) and a Terapix object flag=1 or 0 (i.e. stellar or extended sources, only non-saturated objects in non-masked regions). Only sources fainter than $u^*, g=20.5$ and $r, i, y, z=19.5$, and brighter than the D-25 80% completeness limit of extended sources are selected. This cut ensures the homogeneity and completeness of the D-25 and D-85 populations.

The internal photometric errors are derived from the distributions of magnitude differences of source pairs between the D-25 and D-85 catalogues, D25–D85, as function of D-25 magnitudes. The analyses are carried out three magnitude ranges, for all filters, and after a 3σ clipping over the distributions of magnitude differences. The statistics use the MAG_AUTO magnitudes to derive first the median and mean systematic magnitude offsets between D-25 and D-85, then the mean scatter, based on the *rms*. We verified that the median systematic offset is randomly distributed around zero and never exceeds 0.013 mag., for all sub-samples.

The distributions are then fitted by a Gaussian, which gives the FWHM of the mean magnitude difference of cross-identified sources in D-25 and D-85. The mean internal photometric error is then defined as $\sigma_{D25-D85} = \text{FWHM}/2.35$. We checked that the error estimate based on the Gaussian fitting is very close the *rms* errors. The results are summarised in Table 23. Overall, they look very similar to the Wide survey, when sources with same signal-to-noise ratio are compared.

We use the results quoted in Table 23 to compute the photometric errors listed in the summary Tables 19 and 20. The internal photometric errors are the mean values of the three magnitude ranges. This is a reasonable but probably optimistic estimate because it does not take into account there are much more faint than bright objects. Note that these results are valid for both stellar and extended sources.

In contrast with the Wide survey, we do not have many sources in common between CFHTLS and SDSS in D2 and D3 to estimate accurately external errors. In addition, we do not have any common sources at all for D1 and D4. However taking into account the statistics for the internal errors and the remarkable consistency of the results with the Wide survey, similar conclusions as for the TERAPIX T0006 Wide data can be drawn. Therefore, TERAPIX considers the following errors are reasonably accurate and conservative estimates of the *rms* photometric errors over a rather broad magnitude range of the CFHTLS Deep survey (details in Table 23):

- 5% in u^* ; 3% in g, r and i/y , 4% in z .

For faint sources photometric errors rise by a factor of ~ 2 in all bands with respect to the magnitude range quoted above and in Tables 19 and 20.




Figure 43: Estimation of the internal photometric accuracy in Deep stacks by comparing the the MAG_AUTO magnitudes of sources in D4-25-*i* and D-85-*i*. The sample comprises all (stars and galaxies) common sources down to the 80% completeness limits for extended sources of the D-25 stack (sharp cuts on the left panels). The catalogue is then split into three magnitude bins (from top to bottom, the red dots: $19.5 < i < 21.21$, $21.21 < i < 22.71$, $22.71 < i < 24.21$), and for each bin we analyse the *i*-band magnitude differences D25-D85 as function of magnitude (left panels). The right panels show the distribution of magnitude differences. The histograms are first sigma-clipped and then fit by a Gaussian that returns the FWHM of the distribution. The mean internal photometric error is then defined as $\sigma_{D25-D85} = \text{FWHM}/2.35$.

Filter	D1 mag. range [AB MegaCam]	$\sigma_{\text{D}25-\text{D}85}$ [mag.]	CFHTLS T0006 Deep data				D4 mag. range [AB MegaCam]	$\sigma_{\text{D}25-\text{D}85}$ [mag.]
			D2 mag. range [AB MegaCam]	$\sigma_{\text{D}25-\text{D}85}$ [mag.]	D3 mag. range [AB MegaCam]	$\sigma_{\text{D}25-\text{D}85}$ [mag.]		
u^*	20.50 - 22.42	0.011	20.50 - 22.54	0.011	20.50 - 22.35	0.013	20.50 - 22.27	0.014
	22.42 - 23.92	0.023	22.54 - 24.04	0.021	22.35 - 23.85	0.025	22.27 - 23.77	0.026
	23.92 - 25.42	0.062	24.04 - 25.54	0.053	23.85 - 25.35	0.060	23.77 - 25.27	0.068
g	20.50 - 22.19	0.008	20.50 - 22.20	0.006	20.50 - 22.19	0.007	20.50 - 22.16	0.007
	22.19 - 23.69	0.014	22.20 - 23.70	0.012	22.19 - 23.69	0.015	22.16 - 23.66	0.014
	23.69 - 25.19	0.035	23.70 - 25.20	0.030	23.69 - 25.19	0.037	23.66 - 25.16	0.037
r	19.50 - 21.58	0.007	19.50 - 21.58	0.006	19.50 - 21.59	0.006	19.50 - 21.55	0.007
	21.58 - 23.08	0.012	21.58 - 23.08	0.010	21.59 - 23.09	0.011	21.55 - 23.05	0.012
	23.08 - 24.58	0.030	23.08 - 24.58	0.026	23.09 - 24.59	0.029	23.05 - 24.55	0.031
i	19.50 - 21.22	0.008	19.50 - 21.28	0.007	19.50 - 21.29	0.007	19.50 - 21.21	0.008
	21.22 - 22.72	0.016	21.28 - 22.78	0.011	21.29 - 22.79	0.014	21.21 - 22.71	0.014
	22.72 - 24.22	0.040	22.78 - 24.28	0.027	22.79 - 24.29	0.034	22.71 - 24.21	0.034
y	19.50 - 21.18	0.012	19.50 - 21.29	0.010	19.50 - 21.26	0.007	19.50 - 21.12	0.007
	21.18 - 22.68	0.019	21.29 - 22.79	0.012	21.26 - 22.76	0.015	21.12 - 22.62	0.016
	22.68 - 24.18	0.040	22.79 - 24.29	0.028	22.76 - 24.26	0.037	22.62 - 24.12	0.042
z	19.50 - 20.73	0.010	19.50 - 20.80	0.008	19.50 - 20.61	0.011	19.50 - 20.66	0.009
	20.73 - 22.23	0.023	20.80 - 22.30	0.020	20.61 - 22.11	0.026	20.66 - 22.16	0.020
	22.23 - 23.73	0.061	22.30 - 23.80	0.050	22.11 - 23.61	0.071	22.16 - 23.66	0.059

Table 23: Analysis of the internal photometric errors in the CFHTLS T0006 Deep data from the comparison of source pairs in D-25 and D-85. For each Deep field, the internal error is estimated from the mean MAG_AUTO magnitude differences of common sources in D-25 and D-85. The statistics are based on a $3-\sigma$ clipping and a Gaussian fitting of the distribution of magnitude differences. The best fit returns the FWHM of the distribution. The mean internal photometric error is then defined as $\sigma_{\text{D}25-\text{D}85} = \text{FWHM}/2.35$. Each sample is split into three magnitude ranges, but does not make any morphological selection, so the internal errors quoted in this table are valid for any sources. The bright cuts are AB=20.5 for u^* and g and or AB=19.5 for r, i, y and z , while for the faint sources, the cut is set by the 80% completeness limits of extended sources in the D-25 stacks, so both D-85 and D-25 are complete up to the depth of the analyses.




Figure 44: Weightmap images of the D2 CFHTLS_D-85_u_100028+021230_T0007 (left) and CFHTLS_D-85_i_100028+021230_T0007 (right) stacks. The mosaicing of the D2- u^* field by CFHTLS and COSMOS data produces a heterogeneous stack, with significant variations of the exposure times and depths over the field. The contrast with the i -band (and other filters) is striking. The innermost bright region of the D2- u^* weight-map corresponds to the central squares inside the bold contours drawn on Fig. 45, and the numbers quoted on Tables 19 and 20 for the D2- u^* stacks are only relevant for the regions inside the black contours.

5.4 Depth and completeness limits

The depth is measured the same way as in Section 4.3, and these completeness limits and galaxy count plots are available in the synoptic table.

The depths of D-25 and D-85 are given in Tables 19 and 20 for the median combined stacks and Tables 21 and 22 for the sigma-combined stacks. These numbers are also presented in the synoptic table. The errors quoted for the completeness limits in the Tables are dominated by the fitting error. For the 80% and 50% values, this is due sparse sampling of the curve in the magnitude range where the variations of the completeness as function of magnitude are important.

From Figure 46 the 80% completeness limits of stellar sources is a good indicator of turn-over magnitude for the galaxy counts. Similarly, the 80% completeness limits of extended sources corresponds well to the turnover point where the galaxy counts begin to be incomplete. This is not true for the u^* -band data, where both depth parameters have similar values and for the z band, where the completeness limit value is lower than the turnover point and seems a pessimistic estimate of depth.

We note that the completeness limit measurements with simulated sources in the Deep data seem to be in poorer agreement with the galaxy counts plots in comparison with the Wide survey (see Fig. 27). Furthermore, the Deep D-25 estimates are closer to expectations than D-85. This is probably a consequence of increased crowding in deeper images. In these images the fraction of blended sources increases and makes the unambiguous detection of simulated sources more and more difficult.

The D2- u^* should be interpreted with caution. As contains a mix of CFHTLS and cosmos images that are shifted by 30 arc-minutes, the center of the stacks is deeper and the corners are shallower than the mean depth of the stack (see Fig. 44). Note that the total exposure times and the depths quoted in the Tables and on the figures for the D2-25- u^* and D2-85- u^* are *not* the




Figure 45: Locations of u^* -band pointings used to produce the D2- u^* stack. The colored squares represent the different MegaCam fields, and the colored points are the center positions of each CFHTLS and COSMOS images that are combined to produce the D-25- u^* and D-85- u^* images. The dark squares are located at the D2 center position and outline the contour of the final D2- u^* . The D2- u^* characteristics quoted in Tables 19 and 20 only refer to the central regions delimited by the black squares. The bold squares show the central region containing all exposures. The stacks inside this narrow region are extremely deep: 51012 s. for D2- u^* -25, and 142970 s. for D2- u^* -85.

The D2- u^* is the only Deep stack with a non-uniform field. The observing sequences have been split into five positions of MegaCam with respect to the Deep D2 center field. They are referenced as follows:

- the D2-cc- u^* center pointing;
- the D2-ul- u^* upper left pointing, located North-East from the center field;
- the D2-ur- u^* upper right pointing, located North-West;
- the D2-ll- u^* lower left pointing, located South-East; and
- the D2-lr- u^* lower right pointing, located South-West.

The relative positions of D2-cc, D2-ul, D2-ur, D2-ll and D2-lr are shown on Fig. 45. The black contours outline the shape of the D2- u^* stacks. All coloured areas located inside are combined to produce the D-25- u^* and D-85- u^* , which explains the complex weightmap shown on the left panel of Fig. 44.

The complex mosaic pattern and the division of observations amongst several observing runs results in a non-uniform completeness for the D2- u^* stacks. The exposure time and depth can only be defined locally over for the D2- u^* MegaCam field. Table 24 describes the observations in sub-quadrants drawn on Fig. 45. Each quadrant of D-25- u^* and D-85- u^* combines the cc images with either D2-ul, or D2-ur, or D2-ll, or D2-lr, while the central part combines them all. A global estimation of exposure time and depth for D2- u^* is clearly impossible. Note that the exposure times inside the bold contours of Fig. 45 are 51012 s. and 142970 s., for the D2- u^* -25 and D2- u^* -85 stacks, respectively.

CFHTLS+COSMOS D2- u^* field name	Reference center RA ; DEC [J2000]	Number of Exposures	Total Exp. time [s]	Mean Seeing \pm rms [""]
D2-cc-25	10:00:28.00 ; +02:12:30	37	19663	0.827 ± 0.133
D2-cc-85		37	19663	0.827 ± 0.133
D2-ul-25	10:01:48.00 ; +02:24:44	15	6393	0.812 ± 0.019
D2-ul-85		61	31004	0.909 ± 0.080
D2-ur-25	09:58:50.00 ; +02:24:44	15	12482	0.730 ± 0.059
D2-ur-85		58	27892	0.853 ± 0.099
D2-11-25	10:01:48.00 ; +01:49:47	15	19299	0.716 ± 0.019
D2-11-85		64	32805	0.840 ± 0.098
D2-1r-25	09:58:50.00 ; +01:49:47	15	12866	0.690 ± 0.044
D2-1r-85		62	28325	0.865 ± 0.124

Table 24: Overview of the mosaicing of u^* -band observations over the five pointings that are used to produce D-25- u^* and D-85- u^* . The total field of view covered by the five pointings is $1.4 \times 1.4 \text{ deg}^2$, but we only keep the $1 \times 1. \text{ deg}^2$ field at the D2 T0007 reference position. Only the very central region of stacks contains all data and corresponds to the D2- u^* properties quoted in Tables 19 and 20. This region is roughly contained within the bold squares of Fig. 45. The seeing is not the same, but the scatter is large and all stacks agree with the same mean seeing, within 1σ .

In contrast, the seeing is more uniform. The last column of Table 24 provides the mean seeing, as derived from the median seeing value of the single MegaCam exposures comprising D2-cc, D2-ul, D2-ur, D2-11 and D2-1r. The errors are the rms of the mean. None of the seeing values are further than 1σ from the mean.

Stacks labelled SIGWEI have been combined using a sigma-clipping method. Sources in such a sigma-clipped image combination should have slightly better signal-to-noise ratios (around 20%) compared to a median-combined image. Our results do show a modest improvement in u and z (0.1 to 0.2 mag) but almost no improvement within the error bars in r and i . We note that this result has to be considered with caution since the gri bandpasses suffer from crowding, and the technique of adding simulated objects to a field where a large fraction of pixels are already masked (due to the presence of objects) is necessarily problematic. Other methods should be investigated to test the improvement of depth with the combination method.




Figure 46: Galaxy counts for the deep, sigma-weighted stacks in all bands for each of the four fields. The dotted lines show the 85% completeness for galaxies described in Section 5.4.

6 Data products

6.1 Data set

Unlike the previous CFHTLS releases, T0007 is immediately public. The T0007 synoptic table¹¹ is an easy way to access all the data and presents a complete summary of the release. These images and catalogues form the core of the T0007 release. These data are:

- the complete set of individual weight-map images corresponding to the 6043 and 8876 single images used during the production of the CFHTLS Wide and Deep releases. The Terapix weight-map images are Multi-Extention FITS (MEF), like the native CFHT images.
- Stacked images with their corresponding weight-maps;
- 855 Wide stacks, corresponding to u^* , g , r , i or y and z bands:
 - 360 for W1,
 - 125 for W2,
 - 245 for W3 and
 - 125 for W4;
- 96 Deep stacks corresponding to u^* , g , r , i , y and z bands, consisting of:
 - 24 for D1 (12 D-25, 12 D-85),
 - 24 for D2,
 - 24 for D3 and
 - 24 for D4;
- each stack corresponds to a tile of 1 deg. \times 1 deg. field (19354 \times 19354 pixels of 0.1860''), centered at the positions listed in Tables 32 (Wide), and in 18 (Deep);
- the Equatorial coordinate system is J2000 (ICRS) and the projection type is the distorted tangential TAN. Stacks are produced using a median filter, are weighted accordingly using the weight-map images, and combined using a Lanczos3 interpolation kernel.
- the “chi2” detection images ($g-r-i/y$ for the Wide and $g-r-i$ for the Deep data) images with their weight-map (FITS image).
 - the chi2 image only combines g , r and i/y ¹² (Wide) or g , r and i (Deep) images;
 - As for the Wide stacks, they are produced in two versions, sigma-clipped and median-combined;
 - each has the same size, pixel scale and projection type as the native stacks;
 - the pixel values are actually $\sqrt{\text{chi2}}$, not chi2

¹¹http://terapix.iap.fr/cplt/T0007/table_syn_T0007.html

¹²We i/y means either i or (exclusive) y data.

- there is one chi2 image per Wide tile and Deep field. Since T0007 is complete, there are 171 chi2 images for the Wide and 8 chi2 images for the Deep.

In total the T0007 release is therefore composed of 2052 Wide and 224 Deep MegaCam-size science, chi2 or weight-map images;

- the catalogues of sources extracted from each stack, prior to produce catalogues from the chi2 reference image (855 .1dac Wide and 48 .1dac Deep FITS table);
- single filter catalogues, one per stack. They are created by running SExtractor in dual-image mode using the chi2 image as the reference source detection image and the u^*, g, r, i, y or a z -stack as a photometry image (* $u/g/r/i/z^*$.cat ASCII tables). The T0007 single filter catalogues contain all parameters listed in Tables 29, 30 and 31. There is one source catalogue per chi2 source detection and per filter, that is 855 Wide and 96 Deep catalogues. So, for each MegaCam stack position, the Wide ($u^*, g, r, i/y, z$) and the Deep (u^*, g, r, i, y, z) catalogues have the same number of sources;
- ASCII merged source catalogues (M-SC) are also provided:
 - 342 Wide merged 5-filters $u^*gr[i/y], z$ catalogues (either i or y band data inside), and
 - 32 Deep merged 6-filters u^*griyz catalogues (both i and y band inside),

in ASCII table format. The Wide catalogues are named *urgiz*.cat or *urgyz*.cat; the Deep are all named *ugriyz*.cat, and contain i and y data. They contain all objects with a restricted list of parameters from the parent single filter catalogues, but include $e(b - v)$ values for each objects. They are estimated at each source position from interpolation of the Schlegel et al. (1998) maps; Two sets of catalogs are produced containing either MAG_AUTO magnitudes or SNLS aperture magnitudes (SNLS and IQ20 magnitudes). Please refer to section 6.3 for a detailed catalogue content description.

- The ASCII Wide patch merged catalog. These four catalogs (one for each Wide patch) contain all parameters in all filters for each object detected in the corresponding Wide patch. The parent catalogs are the Chi2 catalogs which are merged together. For objects in overlapping regions which are detected on several tiles, the parameters are kept from the largest i-band signal to noise detection (FLUX_AUTO/FLUX_ERR). Note that these catalogs are huge (40 to 130 GB).
- the DS9 compliant masks (.reg ASCII file), *one for each stack*. The masks are produced automatically. The masking uses the USNO source catalogues to locate bright stars in CFHTLS stacks and draw a polygon that delimits a polluted region. The size of the polygon depends on the magnitude of the stars. After the stellar source masking, polygons are added automatically to all mask, to exclude the edges of fields. Masks are then tuned manually with additional polygons that exclude regions with missing CCDs.

It is important to notice that the mask needs depend on the science goals. The T0007 masks may therefore be tuned accordingly. We recommend to CFHTLS users to overlay the masks on a DS9 view of each stack image and have a first look prior to use them.

All quality control files produced during TERAPIX processing are public. The supplementary data available are:

- a set of 855 Wide and 96 Deep binary masks images (FITS), one per filter, based on the ASCII .reg masks;

- the 6043 Wide and 8876 Deep individual QualityFITS evaluation files attached to each input image (QFITS-in). Only QFITS-in data of images that were selected for stacks in T0007 are available;
- the astrometric and photometric initial rescaling calibration files attached to each image during the SCAMP calibration step. There are 855 Wide and 96 Deep .head and .ahead (ASCII) files;
- the complete list of MegaCam images contained in each stack (upon request);
- the list of the L99 stack rescaling factors;
- the 855 Wide and 96 Deep individual QualityFITS evaluation files for each final stack (QFITS-out);
- a series of quality assessment files: tables, images, plots and statistics for any image are available from the T0007 synoptic table http://terapix.iap.fr/cplt/T0007/table_syn_T0007.html. They include:
 - all stellar colour-colour plots. There are three color-color plots per Wide stack, and five color-color plots per Deep stack;
 - all three-filter colour (.jpg) images. There are three color images per stack that combines the five filters in different ways;
 - all completeness limit (.png) plots, one per stack. The ASCII .dat data tables used to make these plots are also available, upon request to TERAPIX;
 - all galaxy count (.ps) plots, one per stack;
 - the complete QualityFITS QFITS-out quality control files (.html page); one per stack;
 - the complete set of SCAMP output and quality control files (.html page); between one (all image together) and six (one per filter) per field;

6.2 Data types and file naming conventions

All files provided with the T0007 release are listed and briefly described in Tables 25 to 28. The CFHT input image names are the native CFHT odometer numbers. Terapix preserves this naming convention for all relevant files attached to single images, such as the weight-maps, the QualityFITS .ldac catalogues or the astrometric calibration files.

File name	Content	Data type	Size	Number of files	Access
#[CFHT-odometer]p.fits	Individual input images	MEF-FITS binary 16	0.7 GB	6043 Wide	CADC
#[CFHT-odometer]p_weight.fits	Individual weight-map images	MEF-FITS binary -32	1.4 GB	6043 Wide	CADC
#[CFHT-odometer]p_ldac	Single image early catalogues	FITS binary-table 8	11 MB	6043 Wide	TERAPIX
#[CFHT-odometer]p_ahead	Individual astrometric calibration files	ASCII	100 kB	6043 Wide	TERAPIX
#[CFHT-odometer]p_head	Individual photometric calibration files	ASCII	1.5 kB	6043 Wide	TERAPIX
#[CFHT-odometer]p/	QFITS-in directories	QA files, various type	350 MB	6043 Wide	TERAPIX
				8876 Deep	
CFHTLS_W-[f].RA-DEC_T0007_MEDIAN.fits	Wide stack science images	FITS binary -32	1.4 GB	855	CADC
CFHTLS_W-[f].RA-DEC_T0007_MEDIAN_weight.fits	Wide stack weight maps	FITS binary -32	1.4 GB	855	CADC
CFHTLS_W-gri.RA-DEC_T0007_MEDIAN.fits	Wide chi2 stacks, for i stacks	FITS binary -32	1.4 GB	139	CADC
CFHTLS_W-gri.RA-DEC_T0007_MEDIAN_weight.fits	Wide chi2 weight map for i stacks,	FITS binary -32	1.4 GB	139	CADC
CFHTLS_W-gry.RA-DEC_T0007_MEDIAN.fits	Wide chi2 image for y stacks,	FITS binary -32	1.4 GB	32	CADC
CFHTLS_W-gry.RA-DEC_T0007_MEDIAN_weight.fits	Wide chi2 weight map for y stacks,	FITS binary -32	1.4 GB	32	CADC
	gry combined				
CFHTLS_W-[f].RA-DEC_T0007_MEDIAN_ldac	Wide stack catalogues	FITS binary-table 8	50 MB	855	CADC
CFHTLS_W-[f].RA-DEC_T0007_MEDIAN.cat	Wide stack chi2 catalogues	ASCII 181 columns	450 MB	855	CADC
CFHTLS_W-ugriz.RA-DEC_T0007_MEDIAN_MAGAUTO.cat	Wide chi2 merged band catalogues,	ASCII 24 columns	50 MB	171	CADC
MAG_AUTO magnitudes					

Table 25: CFHTLS files, point-of-access and naming conventions. The first line of the table gives the input images delivered from CFHT. Successive lines refer to Terapix T0007 data products. Access to restricted CADC and Terapix data sets, public figures and plots are possible from the T0007 synoptic table. The number of files for QFITS-in/out refers to the number of directories, each containing around 100 files per directory).

File name	Content	Data type	Size	Number of files	Access
CFHTLS_W_ugriz_RA-DEC_T0007_MEDIAN_MAGSNSLS.cat	Wide chi2 merged band catalogues, MAG_SNSL magnitudes	ASCII 29 columns	60 MB	171	CADC
CFHTLS_W_ugriz_RA-DEC_T0007_MEDIAN.apc	Wide chi2 27+MAG_SNLS aperture merged band catalogues	ASCII 556 columns	1.3 GB	171	TERAPIX
CFHTLS_W_[f]_RA-DEC_T0007_MEDIAN.reg	Wide DS9 compliant mask f -band	ASCII	100 kB	855	CADC
CFHTLS_W_[f]_RA-DEC_T0007_MEDIAN_bimmask.fits	Wide binary mask image f -band	FITS binary -32	1.4 GB	855	TERAPIX
CFHTLS_W_[f]_RA-DEC_T0007_MEDIAN/	Wide f -band stack QFITS-out directory	QA files, various type	50 MB	855	TERAPIX
CFHTLS_W_[fff]_RA-DEC_T0007.jpg	Wide stacks 3-color image (u^*gr); ($gr[i/y]$); ($r[i/yz]$)	JPEG	50 MB	513	TERAPIX
CFHTLS_W_ugriz_RA-DEC_T0007_MEDIAN_MAGAUTO_fff.png	Wide stellar color-color tracks plots (u^*-g)/($g-r$); ($g-r$)/($r-i$); ($r-i$)/($i-z$)	PNG	50 kB	417	TERAPIX
CFHTLS_W_ugriz_RA-DEC_T0007_MEDIAN_MAGSNSL_fff.png	Wide stellar color-color tracks plots (u^*-g)/($g-r$); ($g-r$)/($r-i$); ($r-i$)/($i-z$)	PNG	50 kB	417	TERAPIX
CFHTLS_W_ugriz_RA-DEC_T0007_MEDIAN_MAGAUTO_fff.png	Wide stellar color-color tracks plots (u^*-g)/($g-r$); ($g-r$)/($r-y$); ($r-y$)/($y-z$)	PNG	50 kB	96	TERAPIX
CFHTLS_W_ugriz_RA-DEC_T0007_MEDIAN_MAGSNSL_fff.png	Wide stellar color-color tracks plots (u^*-g)/($g-r$); ($g-r$)/($r-y$); ($r-y$)/($y-z$)	PNG	50 kB	96	TERAPIX
CFHTLS_W_[f]_RA-DEC_T0007_MEDIAN_CompLim.png	Wide stacks completeness limit plots f -band	PNG	60 kB	855	TERAPIX
CFHTLS_W_[f]_RA-DEC_T0007_MEDIAN_CompLim.dat	Wide stacks completeness data points f -band	ASCII	0 kB	855	TERAPIX
CFHTLS_W_[f]_RA-DEC_T0007_gal_histo.ps	Wide stacks galaxy counts f -band	PS	50 kB	855	TERAPIX

Table 26: CFHTLS files, point-of-access and naming conventions (cont'd).

File name	Content	Data type	Size	Number of files	Access
Each DEEP product is produced in 4 flavours (D-[28]5 and COMB=MEDIAN/SIGWEI)					
CFHTLS_D-[28]5_[f].RA-DEC_T0007_[COMB].fits	Deep [28]5% best seeing stack science image <i>f</i> -band	Fitrs binary -32	1.4 GB	24 * 4	CADC
CFHTLS_D-[28]5_[f].RA-DEC_T0007_[COMB]_weight.fits	Deep [28]5% best seeing stack weight maps <i>f</i> -band	Fitrs binary -32	1.4 GB	24 * 4	CADC
CFHTLS_D-[28]5_gri_RA-DEC_T0007_[COMB].fits	Deep [28]5% best seeing chi2 image for <i>i</i> stacks, chi2- <i>gri</i> combined	Fitrs binary -32	1.4 GB	4 * 4	CADC
CFHTLS_D-[28]5_gri_RA-DEC_T0007_[COMB]_weight.fits	Deep [28]5% best seeing chi2 weight map for <i>i</i> stacks,chi2- <i>gri</i> combined	Fitrs binary -32	1.4 GB	4 * 4	CADC
CFHTLS_D-[28]5_[f].RA-DEC_T0007_[COMB].dac	Deep [28]5% best seeing stack catalogue <i>f</i> -band	Fitrs binary-table 8	50 MB	24 * 4	CADC
CFHTLS_D-[28]5_[f].RA-DEC_T0007_[COMB].cat	Deep [28]5% best seeing stack chi2 catalogue <i>f</i> -band	ASCII 181 columns	500 MB	24 * 4	CADC
85					
CFHTLS_D-[28]5_ugriyz_RA-DEC_T0007_[COMB]_MAGAUTO.cat	Deep [28]5% best seeing chi2 catalogue merged band (in MAGAUTO)	ASCII 27 columns; e(b-v)	100 MB	4 * 4	CADC
CFHTLS_D-[28]5_ugriyz_RA-DEC_T0007_[COMB]_MAGSNLS.cat	Deep [28]5% best seeing chi2 catalogue merged band (in MAGAUTO)	ASCII 27 columns; e(b-v)	100 MB	4 * 4	CADC
CFHTLS_D-[28]5_ugriyz_RA-DEC_T0007_[COMB].ape	Deep [28]5% best seeing chi2 27 aperture photometry catalogue merged band	ASCII 618 columns	3.1 GB	4 * 4	TERAPIX
CFHTLS_D-[28]5_[f].RA-DEC_T0007_[COMB].reg	Deep [28]5% best seeing DS9 compliant mask <i>f</i> -band	ASCII	100 kB	24 * 4	CADC
CFHTLS_D-[28]5_[f].RA-DEC_T0007_[COMB]_bimmask.fits	Deep [28]5% best seeing binary mask image <i>f</i> -band	Fitrs binary -32	1.4 GB	24 * 4	TERAPIX
CFHTLS_D-[28]5_[f].RA-DEC_T0007_[COMB]/	Deep [28]5% best seeing <i>f</i> -band stack qa: qfts-out directory	QA files, various type	(2.3 MB .gz)	24 * 4	TERAPIX
CFHTLS_D-[28]5_[ff].RA-DEC_T0007_[COMB].jpg	Deep [28]5% best seeing [(<i>u*</i> gr);(gri/y);(ri/yz)] of stacks	JPEG	75 MB	12 * 4	TERAPIX
			50 MB		

Table 27: CFHTLS files, point-of-access and naming conventions (cont'd).

File name	Content	Data type	Size	Number of files	Access
CFHTLS_D-[28]5_ugriz_RA-DEC_T0007_[COMB].MAGAUTO_fif.png	Deep [28]5% best seeing stellar 3-color-color plots (in MAGAUTO) $(u^*-g)/(g-r);(g-r)(r-i);(r-i)/(i-z)$	PNG	200 kB	4 * 4	TERAPIX
CFHTLS_D-[28]5_ugriz_RA-DEC_T0007_[COMB].MAGSNLS_fif.png	Deep [28]5% best seeing stellar 3-color-color plots (in MAGSNLS) $(u^*-g)/(g-r);(r-y)/(y-z)$	PNG	200 kB	4 * 4	TERAPIX
CFHTLS_D-[28]5_[f].RA-DEC_T0007_[COMB].CompLim.png	Deep [28]5% best seeing stacks completeness limit plots f -band	PNG	60 kB	24 * 4	TERAPIX
CFHTLS_D-[28]5_[f].RA-DEC_T0007_[COMB].CompLim.dat	Deep [28]5% best seeing stacks completeness data points f -band	ASCII	0 kB	24 * 4	TERAPIX
CFHTLS_D-[28]5_[f].RA-DEC_T0007_[COMB].gal_histos.ps	Deep stacks galaxy counts f -band	PS	50 kB	24 * 4	TERAPIX

Table 28: CFHTLS files, point-of-access and naming conventions (cont'd).

6.3 Content of CFHTLS source catalogues

Five types of source catalogue are provided:

- “.1dac” source catalogues for individual images. There is one .1dac catalogue per CFHT input image. For T0007, 6043 .1dac Wide and 8876 .1dac Deep are produced;
- the FITS-table output-ldac source catalogues of each individual stack. There is one catalogue per tile and per filter. So 855 .1dac-Wide (171 tiles, 5 filters per tiles) and 96 .1dac-Deep (4 fields, 6 filters per field, D-25 and D-85 seeing selections, MEDIAN and SIGWEI combination) source catalogues are produced;
- the ASCII-table chi2-image reference source catalogues (chi2-RSC), produced from the aperture-matched detections in the five Wide (u^*gri/yz) or six Deep (u^*griyz) stacked images of each tile. There is one catalogue per tile and per filter, but each filter has the same number of sources, located at the same positions, as measured in the chi2 image. These catalogues are not corrected for galactic extinction. 855 Wide and 96 Deep *[f]*.cat catalogues are produced, where [f] denotes the filter, and they all contain the SExtractor parameters listed in Tables 29, 30 and 31;
- the ASCII merged source catalogues (M-SC), produced by merging the chi2-RSC for each filter into one single catalogue (u^*griz , or u^*gryz , or u^*griyz). The Wide *ugriz*.cat, *ugryz*.cat and Deep *ugriyz*.cat catalogues are more concise, but may be more convenient for most CFHTLS users. Note that the Wide and Deep catalogues do not have the same number of columns.
 - The ASCII merged source catalogues are produced in two versions. The “MAGAUTO” version contains MAG_AUTO magnitudes and is suitable for science topics involving galaxies. The “MAGSNLS” version contains two sorts of aperture magnitudes: MAG_SNLS (aperture magnitude with a diameter of $7.5 * \text{FWHM}$) and MAG_IQ20 (MAG_SNLS magnitude with an aperture correction). These are the magnitudes used for the photometric calibration of star catalogs (mainly IQ20 magnitudes). For a detailed description of these magnitudes, please refer to the photometric calibration section.
 - The Wide merged catalogues contain the following parameters, extracted from the either the chi2-RSC $ugriz$ or the $ugryz$ catalogues (`id, x, y, ra, dec, r2, flag, u*, g, r, i/y, z, uerr*`, g_{err} , r_{err} , $(i/y)_{err}$, z_{err} , $e(b-v)$, $u_{SEx-flag}^*$, $g_{SEx-flag}$, $r_{SEx-flag}$, $(i/y)_{SEx-flag}$, $z_{SEx-flag}$, `dk`), where
 - * `id` : SExtractor object ID. This corresponds to the object ID which appears in the chi2 catalogue;
 - * `x, y` (pixels) : object pixel coordinates. The pixel scale is $0.186''$;
 - * `RA, DEC` : right ascension and declination in J2000 coordinates;
 - * `r2` (pixels) : radius enclosing half the flux;
 - * `flag` : Terapix object flag, derived from the SExtractor `r2` parameter, the saturation and the masking. The flag value is a combination of the following binary flags :
 - 0/1 : galaxy/star
 - 0/2 : saturated object in at least one filter
 - 0/4 : masked in `z` band
 - 0/8 : masked in `y` band
 - 0/16 : masked in `i` band

- 0/32 : masked in r band
- 0/64 : masked in g band
- 0/128 : masked in u band

For exemple, an object with flag 37 is a star which is in a masked region in the r and z bands.

- * $u^*, g, r, i/y, z$: Depending on the catalog, object **MAG_AUTO** or **MAG_SNLS** magnitudes in the MegaCam instrumental reference frame. When magnitude and its error are missing, these values are set to 99. Note that the i or y magnitudes are both listed in a column labelled i on the top header of each catalog.
- * $u_{err}^*, g_{err}, r_{err}, (i/y)_{err}, z_{err}$: Object magnitude errors;
- * $e(b-v)$: the values of the galactic extinction are calculated using the Schlegel et al. (1998) dust map at the object's position. The extinction, $E(B - V)$, is derived at each source position using a linearly interpolated dust value from the four nearest pixels. The $E(B - V)$ is then added in the last column of the merged catalogue;
- * $u_{SEx-flag}^*, g_{SEx-flag}, r_{SEx-flag}, (i/y)_{SEx-flag}, z_{SEx-flag}$: **SExtractor** extraction flags, for each filter. Each flag is set to zero when no source extraction problem is encountered, or follows the sum of power-of-two rule¹³;
- * dk : object cell number for the spatially variable color-term (see photometric calibration).
- * $u_{IQ20}, g_{IQ20}, r_{IQ20}, i/y_{IQ20}, z_{IQ20}$ (only in the SNLS catalogs). IQ20 magnitudes are **MAG_SNLS** aperture magnitudes corrected by an aperture correction factor to estimate the flux in an aperture of $20 * FWHM$. This magnitude is a better measurement for stellar total flux.
- The Deep merged catalogues also contain the parameters extracted from the chi2-RSC, but for six filters instead of five, as for the Wide. All catalogues have $ugriyz$ data for all sources.

342 Wide merged catalogues are produced, one per tile, two for **MAG_AUTO**, **MAG_SNLS**, and 32 Deep merged catalogues are produced, two per field (D-25 and D-85), two for **MEDIAN/SIGWEI**, two for **MAG_AUTO**, **MAG_SNLS**;

- the ASCII multi-aperture merged source catalogues (MAM-SC), produced like the (M-SC), but the catalogues only include the data from the 27 apertures (SNLS+26 apertures) and aperture magnitudes of each sources of the chi2-RSC catalogue. The aperture sizes range from 10 to 60 pixels. As the M-SC, 171 Wide catalogues and 16 Deep catalogues are produced. These catalogues are very large (1-3 GB). They have 536 columns per source for the Wide and 642 for the Deep.
- The ASCII Wide patch merged catalog (WPM-SC). These four catalogs (one for each Wide patch) contain all parameters in all filters for each object detected in the corresponding Wide patch. The parent catalogs are the Chi2 catalogs (27 apertures) which are merged together.

All catalogues have a header on that describes the meaning of each column.

All data of the two last catalogues with the exception of the $E(B - V)$ for the merged source catalogue, are extracted from the large chi2-RSCs. They are produced only for convenience. All of them have been produced using **SExtractor**, but with different configuration files and output parameter lists. Most i stacks are made with the first $i\text{-}(i.\text{MP9702})$ filter. However, there are 16 W1, 2 W2, 7 W3 and 7 W4

¹³<http://astromatic.iap.fr/software/sextarator>

stacks made with the *y-(i.MP9702)* filter. The *y* stacks are listed in Tables 32 and quoted in Tables 16 and 17. All Deep fields comprise both *i* and *y*-band stacks, but the *i* stacks contain much more images and are much deeper.

The two input-ldac and output-ldac catalogues as well as the chi2-RSC catalogue contain the 75 parameters described in Table 29 to 31. However, they do not have the same input nor the same of output parameter values. Some of them are vectors, so the number of entries are also not the same and can be much higher than 75. In particular, they do not have the same detection threshold, or the same number of MAG_APER aperture magnitudes. Columns of catalogues with both the '.cat' or the '.ldac' extensions are defined in the '.param' files. For the Wide survey, there are 77 columns in the .ldac catalogues, 181 columns in the chi2-RSC, 24 (resp 30) in the merged MAG_AUTO (resp MAG_SNLS) M-SC catalogues, 536 in the merged MAM-SC catalogues and 827 in the patch-merged catalogs WPM-SC.

All images have a new magnitude ZP set to 30 AB magnitudes. The magnitudes of objects in the final stacks are computed as follows:

$$m = 30 - 2.5 \log(counts). \quad (18)$$

It is important to realise that the .cat catalogues are produced using specific selection criteria or filters selected by TERAPIX from past experience and after discussions with experienced users and the CFHTLS Steering Group. They are certainly not suitable for all scientific goals. Please examine the configuration and parameter list files and check they meet your needs. In case different selections or configuration parameters are needed, it may be better to produce a new and more suitable catalogue, or to produce a new chi2 image. TERAPIX can provide specific help to users who want to produce their own images or catalogues.

Id	Parameter	Description	Units	Comments
1	NUMBER	Running object number	-	[pixel]
2	X_IMAGE	Object position along x	[pixel]	[deg]
3	Y_IMAGE	Object position along y	[pixel]	[pixel]
4	ERRA_IMAGE	RMS position error along major axis	[pixel]	Error-ellipse shape parameter. Generic SExtractor parameter naming construction: <code>ERR[-]ERR</code> refers to error-ellipse properties, while <code>[-]ERR</code> refers to error on SExtractor object parameters.
5	ERRB_IMAGE	RMS position error along minor axis	[pixel]	[deg]
6	ERRTHETA_IMAGE	Error ellipse position angle (CCW/x)	[deg]	[pixel]
7	A_IMAGE	Profile RMS along major axis	[pixel]	[pixel]
8	B_IMAGE	Profile RMS along minor axis	[pixel]	[pixel]
9	POLAR_IMAGE	$(A_IMAGE^2 - B_IMAGE^2)/(A_IMAGE^2 + B_IMAGE^2)$	Position angle (CCW/x)	[deg]
10	THETA_IMAGE	Barycenter position along world x axis	[deg]	[deg]
11	X_WORLD	Barycenter position along world y axis	[deg]	[deg]
12	Y_WORLD	World RMS position error along major axis	[deg]	[deg]
13	ERRA_WORLD	World RMS position error along minor axis	[deg]	[deg]
14	ERRB_WORLD	World RMS position error along world-x	[deg]	[deg]
15	ERRTHETA_WORLD	Error ellipse pos. angle (CCW/world-x)	[deg]	[deg]
16	A_WORLD	Profile RMS along major axis (world units)	[deg]	[deg]
17	B_WORLD	Profile RMS along minor axis (world units)	[deg]	[deg]
18	POLAR_WORLD	$(A_WORLD^2 - A_WORLD^2)/(A_WORLD^2 + B_WORLD^2)$	Position angle (CCW/world-x)	[deg]
19	THETA_WORLD	Right ascension of barycenter (J2000)	[deg]	[deg]
20	ALPHA_J2000	Declination of barycenter (J2000)	[deg]	[deg]
21	DELTA_J2000	J2000 error ellipse pos. angle (east of north)	[deg]	[deg]
22	ERRTHETA_J2000	Position angle (east of north) (J2000)	[deg]	[deg]
23	THETA_J2000	Windowed position estimate along x	[pixel]	[pixel]
24	XWIN_IMAGE	Windowed position estimate along y	[pixel]	[pixel]
25	YWIN_IMAGE	RMS windowed pos error along major axis	[pixel]	[pixel]
26	ERRAWIN_IMAGE	RMS windowed pos error along minor axis	[pixel]	[pixel]
27	ERRBWIN_IMAGE	Windowed error ellipse pos angle (CCW/x)	[deg]	[deg]
28	ERRTHETAWIN_IMAGE			

Table 29: Description of parameters listed in T0007 catalogues.

Id	Parameter	Description	Units	Comments
29	AWIN_IMAGE	Windowed profile RMS along major axis	[pixel]	
30	BWIN_IMAGE	Windowed profile RMS along minor axis	[pixel]	
31	POLARWIN_IMAGE	$(\text{AWIN}^2 - \text{BWIN}^2)/(\text{AWIN}^2 + \text{BWIN}^2)$		
32	THETAWIN_IMAGE	Windowed position angle (CCW/x)	[deg]	
33	XWIN_WORLD	Windowed position along world x axis	[deg]	
34	YWIN_WORLD	Windowed position along world y axis	[deg]	
35	ERRAWN_WORLD	World RMS windowed pos error along major axis	[deg]	
36	ERRBWIN_WORLD	World RMS windowed pos error along minor axis	[deg]	
37	ERRTHETAWIN_WORLD	Windowed error ellipse pos. angle (CCW/world-x)	[deg]	
38	AWIN_WORLD	Windowed profile RMS along major axis (world units)	[deg]	
39	BWIN_WORLD	Windowed profile RMS along minor axis (world units)	[deg]	
40	POLARWIN_WORLD	$(\text{AWIN}^2 - \text{BWIN}^2)/(\text{AWIN}^2 + \text{BWIN}^2)$		
41	THETAWIN_WORLD	Windowed position angle (CCW/world-x)	[deg]	
42	ALPHAWIN_J2000	Windowed right ascension (J2000)	[deg]	
43	DELTAWIN_J2000	Windowed declination (J2000)	[deg]	
44	ERRTHETAWIN_J2000	J2000 windowed error ellipse pos. angle (east of north)	[deg]	
45	THETAWIN_J2000	Windowed position angle (east of north) (J2000)	[deg]	
46	FLUX_ISO	Isophotal flux	[count]	
47	FLUXERR_ISO	RMS error for isophotal flux	[count]	
48	MAG_ISO	Isophotal magnitude	[mag]	
49	MAGER_R_ISO	RMS error for isophotal magnitude	[mag]	
50	FLUX_APER	Flux vector within fixed circular aperture(s)	[count]	
51	FLUXERR_APER	RMS error vector for aperture flux(es)	[count]	
52	MAG_APER	Fixed aperture magnitude vector	[mag]	
53	MAGER_R_APER	RMS error vector for fixed aperture mag.	[mag]	
54	FLUX_AUTO	Flux within a Kron-like elliptical aperture	[count]	
55	FLUXERR_AUTO	RMS error vector for aperture flux(es)	[count]	
56	MAG_AUTO	Fixed aperture magnitude vector	[mag]	
57	MAGER_R_AUTO	RMS error vector for fixed aperture mag.	[mag]	
58	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
59	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
60	MAG_KRON	Fixed aperture magnitude vector	[mag]	
61	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
62	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
63	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
64	MAG_KRON	Fixed aperture magnitude vector	[mag]	
65	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
66	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
67	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
68	MAG_KRON	Fixed aperture magnitude vector	[mag]	
69	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
70	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
71	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
72	MAG_KRON	Fixed aperture magnitude vector	[mag]	
73	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
74	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
75	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
76	MAG_KRON	Fixed aperture magnitude vector	[mag]	
77	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
78	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
79	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
80	MAG_KRON	Fixed aperture magnitude vector	[mag]	
81	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
82	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
83	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
84	MAG_KRON	Fixed aperture magnitude vector	[mag]	
85	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
86	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
87	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
88	MAG_KRON	Fixed aperture magnitude vector	[mag]	
89	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
90	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
91	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
92	MAG_KRON	Fixed aperture magnitude vector	[mag]	
93	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
94	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
95	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
96	MAG_KRON	Fixed aperture magnitude vector	[mag]	
97	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
98	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
99	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
100	MAG_KRON	Fixed aperture magnitude vector	[mag]	
101	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
102	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
103	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	
104	MAG_KRON	Fixed aperture magnitude vector	[mag]	
105	MAGER_R_KRON	RMS error vector for fixed aperture mag.	[mag]	
106	FLUX_KRON	Flux within a Kron-like elliptical aperture	[count]	
107	FLUXERR_KRON	RMS error vector for aperture flux(es)	[count]	

Id	Parameter	Description	Units	Comments
55	FLUXERR_AUTO	RMS error for auto flux	[count]	
56	MAG_AUTO	Kron-like elliptical aperture magnitude	[mag]	
57	MAGER_R_AUTO	RMS error for auto magnitude	[mag]	
58	FLUX_PETRO	Flux within a Petrosian-like elliptical aperture	[count]	
59	FLUXERR_PETRO	RMS error for Petrosian flux	[count]	
60	MAG_PETRO	Petrosian-like elliptical aperture magnitude	[mag]	
61	MAGER_R_PETRO	RMS error for PETROsian magnitude	[mag]	
62	FLUX_RADIUS	Fraction-of-light radii	[pixel]	Radii that contain 20%, 50% and 80% of the total flux.
63	KRON_RADIUS	Kron apertures in units of A or B		
64	PETRO_RADIUS	Petrosian apertures in units of A or B		
65	BACKGROUND	Background at centroid position	[count]	
66	THRESHOLD	Detection threshold above background	[count]	
67	MU_THRESHOLD	Detection threshold above background	[mag/arcsec ²]	
68	FLUX_MAX	Peak flux above background	[count]	
69	MU_MAX	Peak surface brightness above background	[mag/arcsec ²]	
70	ISOAREA_IMAGE	Isophotal area above Analysis threshold	[pixel ²]	
71	ISOAREA_AF_IMAGE	Isophotal area (filtered) above Detection threshold	[pixel ²]	
72	ISOAREA_WORLD	Isophotal area above Analysis threshold	[deg ²]	
73	ISOAREA_AF_WORLD	Isophotal area (filtered) above Detection threshold	[deg ²]	
74	FLAGS	Extraction flags		
75	CLASS_STAR	S/G classifier output		
76	FLAG_MASK	Bit flag for star-galaxy separation, saturation and masking		
77	DK_CELL	Refined color term cell number		
78	FLAG_IFILTER	i-filter flag (0 is the old i filter, 1 is the new i filter)		
79	CFHTLS_TILE	CFHTLS tile of the detection		

Table 31: Description of parameters listed in T0007 catalogues (cont'd).

6.4 The QualityFITS input and output products

QualityFITS is a Terapix quality assessment tool for FITS images. During CFHTLS T0007 production, it is used to assess whether individual CFHT input images and the CFHTLS output stacks meet the survey specifications. QualityFITS also produces the input weight-map images as well as the input .ldac catalogues.

The quality assessments are done from a visual inspection of QualityFITS outputs and from a series of statistics, tables and plots. An overview and a quick-look image quality assessments can be made using the QualityFITS web page. This “ID-card” for each image is produced automatically and is used to grade all images through the Youpi user interface¹⁴.

The information returned by QualityFITS depends on the type of images (Multi-extension fits (MEF) or single extension FITS, the type of detectors (single CCD, mosaic of CCDs) and the origin of images. Depending on the steps of the processing (evaluation of input images or of final stacks), they are referenced as QualityFITS-in (or QFITS-in) or QualityFITS-out (or QFITS-out) products.

As a general rule any CFHT images entering or leaving the Terapix center is passes through QualityFITS-in or QualityFITS-out processing steps. 7042 CFHTLS input images and the 2276 T0007 output images were evaluated using this tool.

The QualityFITS data products are images, tables and plots:

- the FITS weight-map image, using **WeightWatcher** (Marmo & Bertin, 2008), in a multiple or single extension FITS format, like the input image;
- the .ldac catalogue, using **SExtractor**;
- an analysis of the shape and spatial variation of the PSF using **PSFEX**, sampled over the whole field (QualityFITS-out), or CCD by CCD for a mosaic (as for QualityFITS-in in the case of MegaCam input images);
- an analysis of the sky background over the whole field of CCD by CCD for a mosaic;
- an analysis of galaxy and stellar counts, based on an automatic blind star-galaxy separation from a r_h ¹⁵-magnitude diagram. The counts are shown on separate plots and compared to expectations: for the galaxies, they are compared to published results of CFHTLS Deep galaxy counts with the MegaCam filters; for stars, the counts are compared to Bahcall-Soneira models (Bahcall & Soneira, 1981);
- an analysis of the astrometry of images, using **SCAMP**. For CFHT input images (QualityFITS-in), the astrometry analysis is approximate, and just relies on the FITS keywords. For CFHTLS stacks (QualityFITS-out), the analysis is based on a comparison between the CFHTLS and the 2MASS source catalogues;
- a properly oriented (in case of reversed detector images due to flipped positions of output amplifiers), scaled and astrometrically calibrate binned view of each CCD and of the whole MegaCam field;

¹⁴<http://youpi.terapix.fr>

¹⁵half-light radius

- close up views of the central and the four corner regions of the MegaCam image. The views are unbinned 512×512 pixels JPEG sub-images of the five regions, but is sometimes expanded to 1024×1024 pixels when necessary;
- a series of tables that contain information from the image FITS header, or statistics on the seeing, the background, the number of detections, either over the whole image or CCD by CCD for a mosaic.

The QualityFITS output files are all public. The QualityFITS QA pages are available from the synoptic table. The T0007 synoptic table is a convenient way to have a quick look at the images.



Evaluation of CFHTLS_W_i_222054+002300_T0007




Figure 47: QFITs-out page of the W4 CFHTLS_W_i_222054+002300 stack. The top table summarises the images origin and the nature of the stack. The next images show, from top left to bottom right: binned images of the stack, its weight-map, and the sky background; the PSF over the MegaCam field. The plots at the bottom show the galaxy counts (left) derived from the .1dac catalogue. The galaxies are extracted from a blind selection of the sources shown on the right r_h – mag plot (red points). The red line on the galaxy count plot is the expectation.






Figure 48: QFITS-out page of the same field (cont'd). The clickable plots show, from top left to bottom right, the stellar-counts (left) derived from a blind selection of red sources shown on the right $r_h - magnitude$ plot. The red line is the predictions of the Bahcall-Soneira model. The plot on the middle panel shows the amplitude ($(a^2 - b^2)/(a^2 + b^2)$ = length of lines) and the orientation (= orientation of lines) of the stellar ellipticity vectors over the MegaCam field. The selected sources are the red points shown on the right $r_h - magnitude$ plot. The plots at the bottom are the 2-dimensional (left) and 1-dimensional astrometric errors of sources with respect to the 2MASS catalogue. They are produced by running SCAMP in a simple diagnostic mode (-MATCH N -SOLVE_ASTROM N -SOLVE_PHOTOM N).

Summary of scamp astrometric statistics	
AstromChi2_Internal_HighSN	0
AstromChi2_Reference	1.97
AstromChi2_Reference_HighSN	1.97
AstromNDets_Internal_HighSN	2504
AstromNDets_Reference	2506

Summary of scamp astrometric statistics	
AstromChi2_Internal_HighSN	0
AstromChi2_Reference	1.97
AstromChi2_Reference_HighSN	1.97
AstromNDets_Internal_HighSN	2504
AstromNDets_Reference	2506



subimage2 CFHTLS_W_i_2222054+002300_T0007[0] (EXT_0)

4x4 binned chip	background (ADU)	sigma_bkg (ADU)	background (mag/arcsec ²)	nsexdet (pix)	seeing (pix)	FRseeing (arcsec)	sloadded	saccepted	schi2
pixel (1,1) is at lower left	-0.0	1.7	-0.16	151438	3.521	4.354	0.655	0.810	8390

4x4 binned chip	background (ADU)	sigma_bkg (ADU)	background (mag/arcsec ²)	nsexdet (pix)	seeing (pix)	FRseeing (arcsec)	sloadded	saccepted	schi2
EXT_0	-0.0	1.7	-0.16	151438	3.521	4.354	0.655	0.810	8390

```
qualityFITS command line : /usr/local/bin/qualityFITS -vvv --scamp2 --subim 500 CFHTLS_W_i_2222054+002300_T0007.fits --weight CFHTLS_W_i_2222054+002300_T0007_weight.fits --background CFHTLS_W_i_2222054+002300_T0007_1dac ..background CFHTLS_W_i_2222054+002300_T0007_mbkg.fits ..configfile CFHTLS_W_i_2222054+002300_T0007.log --filterfile /data/fciex/raid2/hudelot/CFHTLS/T0007/Wide/RescaleL99_apCorr.apCorr/0FITS-out/filterers_megacam.dat -c /data/fciex/raid2/hudelot/CFHTLS/T0007/Wide/RescaleL99_apCorr/0FITS-out/qualityFITS.out
```

6.5 Transfer to CADC and CDS(~~*tbd***~~)and data integrity check**

The only access point for the distribution of TERAPIX restricted T0007 CFHTLS data is at the cadc center¹⁶. The data are restricted to CFHTLS users affiliated to Canadian or French institutes who registered after request to the CFHT Director (veillet@cfht.hawaii.edu).

The data products that are archived and distributed by CADC are all MD5 checksummed by TERAPIX prior to delivery to CADC. The MD5-checksum is calculated again immediately before and after the transfer, and the checksum values are all preserved in the CADC archive. TERAPIX verified the integrity of the whole T0007 release by comparing the TERAPIX and CADC checksum values. The checksums can be downloaded by the CFHTLS users so any user can verify that the images are not corrupted after the transfer from CADC to his own disk.

Note that prior to transfer all data are now compressed using gzip. There is no longer RICE compressed data in the T0007 archived because all weight-map and stack images are not 16-bit Integer FITS files. CFHTLS users also expressed a preference for gzipped data.

¹⁶<http://www.cadc-ccda.hia-ihc.nrc-cnrc.gc.ca/cfht/T0007.html>

7 Acknowledgements

We thank Emmanuel Bertin for practical advice on the use of Astromatic software suite; the CFHT staff; the SNLS team, in particular Pierre Astier, Ray Carlberg, Julien Guy, Chris Pritchett, Raynald Pain; CADC, in particular JJ Kavelaars and John Ouelette; the CDS in Strasbourg; the CFHTLS Data Operation Group and the CFHTLS Steering Group. TERAPIX is funded by the French national research agency (CNRS/INSU), the Programme National Cosmologie et Galaxies (PNCG), the Service d’Astrophysique of the Commissariat à l’Energie Atomique (CEA/SAp), the Institut d’Astrophysique de Paris (IAP), the Agence Nationale de la Recherche (ANR) grants ECOSTAT, DESIR and TG_REGALDIS, and the European FP5 RTD contracts “Astrowise” and “AVO” (Astrophysical Virtual Observatory).

Funding for SDSS-III has been provided by the Alfred P. Sloan Foundation, the Participating Institutions, the National Science Foundation, and the U.S. Department of Energy Office of Science. The SDSS-III web site is <http://www.sdss3.org/>.

SDSS-III is managed by the Astrophysical Research Consortium for the Participating Institutions of the SDSS-III Collaboration including the University of Arizona, the Brazilian Participation Group, Brookhaven National Laboratory, University of Cambridge, Carnegie Mellon University, University of Florida, the French Participation Group, the German Participation Group, Harvard University, the Instituto de Astrofísica de Canarias, the Michigan State/Notre Dame/JINA Participation Group, Johns Hopkins University, Lawrence Berkeley National Laboratory, Max Planck Institute for Astrophysics, Max Planck Institute for Extraterrestrial Physics, New Mexico State University, New York University, Ohio State University, Pennsylvania State University, University of Portsmouth, Princeton University, the Spanish Participation Group, University of Tokyo, University of Utah, Vanderbilt University, University of Virginia, University of Washington, and Yale University.

This survey makes use of data products from the Two Micron All Sky Survey, which is a joint project of the University of Massachusetts and the Infrared Processing and Analysis Center/California Institute of Technology, funded by the National Aeronautics and Space Administration and the National Science Foundation.

A CFHTLS T0007 Wide supplementary information

A.1 Complete list of wide stack coordinates, filters and exposure time

Table 32: The CFHTLS T0007 Wide stack list. Stacks are listed by Cartesian Ident name (column #1). Field coordinates are provided in columns #2 and #3. Column #4 gives the filters in which stacks were observed (important especially for i/y filters). The last five columns quote the total exposure times of T0007 stacks provided by TER-APIX. Highlighted entries denote exposure time and/or filter changes as compared to T0006 due to the VIPERS-DT exposures. The relative positions of all fields of the list are shown in Fig. 19. The complete set of CFHTLS input images combined into each stack are listed in Appendix A.2.

W Cartesian Ident name	CFHTLS Ident name	RA [J2000]	DEC [J2000]	Filters	Exp. Time u^* [s]	Exp. Time g [s]	Exp. Time r [s]	Exp. Time i/y [s]	Exp. Time z [s]
W1(-4 - 4)	020241-104400	02:02:41.15	-10:44:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	7380.0	3600.0
W1(-4 - 3)	020241-094800	02:02:41.15	-09:48:00	u^*, g, r, i, z	3000.0	3000.0	2000.0	4305.0	3600.0
W1(-4 - 2)	020241-085200	02:02:41.15	-08:52:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4920.0	4200.0
W1(-4 - 1)	020241-075600	02:02:41.15	-07:56:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-4 - 0)	020241-070000	02:02:41.15	-07:00:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-4 + 1)	020241-060400	02:02:41.15	-06:04:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-4 + 2)	020241-050800	02:02:41.15	-05:08:00	u^*, g, r, i, z	3000.0	3000.0	2000.0	4305.0	3600.0
W1(-4 + 3)	020241-041200	02:02:41.15	-04:12:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-3 - 4)	020631-104400	02:06:30.86	-10:44:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-3 - 3)	020631-094800	02:06:30.86	-09:48:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-3 - 2)	020631-085200	02:06:30.86	-08:52:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-3 - 1)	020631-075600	02:06:30.86	-07:56:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4920.0	3600.0
W1(-3 - 0)	020631-070000	02:06:30.86	-07:00:00	u^*, g, r, i, z	3000.0	6500.0	2000.0	4305.0	3600.0
W1(-3 + 1)	020631-060400	02:06:30.86	-06:04:00	u^*, g, r, i, z	3000.0	3500.0	2000.0	3690.0	3600.0
W1(-3 + 2)	020631-050800	02:06:30.86	-05:08:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	6600.0
W1(-3 + 3)	020631-041200	02:06:30.86	-04:12:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-2 - 4)	021021-104400	02:10:20.58	-10:44:00	u^*, g, r, y, z	3600.0	2500.0	2000.0	4305.0	3600.0
W1(-2 - 3)	021021-094800	02:10:20.58	-09:48:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-2 - 2)	021021-085200	02:10:20.58	-08:52:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	4305.0	3600.0
W1(-2 - 1)	021021-075600	02:10:20.58	-07:56:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	4305.0	3600.0
W1(-2 - 0)	021021-070000	02:10:20.58	-07:00:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	4305.0	3600.0
W1(-2 + 1)	021021-060400	02:10:20.58	-06:04:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	3690.0	3600.0
W1(-2 + 2)	021021-050800	02:10:20.58	-05:08:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-2 + 3)	021021-041200	02:10:20.58	-04:12:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-1 - 4)	021410-104400	02:14:10.29	-10:44:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-1 - 3)	021410-094800	02:14:10.29	-09:48:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-1 - 2)	021410-085200	02:14:10.29	-08:52:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4920.0	3600.0
W1(-1 - 1)	021410-075600	02:14:10.29	-07:56:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-1 - 0)	021410-070000	02:14:10.29	-07:00:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-1 + 1)	021410-060400	02:14:10.29	-06:04:00	u^*, g, r, i, z	3600.0	3500.0	2000.0	4305.0	3600.0
W1(-1 + 2)	021410-050800	02:14:10.29	-05:08:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	4305.0	6601.0
W1(-1 + 3)	021410-041200	02:14:10.29	-04:12:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	3690.0	6000.0
W1(-0 - 4)	021800-104400	02:18:00.00	-10:44:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-0 - 3)	021800-094800	02:18:00.00	-09:48:00	u^*, g, r, i, z	3000.0	3500.0	2000.0	4305.0	3600.0
W1(-0 - 2)	021800-085200	02:18:00.00	-08:52:00	u^*, g, r, i, z	3000.0	2500.0	3000.0	4305.0	3600.0
W1(-0 - 1)	021800-075600	02:18:00.00	-07:56:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(-0 - 0)	021800-070000	02:18:00.00	-07:00:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4920.0	3600.0
W1(-0 + 1)	021800-060400	02:18:00.00	-06:04:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	4305.0	6601.0
W1(-0 + 2)	021800-050800	02:18:00.00	-05:08:00	u^*, g, r, i, z	3000.0	3000.0	2000.0	4305.0	6000.0
W1(-0 + 3)	021800-041200	02:18:00.00	-04:12:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	6000.0
W1(+1 - 4)	022150-104400	02:21:49.71	-10:44:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(+1 - 3)	022150-094800	02:21:49.71	-09:48:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(+1 - 2)	022150-085200	02:21:49.71	-08:52:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4920.0	3600.0
W1(+1 - 1)	022150-075600	02:21:49.71	-07:56:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4920.0	3600.0
W1(+1 - 0)	022150-070000	02:21:49.71	-07:00:00	u^*, g, r, i, z	3000.0	3000.0	2000.0	4305.0	3600.0
W1(+1 + 1)	022150-060400	02:21:49.71	-06:04:00	u^*, g, r, y, z	3000.0	4500.0	2000.0	3690.0	7201.0
W1(+1 + 2)	022150-050800	02:21:49.71	-05:08:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	6001.0
W1(+1 + 3)	022150-041200	02:21:49.71	-04:12:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	4920.0	6001.0

Continued on next page

Table 32 – Continued from previous page

W Cartesian Ident name	CFHTLS Ident name	RA [J2000]	DEC [J2000]	Filters	Exp. Time u^* [s]	Exp. Time g [s]	Exp. Time r [s]	Exp. Time i/y [s]	Exp. Time z [s]
W1(+2 - 4)	022539-104400	02:25:39.42	-10:44:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(+2 - 3)	022539-094800	02:25:39.42	-09:48:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	4200.0
W1(+2 - 2)	022539-085200	02:25:39.42	-08:52:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(+2 - 1)	022539-075600	02:25:39.42	-07:56:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	3690.0	4200.0
W1(+2 - 0)	022539-070000	02:25:39.42	-07:00:00	u^*, g, r, i, z	3000.0	2500.0	3000.0	3690.0	3600.0
W1(+2 + 1)	022539-060400	02:25:39.42	-06:04:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	2100.0	6000.0
W1(+2 + 2)	022539-050800	02:25:39.42	-05:08:00	u^*, g, r, y, z	6600.0	2500.0	2000.0	4920.0	6000.0
W1(+2 + 3)	022539-041200	02:25:39.42	-04:12:00	u^*, g, r, i, z	5950.0	2500.0	3000.0	4340.0	7200.0
W1(+3 - 4)	022929-104400	02:29:29.14	-10:44:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(+3 - 3)	022929-094800	02:29:29.14	-09:48:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	4305.0	3600.0
W1(+3 - 2)	022929-085200	02:29:29.14	-08:52:00	u^*, g, r, i, z	4200.0	2500.0	2000.0	4305.0	3600.0
W1(+3 - 1)	022929-075600	02:29:29.14	-07:56:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4920.0	3600.0
W1(+3 - 0)	022929-070000	02:29:29.14	-07:00:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4340.0	7201.0
W1(+3 + 1)	022929-060400	02:29:29.14	-06:04:00	u^*, g, r, y, z	3000.0	4450.0	2000.0	3075.0	3600.0
W1(+3 + 2)	022929-050800	02:29:29.14	-05:08:00	u^*, g, r, y, z	4800.0	3950.0	2500.0	1500.0	3600.0
W1(+3 + 3)	022929-041200	02:29:29.14	-04:12:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	3720.0	3600.0
W1(+4 - 4)	023319-104400	02:33:18.85	-10:44:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	7380.0	3600.0
W1(+4 - 3)	023319-094800	02:33:18.85	-09:48:00	u^*, g, r, i, z	3000.0	3000.0	2000.0	4305.0	3600.0
W1(+4 - 2)	023319-085200	02:33:18.85	-08:52:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(+4 - 1)	023319-075600	02:33:18.85	-07:56:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W1(+4 - 0)	023319-070000	02:33:18.85	-07:00:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4960.0	3600.0
W1(+4 + 1)	023319-060400	02:33:18.85	-06:04:00	u^*, g, r, i, z	3000.0	3950.0	2000.0	4340.0	3600.0
W1(+4 + 2)	023319-050800	02:33:18.85	-05:08:00	u^*, g, r, y, z	3000.0	4531.0	2000.0	3075.0	3600.0
W1(+4 + 3)	023319-041200	02:33:18.85	-04:12:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	3720.0	3600.0
W2(-1 - 1)	085011-051100	08:50:11.37	-05:11:00	u^*, g, r, i, z	3000.0	3000.0	2000.0	4305.0	3600.0
W2(-1 - 0)	085011-041500	08:50:11.37	-04:15:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W2(-1 + 1)	085011-031900	08:50:11.37	-03:19:00	u^*, g, r, i, z	3000.0	4000.0	2500.0	4305.0	3600.0
W2(-1 + 2)	085011-022300	08:50:11.37	-02:23:00	u^*, g, r, i, z	3000.0	3000.0	2000.0	4305.0	3600.0
W2(-1 + 3)	085011-012700	08:50:11.37	-01:27:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	3690.0	3600.0
W2(-0 - 1)	085400-051100	08:54:00.00	-05:11:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W2(-0 - 0)	085400-041500	08:54:00.00	-04:15:00	u^*, g, r, i, z	3600.0	3000.0	2000.0	4305.0	4200.0
W2(-0 + 1)	085400-031900	08:54:00.00	-03:19:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W2(-0 + 2)	085400-022300	08:54:00.00	-02:23:00	u^*, g, r, i, z	3000.0	3000.0	2000.0	4305.0	3600.0
W2(-0 + 3)	085400-012700	08:54:00.00	-01:27:00	u^*, g, r, i, z	3000.0	2500.0	3000.0	4305.0	3600.0
W2(+1 - 1)	085749-051100	08:57:48.63	-05:11:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	3690.0	3600.0
W2(+1 - 0)	085749-041500	08:57:48.63	-04:15:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W2(+1 + 1)	085749-031900	08:57:48.63	-03:19:00	u^*, g, r, y, z	3000.0	3000.0	3000.0	4305.0	3600.0
W2(+1 + 2)	085749-022300	08:57:48.63	-02:23:00	u^*, g, r, i, z	3600.0	3000.0	2000.0	4305.0	3600.0
W2(+1 + 3)	085749-012700	08:57:48.63	-01:27:00	u^*, g, r, i, z	3000.0	3000.0	2000.0	3690.0	3600.0
W2(+2 - 1)	090137-051100	09:01:37.26	-05:11:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W2(+2 - 0)	090137-041500	09:01:37.26	-04:15:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W2(+2 + 1)	090137-031900	09:01:37.26	-03:19:00	u^*, g, r, i, z	3000.0	3000.0	2000.0	4305.0	3600.0
W2(+2 + 2)	090137-022300	09:01:37.26	-02:23:00	u^*, g, r, y, z	3000.0	3000.0	2000.0	4305.0	3600.0
W2(+2 + 3)	090137-012700	09:01:37.26	-01:27:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W2(+3 - 1)	090526-051100	09:05:25.89	-05:11:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W2(+3 - 0)	090526-041500	09:05:25.89	-04:15:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W2(+3 + 1)	090526-031900	09:05:25.89	-03:19:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	3690.0	3600.0
W2(+3 + 2)	090526-022300	09:05:25.89	-02:23:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4325.0	7201.0
W2(+3 + 3)	090526-012700	09:05:25.89	-01:27:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W3(-3 - 3)	140016+514231	14:00:16.28	+51:42:31	u^*, g, r, i, z	3001.0	2500.0	2000.0	4306.0	3601.0
W3(-3 - 2)	135955+523831	13:59:55.42	+52:38:31	u^*, g, r, i, z	3000.0	2500.0	2000.0	4306.0	4201.0
W3(-3 - 1)	135933+533431	13:59:33.41	+53:34:31	u^*, g, r, i, z	3000.0	2500.0	2000.0	3720.0	3601.0
W3(-3 - 0)	135910+543031	13:59:10.19	+54:30:31	u^*, g, r, i, z	3000.0	2500.0	2000.0	4306.0	3601.0
W3(-3 + 1)	135846+552631	13:58:45.65	+55:26:31	u^*, g, r, y, z	3001.0	2500.0	2000.0	4306.0	3601.0
W3(-3 + 2)	135820+562231	13:58:19.70	+56:22:31	u^*, g, r, i, z	3000.0	2500.0	2500.0	4306.0	3601.0
W3(-3 + 3)	135752+571831	13:57:52.22	+57:18:31	u^*, g, r, i, z	3000.0	2501.0	2000.0	4306.0	3601.0
W3(-2 - 3)	140609+514231	14:06:08.85	+51:42:31	u^*, g, r, i, z	3000.0	2500.0	2000.0	4306.0	3601.0
W3(-2 - 2)	140555+523831	14:05:54.95	+52:38:31	u^*, g, r, i, z	3001.0	2500.0	2000.0	4306.0	3601.0
W3(-2 - 1)	140540+533431	14:05:40.27	+53:34:31	u^*, g, r, y, z	3000.0	2500.0	2000.0	4306.0	3601.0
W3(-2 - 0)	140525+543031	14:05:24.79	+54:30:31	u^*, g, r, i, z	3000.0	2500.0	2000.0	3691.0	3601.0
W3(-2 + 1)	140509+552631	14:05:08.43	+55:26:31	u^*, g, r, y, z	3000.0	2501.0	2501.0	4306.0	3601.0

Continued on next page

Table 32 – Continued from previous page

W Cartesian Ident name	CFHTLS Ident name	RA [J2000]	DEC [J2000]	Filters	Exp. Time u^* [s]	Exp. Time g [s]	Exp. Time r [s]	Exp. Time i/y [s]	Exp. Time z [s]
W3(−2 + 2)	140451+562231	14:04:51.13	+56:22:31	u^*, g, r, i, z	3000.0	2501.0	2000.0	3691.0	3601.0
W3(−2 + 3)	140433+571831	14:04:32.82	+57:18:31	u^*, g, r, y, z	3000.0	2501.0	3001.0	4306.0	3601.0
W3(−1 − 3)	141202+514231	14:12:01.43	+51:42:31	u^*, g, r, i, z	3000.0	2500.0	2000.0	6152.0	3601.0
W3(−1 − 2)	141155+523831	14:11:54.47	+52:38:31	u^*, g, r, i, z	3000.0	2501.0	2501.0	4306.0	3601.0
W3(−1 − 1)	141147+533431	14:11:47.14	+53:34:31	u^*, g, r, i, z	3001.0	2500.0	2000.0	4306.0	3601.0
W3(−1 − 0)	141139+543031	14:11:39.40	+54:30:31	u^*, g, r, i, z	3000.0	2500.0	2000.0	4306.0	3601.0
W3(−1 + 1)	141131+552631	14:11:31.22	+55:26:31	u^*, g, r, i, z	3000.0	2501.0	2001.0	3691.0	3601.0
W3(−1 + 2)	141123+562231	14:11:22.56	+56:22:31	u^*, g, r, i, z	3000.0	2501.0	2001.0	4306.0	3601.0
W3(−1 + 3)	141113+571831	14:11:13.41	+57:18:31	u^*, g, r, y, z	3001.0	2501.0	2000.0	4306.0	3601.0
W3(−0 − 3)	141754+514231	14:17:54.00	+51:42:31	u^*, g, r, i, z	3000.0	2500.0	3001.0	4341.0	3601.0
W3(−0 − 2)	141754+523831	14:17:54.00	+52:38:31	u^*, g, r, i, z	3000.0	2500.0	2501.0	4341.0	3601.0
W3(−0 − 1)	141754+533431	14:17:54.00	+53:34:31	u^*, g, r, i, z	3001.0	2500.0	2500.0	3721.0	3601.0
W3(−0 − 0)	141754+543031	14:17:54.00	+54:30:31	u^*, g, r, i, z	3000.0	2500.0	2000.0	4341.0	3601.0
W3(−0 + 1)	141754+552631	14:17:54.00	+55:26:31	u^*, g, r, i, z	3000.0	2501.0	2000.0	4306.0	3601.0
W3(−0 + 2)	141754+562231	14:17:54.00	+56:22:31	u^*, g, r, i, z	3001.0	2501.0	2001.0	4306.0	3601.0
W3(−0 + 3)	141754+571831	14:17:54.00	+57:18:31	u^*, g, r, i, z	3001.0	2501.0	2000.0	4306.0	3601.0
W3(+1 − 3)	142347+514231	14:23:46.57	+51:42:31	u^*, g, r, i, z	3000.0	3001.0	2501.0	4341.0	4201.0
W3(+1 − 2)	142354+523831	14:23:53.53	+52:38:31	u^*, g, r, i, z	3001.0	2501.0	2000.0	4341.0	3601.0
W3(+1 − 1)	142401+533431	14:24:00.86	+53:34:31	u^*, g, r, i, z	3000.0	2501.0	2000.0	4341.0	6002.0
W3(+1 − 0)	142409+543031	14:24:08.61	+54:30:31	u^*, g, r, i, z	3001.0	2501.0	2000.0	4341.0	5401.0
W3(+1 + 1)	142417+552631	14:24:16.79	+55:26:31	u^*, g, r, i, z	3001.0	2500.0	2000.0	4306.0	3601.0
W3(+1 + 2)	142425+562231	14:24:25.44	+56:22:31	u^*, g, r, i, z	6001.0	2501.0	2000.0	4306.0	3601.0
W3(+1 + 3)	142435+571831	14:24:34.59	+57:18:31	u^*, g, r, i, z	3001.0	2501.0	2000.0	4306.0	3601.0
W3(+2 − 3)	142939+514231	14:29:39.15	+51:42:31	u^*, g, r, i, z	3001.0	2501.0	2000.0	4961.0	4201.0
W3(+2 − 2)	142953+523831	14:29:53.05	+52:38:31	u^*, g, r, i, z	3000.0	3501.0	2000.0	4341.0	3600.0
W3(+2 − 1)	143008+533431	14:30:07.72	+53:34:31	u^*, g, r, i, z	3000.0	2501.0	2000.0	4961.0	3601.0
W3(+2 − 0)	143023+543031	14:30:23.21	+54:30:31	u^*, g, r, i, z	3001.0	2501.0	2000.0	4306.0	3601.0
W3(+2 + 1)	143040+552631	14:30:39.57	+55:26:31	u^*, g, r, i, z	3001.0	2500.0	2000.0	4306.0	4801.0
W3(+2 + 2)	143057+562231	14:30:56.87	+56:22:31	u^*, g, r, i, z	3001.0	2501.0	2000.0	4306.0	3601.0
W3(+2 + 3)	143115+571831	14:31:15.18	+57:18:31	u^*, g, r, i, z	3001.0	2500.0	2000.0	4306.0	3601.0
W3(+3 − 3)	143532+514231	14:35:31.73	+51:42:31	u^*, g, r, i, z	3001.0	2500.0	2000.0	3691.0	3601.0
W3(+3 − 2)	143553+523831	14:35:52.59	+52:38:31	u^*, g, r, i, z	3000.0	2500.0	2000.0	3691.0	3601.0
W3(+3 − 1)	143615+533431	14:36:14.59	+53:34:31	u^*, g, r, y, z	3000.0	2500.0	2000.0	4306.0	3601.0
W3(+3 − 0)	143638+543031	14:36:37.81	+54:30:31	u^*, g, r, i, z	3000.0	2500.0	2000.0	4306.0	3601.0
W3(+3 + 1)	143702+552631	14:37:02.35	+55:26:31	u^*, g, r, i, z	3001.0	2501.0	2000.0	4306.0	3601.0
W3(+3 + 2)	143728+562231	14:37:28.30	+56:22:31	u^*, g, r, y, z	3001.0	2500.0	2000.0	4921.0	3601.0
W3(+3 + 3)	143756+571831	14:37:55.78	+57:18:31	u^*, g, r, i, z	3001.0	2500.0	2000.0	4306.0	3601.0
W4(+2 − 2)	222054−003100	22:20:53.78	−00:31:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	7995.0	7800.0
W4(+2 − 1)	222054+002300	22:20:53.77	+00:23:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	7200.0
W4(+2 + 0)	222054+011900	22:20:53.88	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(+1 − 2)	221706−003100	22:17:05.77	−00:31:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	3690.0	3600.0
W4(+1 − 1)	221706+002300	22:17:05.77	+00:23:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	8611.0	3600.0
W4(+1 + 0)	221706+011900	22:17:05.82	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(+1 + 1)	221706+021500	22:17:05.94	+02:15:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(+0 − 2)	221318−003100	22:13:17.76	−00:31:00	u^*, g, r, i, z	3000.0	5000.0	2000.0	4305.0	3600.0
W4(+0 − 1)	221318+002300	22:13:17.76	+00:23:00	u^*, g, r, i, z	3000.0	5000.0	2000.0	4305.0	3600.0
W4(+0 + 0)	221318+011900	22:13:17.76	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	4305.0	7200.0
W4(+0 + 1)	221318+021500	22:13:17.76	+02:15:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(−1 − 2)	220930−003100	22:09:29.75	−00:31:00	u^*, g, r, i, z	3000.0	2500.0	3000.0	4305.0	3600.0
W4(−1 − 1)	220930+002300	22:09:29.76	+00:23:00	u^*, g, r, y, z	3000.0	5500.0	2000.0	4305.0	3600.0
W4(−1 + 0)	220930+011900	22:09:29.70	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(−1 + 1)	220930+021500	22:09:29.59	+02:15:00	u^*, g, r, y, z	3000.0	5000.0	2000.0	4305.0	3600.0
W4(−1 + 2)	220930+031100	22:09:29.41	+03:11:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(−1 + 3)	220930+040700	22:09:29.17	+04:07:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(−2 + 0)	220542+011900	22:05:41.64	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	7995.0	3600.0
W4(−2 + 1)	220542+021500	22:05:41.41	+02:15:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(−2 + 2)	220542+031100	22:05:41.06	+03:11:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(−2 + 3)	220542+040700	22:05:40.58	+04:07:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(−3 + 0)	220154+011900	22:01:53.58	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(−3 + 1)	220154+021500	22:01:53.23	+02:15:00	u^*, g, r, i, z	4200.0	2500.0	2000.0	4305.0	3600.0
W4(−3 + 2)	220154+031100	22:01:52.70	+03:11:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(−3 + 3)	220154+040700	22:01:51.99	+04:07:00	u^*, g, r, y, z	3000.0	3000.0	2000.0	4305.0	3600.0

Continued on next page

Table 32 – *Continued from previous page*

W Cartesian Ident name	CFHTLS Ident name	RA [J2000]	DEC [J2000]	Filters	Exp. Time u^* [s]	Exp. Time g [s]	Exp. Time r [s]	Exp. Time i/y [s]	Exp. Time z [s]
W4(+2 – 2)	222054-003100	22:20:53.78	-00:31:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	7995.0	7800.0
W4(+2 – 1)	222054+002300	22:20:53.77	+00:23:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	7200.0
W4(+2 + 0)	222054+011900	22:20:53.88	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(+1 – 2)	221706-003100	22:17:05.77	-00:31:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	3690.0	3600.0
W4(+1 – 1)	221706+002300	22:17:05.77	+00:23:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	8611.0	3600.0
W4(+1 + 0)	221706+011900	22:17:05.82	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(+1 + 1)	221706+021500	22:17:05.94	+02:15:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(+0 – 2)	221318-003100	22:13:17.76	-00:31:00	u^*, g, r, i, z	3000.0	5000.0	2000.0	4305.0	3600.0
W4(+0 – 1)	221318+002300	22:13:17.76	+00:23:00	u^*, g, r, i, z	3000.0	5000.0	2000.0	4305.0	3600.0
W4(+0 + 0)	221318+011900	22:13:17.76	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	4305.0	7200.0
W4(+0 + 1)	221318+021500	22:13:17.76	+02:15:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(–1 – 2)	220930-003100	22:09:29.75	-00:31:00	u^*, g, r, i, z	3000.0	2500.0	3000.0	4305.0	3600.0
W4(–1 – 1)	220930+002300	22:09:29.76	+00:23:00	u^*, g, r, y, z	3000.0	5500.0	2000.0	4305.0	3600.0
W4(–1 + 0)	220930+011900	22:09:29.70	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(–1 + 1)	220930+021500	22:09:29.59	+02:15:00	u^*, g, r, y, z	3000.0	5000.0	2000.0	4305.0	3600.0
W4(–1 + 2)	220930+031100	22:09:29.41	+03:11:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(–1 + 3)	220930+040700	22:09:29.17	+04:07:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(–2 + 0)	220542+011900	22:05:41.64	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2500.0	7995.0	3600.0
W4(–2 + 1)	220542+021500	22:05:41.41	+02:15:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(–2 + 2)	220542+031100	22:05:41.06	+03:11:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(–2 + 3)	220542+040700	22:05:40.58	+04:07:00	u^*, g, r, y, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(–3 + 0)	220154+011900	22:01:53.58	+01:19:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(–3 + 1)	220154+021500	22:01:53.23	+02:15:00	u^*, g, r, i, z	4200.0	2500.0	2000.0	4305.0	3600.0
W4(–3 + 2)	220154+031100	22:01:52.70	+03:11:00	u^*, g, r, i, z	3000.0	2500.0	2000.0	4305.0	3600.0
W4(–3 + 3)	220154+040700	22:01:51.99	+04:07:00	u^*, g, r, y, z	3000.0	3000.0	2000.0	4305.0	3600.0

A.2 List of images in each Wide stack

Table 33: Full list of CFHTLS input images included in each Wide stacks. Highlighted entries denote new images or filter change as compared to T0006 (due to VIPERS-DT data). The corresponding exposure times, or any details regarding each stack, are quoted in Tables 32, and in the T0007 synoptic table

W Cartesian Ident Name	Filter	CFHTL odometer number of input images combined in stacks
W1(-4-4)	u^*	1022212,1022213,1022214,1022215,1022216
	g	942766,942767,942768,942769,942770
	r	816609,816610,1014659,1014660
	y	967664,967665,967666,967894,967895,967896,1030576,1030578,1030579,1030580,1030581,1038680
	z	1037804,1037805,1037806,1037807,1037808,1037809
W1(-4-3)	u^*	1022217,1022218,1022219,1022220,1022221
	g	862819,862822,862823,862824,862956,862957
	r	814948,814949,1014657,1014658
	i	880193,880194,880195,880196,880197,880198,880199
	z	1038038,1038039,1038040,1038041,1038042,1038043
W1(-4-2)	u^*	1030705,1030706,1030708,1030710,1030748
	g	879742,879743,879744,879745,879746
	r	814942,814943,1014655,1014656
	i	880200,880201,880203,880204,880205,880206,880207,880208
	z	1038045,1038046,1038350,1038351,1038353,1038356,1038357
W1(-4-1)	u^*	1030698,1030699,1030701,1030704,1038673
	g	879977,879978,879979,879980,879981
	r	811173,811174,811181,811186
	i	880209,880210,880211,880212,880213,880214,880215
	z	1038355,1038358,1038359,1038360,1038361,1038362
W1(-4-0)	u^*	1030595,1030596,1030597,1030696,1030697
	g	880967,880968,880969,880970,880971
	r	814940,814941,1014651,1014652

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W1(-4+1)	<i>i</i>	880434,880436,880437,880438,880439,880440,880441
	<i>z</i>	1038476,1038477,1038478,1038479,1038480,1038481
	<i>u*</i>	1030590,1030591,1030592,1030593,1038672
	<i>g</i>	880972,880973,880974,880975,880976
	<i>r</i>	810510,810511,1014649,1014650
	<i>i</i>	880977,880978,880979,880980,880981,880982,880983
W1(-4+2)	<i>z</i>	1038482,1038483,1038484,1038485,1038486,1038487
	<i>u*</i>	1030585,1030586,1030587,1030588,1030589
	<i>g</i>	883305,883306,885065,885317,885318,885319
	<i>r</i>	810504,810505,1014467,1014468
	<i>i</i>	881254,881255,881256,881257,881258,881259,881260
	<i>z</i>	1038488,1038489,1038490,1038491,1038493,1038661
W1(-4+3)	<i>u*</i>	1030476,1030477,1038669,1038670,1038671
	<i>g</i>	885422,885423,885424,885425,1031327
	<i>r</i>	810496,810497,1014465,1014466
	<i>i</i>	881261,881262,881263,881264,881265,881266,881267
	<i>z</i>	1038494,1038495,1038496,1038497,1038498,1038499
	<i>u*</i>	1030749,1030778,1030779,1030780,1030781
W1(-3-4)	<i>g</i>	942771,942772,942773,942774,942775
	<i>r</i>	816607,816608,1021185,1021186
	<i>y</i>	964850,964851,964852,964853,964854,964855,964856
	<i>z</i>	1037798,1037799,1037800,1037801,1037802,1037803
	<i>u*</i>	1030468,1030469,1030470,1030471,1030472
	<i>g</i>	872207,872208,872209,872210,872211
W1(-3-2)	<i>r</i>	814956,814957,1014463,1014464
	<i>i</i>	879636,879638,879639,879640,879641,879642,879643
	<i>z</i>	1030196,1030197,1030198,1030199,1030200,1030201
	<i>u*</i>	1022616,1022617,1022618,1022619,1022620
	<i>g</i>	872212,872213,872214,872215,872216
	<i>r</i>	810486,810487,1014461,1014462
W1(-3-1)	<i>i</i>	879644,879645,879646,879647,879648,879649,879650
	<i>z</i>	1030190,1030191,1030192,1030193,1030194,1030195
	<i>u*</i>	1022611,1022612,1022613,1022614,1022615
	<i>g</i>	872217,872218,872219,872220,872222
	<i>r</i>	810488,810516,1014459,1014460
	<i>i</i>	879747,879748,879749,879750,879753,879982,879983,879984
W1(-3-0)	<i>z</i>	1030075,1030076,1030077,1030078,1030079,1030080
	<i>u*</i>	1030463,1030464,1030465,1030466,1030467
	<i>g</i>	872277,872279,872280,872281,872282,872283,872284,872285,872286,872287,872289,872290,872291
	<i>r</i>	810491,810517,1014008,1014009
	<i>i</i>	879985,879986,879987,879988,879989,879991,879992
	<i>z</i>	1030069,1030070,1030071,1030072,1030073,1030074
W1(-3+1)	<i>u*</i>	1022472,1022473,1022475,1022476,1022610
	<i>g</i>	875012,875013,875014,875015,875016,875017,875018
	<i>r</i>	810492,810493,1014006,1014007
	<i>i</i>	880087,880088,880089,880091,880092,880093
	<i>z</i>	1030063,1030064,1030065,1030066,1030067,1030068
	<i>u*</i>	1022467,1022470,1022471,1022608,1022609
W1(-3+2)	<i>g</i>	875122,875123,875124,875125,875126
	<i>r</i>	810494,810495,1013887,1013888
	<i>i</i>	880094,880095,880096,880097,880098,880099,880100
	<i>z</i>	1022623,1022624,1022625,1022626,1022627,1030057,1030058,1030059,1030060,1030061,1030062
	<i>u*</i>	1022462,1022463,1022464,1022465,1022466
	<i>g</i>	879631,879632,879633,879634,879635
W1(-2-4)	<i>r</i>	809745,809746,1013885,1013886
	<i>i</i>	880101,880102,880103,880104,880105,880106,880107
	<i>z</i>	1022602,1022603,1022604,1022605,1022606,1022607
	<i>u*</i>	1030783,1030784,1030787,1030788,1030789,1030790
	<i>g</i>	942777,942778,942779,942781,942782
	<i>r</i>	816405,816406,1021187,1021188
W1(-2-3)	<i>y</i>	964843,964844,964845,964846,964847,964848,964849
	<i>z</i>	1033066,1033067,1033068,1033069,1033070,1033071
	<i>u*</i>	955734,955735,955736,955737,955738
	<i>g</i>	872201,872202,872203,872205,872206

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W1(-2-2)	<i>r</i>	814962,814963,1022114,1022115
	<i>i</i>	875622,875623,875627,875783,875784,875785,875786
	<i>z</i>	964970,964971,964972,964973,964974,964975
	<i>u*</i>	948436,948437,948438,948439,948440
	<i>g</i>	827404,827405,827406,827407,827408
	<i>r</i>	810417,810484,810485,1022477,1022478
W1(-2-1)	<i>i</i>	827409,827411,827412,827413,827414,827415,827416
	<i>z</i>	948613,948614,948615,948616,948617,948618
	<i>u*</i>	948328,948329,948330,948331,948332
	<i>g</i>	821835,821836,821837,821838,821839
	<i>r</i>	809512,809612,809613,1022621,1022622
	<i>i</i>	821845,821846,821847,821848,821849,821850,821851
W1(-2-0)	<i>z</i>	947407,947409,955003,955004,955005,955006
	<i>u*</i>	948311,948312,948313,948314,948315
	<i>g</i>	821598,821599,821600,821602,821603
	<i>r</i>	809506,809610,809611,1022481,1022482
	<i>i</i>	821604,821608,821609,821610,821612,821613,821614
	<i>z</i>	947392,947393,947395,947396,947397,947398
W1(-2+1)	<i>u*</i>	947860,947861,947862,947863,947864
	<i>g</i>	821593,821594,821595,821596,821597
	<i>r</i>	809500,809501,1022225,1022226
	<i>i</i>	820501,820502,820565,820566,820567,820568
	<i>z</i>	942131,942132,942133,942134,942143,942197
	<i>u*</i>	947855,947856,947857,947858,947859
W1(-2+2)	<i>g</i>	820488,820489,820490,820491,820492
	<i>r</i>	806863,806864,1022222,1022223
	<i>i</i>	820493,820494,820495,820496,820497,820498,820499
	<i>z</i>	890897,890898,890899,890900,890901,890902
	<i>u*</i>	947845,947846,947847,947848,947849
	<i>g</i>	820483,820484,820485,820486,820487
W1(-2+3)	<i>r</i>	806861,806862,1022479,1022480
	<i>i</i>	820409,820410,820411,820412,820413,820414,820415
	<i>z</i>	891213,891214,891215,891216,891217,891218
	<i>u*</i>	1030791,1030792,1030793,1030794,1030795
	<i>g</i>	948431,948432,948433,948434,948435
	<i>r</i>	816403,816404,1021189,1021190
W1(-1-4)	<i>y</i>	964005,964006,964007,964008,964009,964010,964011
	<i>z</i>	1033060,1033061,1033062,1033063,1033064,1033065
	<i>u*</i>	955393,955394,955395,955396,955397
	<i>g</i>	870647,870648,870649,870650,870802
	<i>r</i>	814969,814970,1022112,1022113
	<i>i</i>	875435,875436,875437,875438,875439,875441,875442
W1(-1-2)	<i>z</i>	964962,964963,964964,964966,964967,964968
	<i>u*</i>	947850,947851,947852,947853,947854
	<i>g</i>	827417,827418,827419,827420,827421
	<i>r</i>	810415,810416,1021976,1021977
	<i>i</i>	831270,831271,831272,831273,831274,831275,831276,831277
	<i>z</i>	890762,890763,890764,890765,890767,890768
W1(-1-1)	<i>u*</i>	942315,942316,942317,942318,942319
	<i>g</i>	821840,821841,821842,821843,821844
	<i>r</i>	809518,809519,1021974,1021975
	<i>i</i>	821852,821853,821854,821855,821856,821857,821858
	<i>z</i>	880680,880681,880682,880683,880684,880685
	<i>u*</i>	889435,889436,889437,889438,889439
W1(-1-0)	<i>g</i>	820397,820398,820399,820400,820401
	<i>r</i>	806859,806860,1021972,1021973
	<i>i</i>	820402,820403,820404,820405,820406,820407,820408
	<i>z</i>	874465,874466,874467,874468,874469,874470
	<i>u*</i>	880764,883008,883009,883011,883012,1031324
	<i>g</i>	816622,816784,819864,819865,819866,819867,819868
W1(-1+1)	<i>r</i>	806857,806858,1021970,1021971
	<i>i</i>	821586,821587,821588,821589,821590,821591,821592
	<i>z</i>	874117,874460,874461,874462,874463,874464
	<i>u*</i>	765305,765306,765307,765308,765309

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W1(-1+3)	<i>g</i>	765310,765316,765317,765318,765319
	<i>r</i>	759164,765302,765303,1021968,1021969
	<i>i</i>	764947,764948,764949,764950,764951,764952,764953
	<i>z</i>	765761,765762,765763,765764,765765,765766,766294,766295,766296,766297,766298
	<i>u*</i>	765365,765366,765367,765368,765369
	<i>g</i>	765354,765358,765359,765362,765363
	<i>r</i>	758894,758895,1021966,1021967
W1(-0-4)	<i>i</i>	762828,762832,762833,762834,762835,762836
	<i>z</i>	765371,765372,765373,765374,765375,766359,766360,766361,766362,766363
	<i>u*</i>	1030962,1030963,1030964,1030965,1030966
	<i>g</i>	942215,942216,942217,942219,942220
	<i>r</i>	816397,816398,1021191,1021192
	<i>y</i>	963763,963764,963765,963766,963767,963768,963769
	<i>z</i>	1037792,1037793,1037794,1037795,1037796,1037797
W1(-0-3)	<i>u*</i>	948622,948623,948626,955391,955392
	<i>g</i>	863927,864040,870641,870642,870643,870644,870645
	<i>r</i>	814975,814976,1022110,1022111
	<i>i</i>	863913,863914,863920,863922,863923,863924,863925
	<i>z</i>	963435,963436,963437,963438,963439,963440
	<i>u*</i>	947503,947504,947505,947506,947507
	<i>g</i>	827422,827423,827424,827425,827426
W1(-0-2)	<i>r</i>	810993,810994,810995,810996,1021978,1021979
	<i>i</i>	831160,831161,831162,831163,831164,831165,831166
	<i>z</i>	890351,890352,890353,890354,890355,890356
	<i>u*</i>	942205,942206,942207,942208,942209
	<i>g</i>	826625,826626,826627,826628,826629
	<i>r</i>	809614,809615,1021830,1021831
	<i>i</i>	826519,826520,826521,826522,826523,826524,826525
W1(-0-1)	<i>z</i>	880664,880665,880666,880668,880669,880670
	<i>u*</i>	889633,889634,889635,889636,889637
	<i>g</i>	816413,816414,816415,816416,816509
	<i>r</i>	806855,806856,1021832,1021833
	<i>i</i>	816895,819719,819720,819721,819722,819723,819724,819725
	<i>z</i>	874471,874472,874473,874474,874475,874476
	<i>u*</i>	761701,761702,761703,761704,761705
W1(-0+1)	<i>g</i>	761321,761322,761323,761324,761325
	<i>r</i>	759155,761326,761327,1021834,1021835
	<i>i</i>	762493,762494,762495,762496,762497,762498,762499
	<i>z</i>	765767,765768,765769,765770,765771,765772,766289,766290,766291,766292,766293
	<i>u*</i>	761981,761982,761983,761984,761985
	<i>g</i>	762628,765155,765156,765157,765158,765159
	<i>r</i>	759153,759154,1021962,1021963
W1(-0+2)	<i>i</i>	762474,762475,762476,762477,762478,762479,762480
	<i>z</i>	764800,764801,764802,764803,764804,766177,766178,766179,766180,766181
	<i>u*</i>	761970,761971,761972,761973,761974
	<i>g</i>	762623,762624,762625,762626,762627
	<i>r</i>	758577,758578,1021964,1021965
	<i>i</i>	762390,762391,762392,762393,762394,762395,762396
	<i>z</i>	764795,764796,764797,764798,764799,766170,766171,766172,766173,766174
W1(+1-4)	<i>u*</i>	1030967,1030968,1030969,1030970,1030971
	<i>g</i>	942210,942211,942212,942213,942214
	<i>r</i>	815808,816392,1021193,1021194
	<i>y</i>	963756,963757,963758,963759,963760,963761,963762
	<i>z</i>	1032875,1032876,1032877,1032878,1032879,1032880
	<i>u*</i>	948451,948619,948620,948621,1031326
	<i>g</i>	863283,863284,863285,863286,863287
W1(+1-3)	<i>r</i>	815132,815133,1022108,1022109
	<i>i</i>	875443,875444,875445,875446,875447,875448,875449
	<i>z</i>	955020,955021,955212,955213,955214,955215
	<i>u*</i>	947498,947499,947500,947501,947502
	<i>g</i>	827325,827326,827327,827328,827329
	<i>r</i>	809776,809777,1021980,1021981
	<i>i</i>	830980,831153,831154,831155,831156,831157,831158,831159
W1(+1-2)	<i>z</i>	889306,889307,889308,889309,889310,889311

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W1(+1-1)	u^*	883299,883300,883301,883302,883303
	g	826630,826631,826645,826646,826647
	r	809620,809621,1021828,1021829
	y	1030480,1038662,1038663,1038664,1038665,1038666,1038667,1038668
W1(+1-0)	z	884123,884124,884125,884126,884127,884128
	u^*	942076,942077,942080,942081,942082
	g	816407,816408,816409,816410,816411,816412
	r	806761,806762,1021814,1021815
W1(+1+1)	i	819869,819870,819871,819872,819873,819874,819875
	z	831420,831421,831422,831423,831532,831533
	u^*	761469,761470,761471,761472,761473
	g	761197,761198,761199,761200,761320,761582,761583,761584,761585
W1(+1+2)	r	758575,758576,1021683,1021684
	y	1030457,1030458,1030459,1030460,1030461,1030462
	z	761588,761592,761696,761697,761698,761699,761700,766164,766165,766166,766167,766168
	u^*	761838,761839,761840,761841,761842
W1(+1+3)	g	761826,761827,761828,761829,761830
	r	758401,758402,1021681,1021682
	i	760933,760934,760935,760936,760938,760939,760940
	z	764954,764955,764956,764957,764958,765858,765860,765861,765862
W1(+2-4)	u^*	761832,761833,761834,761835,761836
	g	728058,728059,728060,728061,728062
	r	779979,779980,780209,1021679,1021680
	i	758566,758567,758568,758569,758570,758571,758572,758573
W1(+2-3)	z	761059,761060,761061,761062,761063,765851,765852,765853,765854,765855
	u^*	1030972,1030973,1030974,1030975,1030976
	g	942050,942051,942052,942053,942075
	r	815620,815622,1021195,1021196
W1(+2-2)	y	963132,963133,963134,963135,963136,963137,963138
	z	1032233,1032234,1032235,1032236,1032237,1032238
	u^*	948441,948442,948443,948444,948445
	g	863090,863091,863092,863093,863094
W1(+2-1)	r	815138,815139,1022106,1022107
	i	875613,875614,875616,875617,875618,875619,875620
	z	960408,962895,962896,962897,962898,962899,962900
	u^*	947399,947400,947401,947402,1031325
W1(+2-0)	g	827313,827314,827315,827316,827317
	r	809770,809771,1021982,1021983
	i	827318,827319,827320,827321,827322,827323,827324
	z	885304,885306,885307,885308,885309,885310
W1(+2+1)	u^*	942200,942201,942202,942203,942204
	g	826736,826737,826738,826739,826740
	r	809626,809627,1021826,1021827
	i	826729,826731,826732,826733,826734,826735
W1(+2+2)	z	881347,884117,884118,884119,884120,884121,884122
	u^*	934919,934920,934921,935068,935200
	g	732957,732958,732959,732960,732961
	r	729725,729726,806759,806760,1021816,1021817
W1(+2+3)	i	816763,816764,816765,816766,816768,816769
	z	879864,879865,879866,879867,879868,879869
	u^*	761975,761976,761977,761978,761979
	g	728046,728047,728048,728049,728050
W1(+2+4)	r	727579,727580,1021673,1021674
	y	1110944,1110945,1118156,1118157,1118158,1118159,1118308
	z	764693,764694,764695,764696,764697,765846,765847,765848,765849,765850
	u^*	758888,758889,758890,758891,758892,1110668,1110669,1110670,1110671,1110672,1110673
W1(+2+5)	g	727461,727462,727463,727464,727465
	r	727459,727460,1021675,1021676
	y	1030300,1030301,1030302,1030303,1030305,1030306,1038678,1038679
	z	760942,760943,760944,760945,760946,760947,765774,765775,765776,765777,765778
W1(+2+6)	u^*	719023,719024,719025,719026,719027,719028,719029
	g	715499,715500,715501,715502,715503
	r	715071,715072,715073,715074,1021677,1021678
	i	715226,715227,715228,715229,715230,715231,715232

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W1(+1-0)	<i>z</i>	718692,718693,718694,718695,718696,718697,718698,718699,718700
	<i>u*</i>	942076,942077,942080,942081,942082
	<i>g</i>	816407,816408,816409,816410,816411,816412
	<i>r</i>	806761,806762,1021814,1021815
	<i>i</i>	819869,819870,819871,819872,819873,819874,819875
W1(+1+1)	<i>z</i>	831420,831421,831422,831423,831532,831533
	<i>u*</i>	761469,761470,761471,761472,761473
	<i>g</i>	761197,761198,761199,761200,761320,761582,761583,761584,761585
	<i>r</i>	758575,758576,1021683,1021684
	<i>y</i>	1030457,1030458,1030459,1030460,1030461,1030462
W1(+1+2)	<i>z</i>	761588,761592,761696,761697,761698,761699,761700,766164,766165,766166,766167,766168
	<i>u*</i>	761838,761839,761840,761841,761842
	<i>g</i>	761826,761827,761828,761829,761830
	<i>r</i>	758401,758402,1021681,1021682
	<i>i</i>	760933,760934,760935,760936,760938,760939,760940
W1(+1+3)	<i>z</i>	764954,764955,764956,764957,764958,765858,765859,765860,765861,765862
	<i>u*</i>	761832,761833,761834,761835,761836
	<i>g</i>	728058,728059,728060,728061,728062
	<i>r</i>	779979,779980,780209,1021679,1021680
	<i>i</i>	758566,758567,758568,758569,758570,758571,758572,758573
W1(+2-4)	<i>z</i>	761059,761060,761061,761062,761063,765851,765852,765853,765854,765855
	<i>u*</i>	1030972,1030973,1030974,1030975,1030976
	<i>g</i>	942050,942051,942052,942053,942075
	<i>r</i>	815620,815622,1021195,1021196
	<i>y</i>	963132,963133,963134,963135,963136,963137,963138
W1(+2-3)	<i>z</i>	1032233,1032234,1032235,1032236,1032237,1032238
	<i>u*</i>	948441,948442,948443,948444,948445
	<i>g</i>	863090,863091,863092,863093,863094
	<i>r</i>	815138,815139,1022106,1022107
	<i>i</i>	875613,875614,875616,875617,875618,875619,875620
W1(+2-2)	<i>z</i>	960408,962895,962896,962897,962898,962899,962900
	<i>u*</i>	947399,947400,947401,947402,1031325
	<i>g</i>	827313,827314,827315,827316,827317
	<i>r</i>	809770,809771,1021982,1021983
	<i>i</i>	827318,827319,827320,827321,827322,827323,827324
W1(+2-1)	<i>z</i>	885304,885306,885307,885308,885309,885310
	<i>u*</i>	942200,942201,942202,942203,942204
	<i>g</i>	826736,826737,826738,826739,826740
	<i>r</i>	809626,809627,1021826,1021827
	<i>i</i>	826729,826731,826732,826733,826734,826735
W1(+2-0)	<i>z</i>	881347,884117,884118,884119,884120,884121,884122
	<i>u*</i>	934919,934920,934921,935068,935200
	<i>g</i>	732957,732958,732959,732960,732961
	<i>r</i>	729725,729726,806759,806760,1021816,1021817
	<i>i</i>	816763,816764,816765,816766,816768,816769
W1(+2+1)	<i>z</i>	879864,879865,879866,879867,879868,879869
	<i>u*</i>	761975,761976,761977,761978,761979
	<i>g</i>	728046,728047,728048,728049,728050
	<i>r</i>	727579,727580,1021673,1021674
	<i>y</i>	1110944,1110945,1118156,1118157,1118158,1118159,1118308
W1(+2+2)	<i>z</i>	764693,764694,764695,764696,764697,765846,765847,765848,765849,765850
	<i>u*</i>	758888,758889,758890,758891,758892,1110668,1110669,1110670,1110671,1110672,1110673
	<i>g</i>	727461,727462,727463,727464,727465
	<i>r</i>	727459,727460,1021675,1021676
	<i>y</i>	1030300,1030301,1030302,1030303,1030305,1030306,1038678,1038679
W1(+2+3)	<i>z</i>	760942,760943,760944,760945,760946,765774,765775,765776,765777,765778
	<i>u*</i>	719023,719024,719025,719026,719027,719028,719029
	<i>g</i>	715499,715500,715501,715502,715503
	<i>r</i>	715071,715072,715073,715074,1021677,1021678
	<i>i</i>	715226,715227,715228,715229,715230,715231,715232
W1(+3-3)	<i>z</i>	718692,718693,718694,718695,718696,718697,718698,718699,718700
	<i>u*</i>	948333,948334,948335,948446,948447
	<i>g</i>	863085,863086,863087,863088,863089
	<i>r</i>	815145,815273,815274,1022104,1022105

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W1(+3-2)	<i>i</i>	874623,874624,874625,874626,874627,874628,874629
	<i>z</i>	948635,948636,948637,948638,955017,955018
	<i>u*</i>	942325,942326,942397,942398,942399,942400,942401
	<i>g</i>	827307,827308,827309,827310,827311
	<i>r</i>	809764,809765,1022102,1022103
	<i>i</i>	827300,827301,827302,827303,827304,827305,827306
W1(+3-1)	<i>z</i>	885067,885068,885069,885070,885071,885072
	<i>u*</i>	942045,942046,942047,942048,942049
	<i>g</i>	826741,826742,826743,826744,826745
	<i>r</i>	809632,809633,1021824,1021825
	<i>i</i>	826746,826747,826748,826749,826750,826751,826752,826753
	<i>z</i>	880424,880425,880430,880431,880432,880435
W1(+3-0)	<i>u*</i>	832185,832186,832187,832188,832189
	<i>g</i>	724440,724441,724442,724443,724444
	<i>r</i>	720440,720441,1021818,1021819
	<i>i</i>	720087,720088,720089,720090,720091,720092,720093
	<i>z</i>	832484,832485,832486,832487,832488,832489,832713,832714,832715,832716,832717,832719
	<i>u*</i>	831522,831523,831524,831525,831526
W1(+3+1)	<i>g</i>	719196,719197,719198,719199,719200,719202, 1118579,1118580,1118581,1118582,1118583
	<i>r</i>	719194,719195,1021671,1021672
	<i>y</i>	1030206,1030207,1030208,1038675,1038804
	<i>z</i>	831967,831968,831969,831970,831971,831972
	<i>u*</i>	820092,826810,826811,831517,831518,831519,831520,831521
	<i>g</i>	724435,724436,724437,724438,724439, 1119117,1119118,1119119,1119120,1119121
W1(+3+2)	<i>r</i>	719958,720444,720445,1021551,1021552
	<i>y</i>	1118742,1118743,1118744,1118745,1118746
	<i>z</i>	831862,831863,831864,831865,831866,831867
	<i>u*</i>	816625,816626,816903,816904,1031323
	<i>g</i>	719946,719947,719948,719949,719950
	<i>r</i>	719944,719945,1021505,1021506
W1(+3+3)	<i>i</i>	719951,719952,719953,719954,719955,719956
	<i>z</i>	831631,831632,831633,831634,831635,831636
	<i>u*</i>	1031188,1031189,1031190,1031191,1038674
	<i>g</i>	934914,934915,934916,934917,934918
	<i>r</i>	815289,816391,1021501,1021502
	<i>y</i>	962886,962887,962889,962890,962892,1030598,1030599,1030600,1030796,1030797,1030798,1030799
W1(+4-4)	<i>z</i>	1032881,1032882,1032883,1032884,1032885,1032886
	<i>u*</i>	942402,942403,942404,948448,948449
	<i>g</i>	862721,863278,863279,863280,863281,863282
	<i>r</i>	815279,815287,1022100,1022101
	<i>i</i>	862611,862612,862613,862614,862615,862616,862617
	<i>z</i>	942760,942761,942762,942763,942764,942765
W1(+4-3)	<i>u*</i>	942320,942321,942322,942323,942324
	<i>g</i>	826648,826649,826650,826651,826652
	<i>r</i>	810325,810326,1022098,1022099
	<i>i</i>	826960,826961,827067,827068,827069,827070,827071
	<i>z</i>	884609,884610,884611,884612,884613,884614
	<i>u*</i>	940656,940658,941955,941956,942044
W1(+4-2)	<i>g</i>	826954,826955,826956,826957,826958
	<i>r</i>	810323,810324,1021822,1021823
	<i>i</i>	826819,826820,826821,826822,826823,826824,826825
	<i>z</i>	879878,879879,879880,879881,879882,879883
	<i>u*</i>	832057,832058,832059,832060,832061
	<i>g</i>	724447,724448,724449,724450,724451
W1(+4-1)	<i>r</i>	720442,720443,1021820,1021821
	<i>i</i>	720102,720103,720104,720105,720106,720108,720109,720110
	<i>z</i>	832478,832479,832480,832481,832482,832483
	<i>u*</i>	831857,831858,831859,831860,831861
	<i>g</i>	724612,724613,724614,724615,724616, 1118892,1118893,1118894,1118895,1118896
	<i>r</i>	724371,724372,1021669,1021670
W1(+4-0)	<i>i</i>	723402,723403,723404,723405,723406,723407,723408
	<i>z</i>	832190,832191,832192,832193,832194,832195
	<i>u*</i>	831626,831627,831628,831629,831630
	<i>g</i>	724606,724608,724609,724610,724611, 1118408,1118865,1118866,1118867,1118868,1118869,1118891

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W1(+4+3)	<i>r</i>	724369,724370,1021667,1021668
	<i>y</i>	1030216,1030217,1030218,1038676,1038677
	<i>z</i>	832062,832063,832064,832065,832066,832067
	<i>u*</i>	831527,831528,831529,831530,831531
	<i>g</i>	715504,715505,715506,715507,715820
	<i>r</i>	715075,715076,1021503,1021504
	<i>i</i>	720022,720023,720024,720025,720026,720027
W2(-1-1)	<i>z</i>	831973,831974,831975,831976,831977,831978
	<i>u*</i>	906869,906870,906871,906872,906873
	<i>g</i>	881306,883362,883363,883364,883365,883366
	<i>r</i>	832209,832210,967608,967609
	<i>i</i>	832213,832214,832215,832216,832217,832218,832219
	<i>z</i>	900138,900139,900140,900141,900142,900143
	<i>u*</i>	906775,906776,906777,906867,906868
W2(-1-0)	<i>g</i>	831665,831666,831667,831668,831669
	<i>r</i>	831656,831657,967606,967607
	<i>i</i>	831658,831659,831660,831661,831662,831663,831664
	<i>z</i>	900132,900133,900134,900135,900136,900137
	<i>u*</i>	906177,906178,906179,906180,906181
	<i>g</i>	831313,831315,831316,831333,831334,831335,831336,831337
	<i>r</i>	831309,831310,831311,967604,967605
W2(-1+1)	<i>i</i>	831201,831202,831203,831204,831205,831206,831207
	<i>z</i>	900126,900127,900128,900129,900130,900131
	<i>u*</i>	898948,898949,898951,898952,898953
	<i>g</i>	831195,831196,831197,831198,831199,831200
	<i>r</i>	831193,831194,967602,967603
	<i>i</i>	830746,830747,830748,830749,830750,830751,830752
	<i>z</i>	900037,900038,900039,900040,900041,900042
W2(-1+2)	<i>u*</i>	898954,898955,898956,898957,898958
	<i>g</i>	731002,731003,731004,731005,731006
	<i>r</i>	730895,731000,731001,962772,962773
	<i>i</i>	775337,775339,775349,789017,789018,789019
	<i>z</i>	900031,900032,900033,900034,900035,900036
	<i>u*</i>	963593,963594,963596,963597,987072
	<i>g</i>	881290,881291,881292,881293,881294
W2(-0-1)	<i>r</i>	832102,832103,967600,967601
	<i>i</i>	832086,832087,832088,832089,832090,832091,832092
	<i>z</i>	960992,960993,960994,960995,960996,960997
	<i>u*</i>	905607,905608,905609,905610,905611,905612
	<i>g</i>	831561,831562,831563,831564,831565,831566
	<i>r</i>	831654,831655,967598,967599
	<i>i</i>	831549,831550,831551,831552,831553,831554,831555
W2(-0-0)	<i>z</i>	899551,899552,899553,899554,899555,899556,899557
	<i>u*</i>	896035,896036,896037,896038,896039
	<i>g</i>	826673,826674,826675,826676,826677
	<i>r</i>	826541,826542,967596,967597
	<i>i</i>	830739,830740,830741,830742,830743,830744,830745
	<i>z</i>	899368,899369,899370,899371,899372,899373
	<i>u*</i>	895798,895799,895800,895801,895802
W2(-0+1)	<i>g</i>	826839,826840,826841,826842,826843,826844
	<i>r</i>	826539,826540,967594,967595
	<i>i</i>	826665,826666,826667,826668,826669,826670,826671
	<i>z</i>	899140,899141,899142,899144,899145,899146
	<i>u*</i>	895793,895794,895795,895796,895797
	<i>g</i>	789020,789021,789022,789023,789024
	<i>r</i>	730652,730653,777838,777839,962770,962771
W2(-0+3)	<i>i</i>	784772,784773,784774,784775,784776,784777,784778
	<i>z</i>	896289,896290,896291,896292,896293,896294
	<i>u*</i>	963346,963347,963348,963349,963350
	<i>g</i>	880241,880242,880243,880244,880245
	<i>r</i>	832100,832101,967592,967593
	<i>i</i>	832093,832094,832095,832096,832097,832098
	<i>z</i>	960423,960424,960425,960428,960429,960431

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W2(+1-0)	<i>u</i> *	905696,905697,905698,905699,905700
	<i>g</i>	831556,831557,831558,831559,831560
	<i>r</i>	831547,831548,967590,967591
	<i>i</i>	831433,831434,831435,831436,831437,831438,831439
	<i>z</i>	899558,899559,899560,899561,899562,899563
W2(+1+1)	<i>u</i> *	896030,896031,896032,896033,896034
	<i>g</i>	789148,826660,826661,826662,826663,826664
	<i>r</i>	777631,777632,963359,963360,963372,963373
	<i>y</i>	986922,986923,986924,986925,986926,987068,987069
	<i>z</i>	889524,889525,889526,889527,889528,889529
W2(+1+2)	<i>u</i> *	890112,890113,890114,890115,890117,890120
	<i>g</i>	774795,774796,774797,774798,774799,774800
	<i>r</i>	777305,777306,963157,963161
	<i>i</i>	777301,777302,777303,777304,777309,777310,777311
	<i>z</i>	889336,889337,889338,889339,889340,889341
W2(+1+3)	<i>u</i> *	890107,890108,890109,890110,890111
	<i>g</i>	774288,774289,774293,774294,774295,774296
	<i>r</i>	777307,777308,962768,962769
	<i>i</i>	775154,775155,775158,775159,775161,775162
	<i>z</i>	889343,889344,889345,889346,889347,889348
W2(+2-1)	<i>u</i> *	963166,963167,963168,963169,963170
	<i>g</i>	880237,880238,880239,880476,880477
	<i>r</i>	831997,831998,967588,967589
	<i>i</i>	832006,832007,832008,832009,832010,832011,832012
	<i>z</i>	956125,956126,956127,956128,956129,956130
W2(+2-0)	<i>u</i> *	905819,905820,905821,905822,905823
	<i>g</i>	831347,831348,831349,831350,831351
	<i>r</i>	831345,831346,967586,967587
	<i>i</i>	831338,831339,831340,831341,831342,831343,831344
	<i>z</i>	899564,899565,899566,899568,899569,899570
W2(+2+1)	<i>u</i> *	896025,896026,896027,896028,896029
	<i>g</i>	774116,774117,774118,774119,774120,774121
	<i>r</i>	774129,774130,962801,962802
	<i>i</i>	774122,774123,774124,774125,774126,774127,774128
	<i>z</i>	889530,889531,889532,889533,889534,889535
W2(+2+2)	<i>u</i> *	890407,890408,890409,890410,890411
	<i>g</i>	774281,774282,774283,774284,774285,774286
	<i>r</i>	731035,731036,963159,963160
	<i>y</i>	1038712,1038713,1038714,1038840,1038841,1038842,1038843
	<i>z</i>	889350,889351,889352,889353,889354,889355
W2(+2+3)	<i>u</i> *	895788,895789,895790,895791,895792
	<i>g</i>	731007,731008,731009,731010,731011
	<i>r</i>	730922,962766,962767,987075
	<i>i</i>	777315,777316,777317,777318,777446,777447,777448
	<i>z</i>	895598,895599,895600,896295,896296,896297
W2(+3-1)	<i>u</i> *	963052,963053,963054,963055,963056
	<i>g</i>	880225,880226,880227,880228,880229
	<i>r</i>	831995,831996,967584,967585
	<i>i</i>	831999,832000,832001,832002,832003,832004,832005
	<i>z</i>	955447,955448,955449,955450,955451,955452
W2(+3-0)	<i>u</i> *	905935,905936,905937,905938,905939
	<i>g</i>	739202,739203,739204,739205,739650
	<i>r</i>	730941,730942,963591,963592
	<i>i</i>	784765,784766,784767,784768,784769,784770,784771
	<i>z</i>	899936,899937,899938,899939,899940,899941
W2(+3+1)	<i>u</i> *	890565,890566,890567,890568,890569
	<i>g</i>	733290,733291,733292,733293,733294
	<i>r</i>	730939,730940,963164,963165
	<i>i</i>	777312,777313,777314,777442,777443,777445
	<i>z</i>	889356,889357,889358,889359,889360,889361
W2(+3+2)	<i>u</i> *	890560,890561,890562,890563,890564
	<i>g</i>	732998,732999,733000,733001,733002
	<i>r</i>	730738,730739,963162,963163
	<i>i</i>	732380,732381,732382,732383,781182,781183,781184

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W2(+3+3)	<i>z</i>	781185,781186,781187,781188,781189,781190,781191,781192,781195,781196,781197,781198
	<i>u*</i>	895593,895594,895595,895596,895597
	<i>g</i>	732991,732992,732993,732994,732996
	<i>r</i>	732760,732762,962764,962765
	<i>i</i>	784758,784759,784760,784761,784762,784763,784764
W3(-3-3)	<i>z</i>	895572,895573,895574,895575,895576,895577
	<i>u*</i>	850250,850251,850252,850253,850254
	<i>g</i>	792941,792942,792943,792944,792945
	<i>r</i>	792446,792447,967513,967514
	<i>i</i>	793316,793317,793318,793319,793320,793321,793322
W3(-3-2)	<i>z</i>	850441,850442,850443,850444,850445,850446
	<i>u*</i>	850245,850246,850247,850248,850249
	<i>g</i>	793176,793177,793178,793179,793180
	<i>r</i>	792448,792449,967515,967516
	<i>i</i>	793323,793324,793325,793326,793327,793328,793329
W3(-3-1)	<i>z</i>	850255,850256,850257,850258,850259,850260,850261
	<i>u*</i>	905718,905719,905720,905721,905722
	<i>g</i>	708589,708590,708591,708592,708593
	<i>r</i>	708586,708587,967972,967973
	<i>i</i>	708704,708705,708706,708707,708708,708709
W3(-3-0)	<i>z</i>	850962,850963,850964,850965,850966,850967
	<i>u*</i>	905849,905850,905851,905852,905853
	<i>g</i>	793330,793331,793332,793333,793334
	<i>r</i>	792953,792954,967981,967982
	<i>i</i>	793456,793457,793458,793459,793460,793461,793462
W3(-3+1)	<i>z</i>	850956,850957,850958,850959,850960,850961
	<i>u*</i>	918225,918226,918227,918228,918229
	<i>g</i>	800976,800977,800978,800979,800980
	<i>r</i>	797257,797258,974334,974335
	<i>y</i>	986927,986928,986929,986930,986931,986932,986933
W3(-3+2)	<i>z</i>	905021,905022,905023,905024,905025,905026
	<i>u*</i>	918977,918978,918979,918980,918981
	<i>g</i>	800982,800983,800984,800985,800986
	<i>r</i>	797662,797663,974350,974675,974676
	<i>i</i>	797761,797762,797763,797764,797765,797766,797767
W3(-3+3)	<i>z</i>	905499,905500,905501,905502,905503,905504
	<i>u*</i>	975448,975449,975450,994906,994907
	<i>g</i>	849609,849610,849611,849612,849613
	<i>r</i>	844750,844751,975587,975588
	<i>i</i>	845231,845232,845233,845234,845235,845236,845237
W3(-2-3)	<i>z</i>	964907,964908,964909,964910,964911,964912
	<i>u*</i>	899071,899072,899075,994908,994909
	<i>g</i>	788717,788718,789050,789051,789052
	<i>r</i>	781209,781210,967613,967614
	<i>i</i>	792946,792947,792948,792949,792950,792951,792952
W3(-2-2)	<i>z</i>	850359,850360,850361,850362,850364,850365
	<i>u*</i>	850348,850349,850350,850351,850352
	<i>g</i>	788842,788843,788844,788845,788846
	<i>r</i>	780551,780553,967611,967612
	<i>i</i>	793051,793052,793053,793054,793055,793056,793057
W3(-2-1)	<i>z</i>	850353,850354,850355,850356,850357,850358
	<i>u*</i>	905723,905724,905725,905726,905727
	<i>g</i>	788847,788848,788849,788850,788851
	<i>r</i>	781217,781218,967970,967971
	<i>y</i>	987079,987080,987081,987082,987083,987084,987085
W3(-2-0)	<i>z</i>	851164,851165,851166,851167,851168,851170
	<i>u*</i>	905854,905855,905856,905857,905858
	<i>g</i>	792935,792936,792937,792938,792939
	<i>r</i>	781219,781220,967983,967984
	<i>i</i>	793065,793066,793068,793069,793070,793071
W3(-2+1)	<i>z</i>	851171,851172,851174,851175,851176,851177
	<i>u*</i>	918456,918457,918458,918459,918460
	<i>g</i>	796972,796973,796974,796975,796981

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W3(-2+2)	r	796979,796980,973413,974332,974333
	y	987093,987094,987095,987096,987097,987098,987099
	z	905027,905028,905029,905030,905031,905032
	u*	919084,919085,919086,919087,919088
	g	802356,802357,802358,802359,802360
	r	797670,797671,974677,974678
W3(-2+3)	i	845099,845100,845101,845102,845103,845104
	z	906682,906683,906684,906685,906686,906687
	u*	975577,975578,975579,975580,975581
	g	849614,849615,849616,849617,849618
	r	845365,845366,975457,975458,975589,975590
	y	987086,987087,987088,987089,987090,987091,987092
W3(-1-3)	z	965362,965363,965364,965365,965366,965367
	u*	850753,850754,850755,850756,850757
	g	788200,788201,788202,788203,788204
	r	777535,777536,967615,967616
	i	789162,789163,789164,789165,789166,789167,789168,789169,789170,789171
	z	850758,850759,850760,850761,850762,850763
W3(-1-2)	u*	850851,850852,850853,850854,850855
	g	788205,789173,789174,789176,789177
	r	781215,781216,967871,967966,967967
	i	792430,792431,792432,792433,792434,792435,792438
	z	850856,850857,850858,850859,850860,850861
	u*	905729,905730,905731,905732,905733
W3(-1-1)	g	792425,792426,792427,792428,792429
	r	781213,781214,967968,967969
	i	792439,792440,792441,792442,792443,792444,792445
	z	850862,850863,850864,850865,850866,850867
	u*	905859,905860,905861,905862,905863
	g	788853,788854,788857,789053,789054
W3(-1-0)	r	781211,781212,967985,967986
	i	792617,792618,792619,792620,792621,792622,792623
	z	853250,853251,853252,853253,853254,853255
	u*	918461,918462,918463,918464,918465
	g	796967,796968,796969,796970,796971
	r	796977,796978,973411,973412
W3(-1+1)	i	796982,796983,796984,796985,796986,796987
	z	905034,905035,905036,905038,905039,905040
	u*	919089,919090,919091,919092,919093
	g	802361,802362,802363,802364,802365
	r	802664,802665,974987,974988
	i	845105,845106,845107,845108,845109,845110,845111
W3(-1+2)	z	906780,906781,906782,906783,906784,906785
	u*	975905,975906,975907,975908,975909
	g	849619,849620,849621,849622,849623
	r	845367,845368,975595,975596
	y	986956,986957,986958,986959,986960,986961,986962
	z	964459,964460,964461,964462,964463,964464
W3(-0-3)	u*	918116,918117,918118,918119,918120
	g	707655,707656,707657,707658,707659
	r	707662,707663,973397,973781,974184,974185
	i	705484,705485,705486,705487,705488,705489,705490
	z	905014,905015,905016,905017,905018,905019
	u*	912457,912458,912459,912460,912461
W3(-0-2)	g	707554,707555,707556,707557,707558
	r	707559,707560,973350,973395,973396
	i	705403,705404,705405,705406,705407,705408,705409
	z	895845,895846,895847,895848,895849,895850
	u*	905987,905988,905989,905990,905991
	g	707434,707435,707436,707437,707438
W3(-0-1)	r	707432,707433,973348,973926,973927
	i	705391,705397,705398,705399,705400,705401
	z	895517,895520,895522,895525,895526,895527
	u*	905982,905983,905984,905985,905986

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W3(-0+1)	<i>g</i>	707276,707277,707278,707279,707280
	<i>r</i>	707274,707275,973346,973347
	<i>i</i>	705244,705245,705246,705247,705248,705249,705250
	<i>z</i>	853918,853919,853920,853921,853922,853923
	<i>u*</i>	918466,918467,918468,918589,918590
	<i>g</i>	796616,796617,796618,796619,796620
W3(-0+2)	<i>r</i>	796623,796624,973409,973410
	<i>i</i>	796626,796744,796745,796746,796747,796748,796749
	<i>z</i>	905224,905225,905226,905227,905228,905229
	<i>u*</i>	919602,919603,919604,919605,919606
	<i>g</i>	802366,802367,802368,802369,802370
	<i>r</i>	802671,802672,974989,974990
W3(-0+3)	<i>i</i>	844865,844866,844867,844868,844869,844870,844871
	<i>z</i>	906810,906811,906812,906813,906814,906815
	<i>u*</i>	979597,979598,979599,979600,979601
	<i>g</i>	849695,849696,849697,849698,849699
	<i>r</i>	845369,845370,975593,975594
	<i>i</i>	849624,849625,849626,849627,849628,849629,849630
W3(+1-3)	<i>z</i>	964178,964179,964180,964181,964182,964458
	<i>u*</i>	918982,918983,918984,918985,918986
	<i>g</i>	739209,739210,739211,739212,739216,739218
	<i>r</i>	739207,739208,973400,974186,974187
	<i>i</i>	742622,742880,742881,742882,742883,742884,742885
	<i>z</i>	906521,906654,906655,906656,906657,906658,906659
W3(+1-2)	<i>u*</i>	918842,918843,918844,918845,918846
	<i>g</i>	742886,742887,742888,742889,742890
	<i>r</i>	742236,742237,973401,973402
	<i>i</i>	743062,743063,743065,743066,743067,743068,743069
	<i>z</i>	906515,906516,906517,906518,906519,906520
	<i>u*</i>	918837,918838,918839,918840,918841
W3(+1-1)	<i>g</i>	745141,745142,745143,745144,745145
	<i>r</i>	745147,745148,973403,973404
	<i>i</i>	743070,743071,743072,743073,743074,743075,743076
	<i>z</i>	906355,906356,906357,906358,906508,906509,906510,906511,906513,906514
	<i>u*</i>	918596,918597,918598,918599,918600
	<i>g</i>	742892,742893,742894,742895,742896
W3(+1-0)	<i>r</i>	745149,745150,973405,973406
	<i>i</i>	743078,743079,743080,743081,743082,743083,743084
	<i>z</i>	906234,906235,906236,906349,906350,906351,906352,906353,906354
	<i>u*</i>	918591,918592,918593,918594,918595
	<i>g</i>	796611,796612,796613,796614,796615
	<i>r</i>	796621,796622,973407,973408
W3(+1+1)	<i>i</i>	796485,796486,796487,796488,796489,796490,796491
	<i>z</i>	905230,905231,905233,905234,905235,905236
	<i>u*</i>	919758,919759,919760,919761,919762,974999,975000,975001,975002,975003
	<i>g</i>	844738,844739,844740,844741,844742
	<i>r</i>	780364,780365,974991,974992
	<i>i</i>	797645,797646,797647,797648,797649,797650,797651
W3(+1+2)	<i>z</i>	907094,907095,907096,907097,907098,907099
	<i>u*</i>	975910,975911,975912,975913,975914
	<i>g</i>	849700,849701,849702,849703,849704
	<i>r</i>	845477,845478,975591,975592
	<i>i</i>	849705,849706,849772,849773,849774,849775,849776
	<i>z</i>	963929,963930,963931,964175,964176,964177
W3(+2-3)	<i>u*</i>	975221,975222,975223,975224,975225
	<i>g</i>	750105,750106,750107,750187,750188
	<i>r</i>	745594,745595,975013,975014
	<i>i</i>	743140,745587,745588,745589,745590,745591,745592,745593
	<i>z</i>	918131,918132,918133,918134,918135,918136,918137
	<i>u*</i>	975131,975132,975133,975134,975135
W3(+2-2)	<i>g</i>	750322,750323,750959,750960,750961,750962,750963
	<i>r</i>	750965,750967,975011,975012
	<i>i</i>	745599,745600,745601,745602,745604,745605,745606
	<i>z</i>	918125,918126,918127,918128,918129,918130

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W3(+2-1)	<i>u</i> *	975004,975005,975006,975007,975008
	<i>g</i>	753782,753783,753784,753785,753786
	<i>r</i>	753780,755116,975009,975010
	<i>i</i>	751034,751197,751198,751199,751200,751201,751202,751203
	<i>z</i>	918027,918028,918029,918030,918031,918032
W3(+2-0)	<i>u</i> *	973921,973922,973923,973924,973925
	<i>g</i>	755117,755118,755119,755120,755244
	<i>r</i>	753788,753789,974997,974998
	<i>i</i>	789056,789057,789058,789059,789060,789061,789062
	<i>z</i>	918021,918022,918023,918024,918025,918026
W3(+2+1)	<i>u</i> *	973916,973917,973918,973919,973920
	<i>g</i>	796351,796352,796608,796609,796610
	<i>r</i>	780366,780367,974995,974996
	<i>i</i>	793809,793810,793811,793812,793813,793814,793815
	<i>z</i>	912552,912553,917941,917942,917943,917944,917945,917946
W3(+2+2)	<i>u</i> *	973911,973912,973913,973914,973915
	<i>g</i>	802666,802667,802668,802669,802670
	<i>r</i>	802673,802674,974993,974994
	<i>i</i>	844743,844744,844745,844746,844747,844748,844749
	<i>z</i>	917935,917936,917937,917938,917939,917940
W3(+2+3)	<i>u</i> *	979602,979603,979604,979605,979606
	<i>g</i>	849767,849768,849769,849770,849771
	<i>r</i>	845479,845480,975235,975236
	<i>i</i>	849777,849778,849779,849780,849781,849782,849783
	<i>z</i>	963923,963924,963925,963926,963927,963928
W3(+3-3)	<i>u</i> *	975226,975227,975228,975229,975230
	<i>g</i>	859218,859219,859623,859624,859625
	<i>r</i>	852994,852995,975115,975116
	<i>i</i>	853622,853623,853624,853625,853626,853739
	<i>z</i>	930854,930855,930856,930857,930858,930859
W3(+3-2)	<i>u</i> *	975582,975583,975584,975585,975586
	<i>g</i>	860019,860020,860021,987108,987109
	<i>r</i>	852996,852997,975117,975118
	<i>i</i>	853849,853912,853913,853914,853915,853916
	<i>z</i>	930860,930861,930862,930863,930864,930865
W3(+3-1)	<i>u</i> *	980090,980091,980092,980093,980094
	<i>g</i>	890597,890600,890601,890603,890604
	<i>r</i>	852998,852999,975119,975120
	<i>y</i>	987229,987230,987231,987232,987233,987234,987235
	<i>z</i>	931000,931001,931002,931003,931004,931005
W3(+3-0)	<i>u</i> *	979853,979854,979855,979856,979857
	<i>g</i>	899066,899067,899068,899069,899070
	<i>r</i>	853000,853001,975122,975123
	<i>i</i>	899485,899486,899487,899488,899489,899490,899491
	<i>z</i>	931006,931007,931008,931009,931010,987110
W3(+3+1)	<i>u</i> *	975915,975916,975917,975918,975919
	<i>g</i>	899576,899577,899578,899579,899580
	<i>r</i>	853002,853003,975136,975137
	<i>i</i>	900058,900059,900060,900061,900062,900063,900064
	<i>z</i>	931115,931116,931117,931118,931119,931120
W3(+3+2)	<i>u</i> *	980095,980096,980097,980098,980099
	<i>g</i>	899971,899972,899973,899974,899975
	<i>r</i>	853004,853005,975231,975232
	<i>y</i>	987236,987237,987238,987239,987240,987241,987242,987243
	<i>z</i>	931121,931122,931123,931124,931125,931126
W3(+3+3)	<i>u</i> *	981430,981431,981432,981433,981434
	<i>g</i>	905494,905495,905496,905497,905498
	<i>r</i>	853006,853007,975233,975234
	<i>i</i>	900166,900167,900168,900169,900170,900171,900172
	<i>z</i>	964913,964914,964915,964916,964917,964918
W4(-3+0)	<i>u</i> *	934901,934902,934903,934904,934905
	<i>g</i>	930784,930785,930786,930787,930788
	<i>r</i>	919694,919695,988176,988177

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W4(-3+1)	<i>i</i>	918162,918163,918164,918165,918265,918266,918267
	<i>z</i>	918919,918920,918921,918922,918923,918924
	<i>u*</i>	934712,934730,934891,934892,934893,934894,934895
	<i>g</i>	930908,930909,930910,930911,930912
	<i>r</i>	930675,930676,987485,987486
	<i>i</i>	918268,918269,918270,918271,918272,918273,918391
W4(-3+2)	<i>z</i>	919025,919026,919027,919028,919029,919030
	<i>u*</i>	935165,935166,935167,935168,935169
	<i>g</i>	919445,919446,919447,919448,919449
	<i>r</i>	930768,930769,987279,987280
	<i>i</i>	918392,918393,918394,918395,918396,918397,918398
	<i>z</i>	919031,919032,919033,919034,919035,919036
W4(-3+3)	<i>u*</i>	935185,935186,935187,935188,935189
	<i>g</i>	935326,935438,935439,935440,935441,935442
	<i>r</i>	934411,934412,987128,987129
	<i>y</i>	995422,995423,995424,995425,995426,995427,995428
	<i>z</i>	931298,931299,931300,931301,931302,931303
	<i>u*</i>	934896,934897,934898,934899,934900
W4(-2+0)	<i>g</i>	850526,850527,850528,850529,850530
	<i>r</i>	850531,850532,996131,996133,996134
	<i>i</i>	853639,853640,853641,853642,853643,853647,853648,862673,862674,862675,862676,862677,862678
	<i>z</i>	874406,874407,874408,874409,874410,874411
	<i>u*</i>	934402,934403,934404,934405,934406
	<i>g</i>	919130,919131,919132,919133,919134
W4(-2+1)	<i>r</i>	919450,919451,996142,996143
	<i>i</i>	918155,918156,918157,918158,918159,918160,918161
	<i>z</i>	918912,918913,918915,918916,918917,918918
	<i>u*</i>	934906,934907,934908,934909,934910
	<i>g</i>	935299,935300,935301,935302,935303
	<i>r</i>	930770,930771,987643,987644
W4(-2+2)	<i>y</i>	995150,995151,995152,995153,995154,995281,995282
	<i>z</i>	919688,919689,919690,919691,919692,919693
	<i>u*</i>	935180,935181,935182,935183,935184
	<i>g</i>	935321,935322,935323,935324,935325
	<i>r</i>	934409,934410,987806,987807
	<i>y</i>	995672,995673,995674,995675,995676,995677,995678
W4(-2+3)	<i>z</i>	931148,931149,931150,931151,931152,931153
	<i>u*</i>	864142,864143,864144,864145,864146
	<i>g</i>	860225,860228,860229,860230,860231
	<i>r</i>	851200,851202,996280,996282,996284,996286
	<i>i</i>	862697,862698,862699,862700,862701,862702,862703
	<i>z</i>	864136,864137,864138,864139,864140,864141
W4(-1-2)	<i>u*</i>	870363,870364,870365,870366,870367
	<i>g</i>	860601,860602,860603,860604,860605,862806,862807,862808,862809,862918,862919
	<i>r</i>	850808,850809,996449,996450
	<i>y</i>	995679,995680,995681,995682,995885,995886,995887
	<i>z</i>	870155,870156,870157,870158,870159,870160
	<i>u*</i>	930774,930775,930776,930777,930778
W4(-1+0)	<i>g</i>	859940,859941,859942,859943,859944
	<i>r</i>	850996,850997,996146,996147
	<i>i</i>	859945,859946,859947,859949,859951,859952,859953
	<i>z</i>	859723,859724,859725,859726,859727,859728
	<i>u*</i>	934397,934398,934399,934400,934401
	<i>g</i>	853649,853650,853651,853652,853653,862692,862693,862694,862695,862696
W4(-1+1)	<i>r</i>	850286,850287,996144,996145
	<i>y</i>	996018,996019,996020,996021,996022,996023,996024
	<i>z</i>	875403,875404,875405,875406,875407,875408
	<i>u*</i>	935170,935171,935172,935173,935174
	<i>g</i>	935304,935305,935306,935307,935308
	<i>r</i>	930772,930773,987645,987646
W4(-1+2)	<i>y</i>	995283,995284,995285,995286,995287,995288,995289
	<i>z</i>	931043,931044,931050,931051,931052,931053
	<i>u*</i>	935175,935176,935177,935178,935179
	<i>g</i>	935316,935317,935318,935319,935320

Continued on next page

Table 33 – *Continued from previous page*

W Cartesian Ident Name	Filter	CFHT odometer number of input images combined in stacks
W4(+0-2)	<i>r</i>	934407,934408,987804,987805
	<i>y</i>	995290,995291,995292,995293,995419,995420,995421
	<i>z</i>	931054,931055,931056,931057,931058,931059
	<i>u*</i>	864147,864148,864149,864150,864151
	<i>g</i>	853285,853286,853287,853288,853289,862801,862802,862803,862804,862805
	<i>r</i>	851127,851128,996451,996452
W4(+0-1)	<i>i</i>	862597,862598,862599,862600,862601,862602,862603
	<i>z</i>	863984,863985,863986,863987,863988,863989
	<i>u*</i>	870368,870369,870371,870372,996025
	<i>g</i>	853290,853291,853292,853293,853294,862920,862921,862922,862923,862924
	<i>r</i>	850994,850995,996453,996454
	<i>i</i>	862794,862795,862796,862797,862798,862799,862800
W4(+0+0)	<i>z</i>	870357,870358,870359,870360,870361,870362
	<i>u*</i>	872170,872171,872173,872175,872176
	<i>g</i>	860077,860078,860079,860080,860081
	<i>r</i>	851189,851190,851191,996455,996456
	<i>i</i>	863246,863247,863248,863249,863250,863251,863252
	<i>z</i>	860606,860607,860608,860609,860610,860611,872158,872159,872160,872161,872162,872163
W4(+0+1)	<i>u*</i>	934392,934393,934394,934395,934396
	<i>g</i>	860188,860189,860190,860191,860192
	<i>r</i>	851192,851193,996457,996458
	<i>i</i>	863445,863446,863447,863448,863449,863450,863451
	<i>z</i>	879612,879613,879614,879615,879616,879617
	<i>u*</i>	863902,863903,863904,863905,863906
W4(+1-2)	<i>g</i>	850998,850999,851000,851001,851002
	<i>r</i>	850000,850001,996629,996630
	<i>i</i>	859675,859676,859677,859678,859679,859681
	<i>z</i>	863896,863897,863898,863899,863900,863901
	<i>u*</i>	870499,870500,870501,870502,870504
	<i>g</i>	851003,851004,851005,851006,851007
W4(+1-1)	<i>r</i>	850102,850103,996627,996628
	<i>i</i>	860594,860595,860596,860597,860598,860599,860600,863044,863045,863046,863047,863048,863049,863050
	<i>z</i>	870493,870494,870495,870496,870497,870498
	<i>u*</i>	872242,872243,872244,872245,872246
	<i>g</i>	851129,851130,851131,851132,851194
	<i>r</i>	850638,850639,996625,996626
W4(+1+0)	<i>i</i>	863051,863052,863053,863054,863055,863056,863057
	<i>z</i>	872057,872058,872059,872060,872061,872062
	<i>u*</i>	930779,930780,930781,930782,930783
	<i>g</i>	851195,851196,851197,851198,851199
	<i>r</i>	850636,850637,996623,996624
	<i>i</i>	863253,863254,863255,863256,863257,863258,863259
W4(+2-2)	<i>z</i>	879618,879619,879621,879622,879623,879624
	<i>u*</i>	858903,858905,858906,858907,859955
	<i>g</i>	850104,850105,850106,850107,850108
	<i>r</i>	849847,849848,996631,996632
	<i>i</i>	853569,853584,853585,853586,853587,853588,862590,862591,862592,862593,862594,862595,862596
	<i>z</i>	853577,853578,853579,853580,853581,853582,853583,863977,863978,863980,863981,863982,863983
W4(+2-1)	<i>u*</i>	858908,858909,858910,858911,858912
	<i>g</i>	850220,850221,850222,850223,850224
	<i>r</i>	849849,849850,996633,996634
	<i>i</i>	860082,860083,860084,860085,860086,860087,860088
	<i>z</i>	853787,853788,853789,853790,853791,853792,870699,870700,870701,870702,870706,870707
	<i>u*</i>	872069,872070,872071,872072,872073
W4(+2+0)	<i>g</i>	850281,850282,850283,850284,850285
	<i>r</i>	849998,849999,996635,996636
	<i>i</i>	860413,860414,860415,860416,860417,860418,860419
	<i>z</i>	871416,871417,871418,871419,871420,871421

A.3 CFHTLS T0007 Wide configuration files

A.3.1 SCAMP configuration files for T0007 Wide

A.3.2 SCAMP internal astrometric reference catalogue run (W1) :

```
# Default configuration file for SCAMP 1.5.5
# EB 2009-04-10
# Last modified for CFHTLS-T0007-W1 (Megacam):
# YG 2010-12-13

#----- Field grouping -----
FGROUP_RADIUS      1.0          # Max dist (deg) between field groups

#----- Reference catalogs -----
REF_SERVER          cocat1.u-strasbg.fr # Internet addresses of catalog servers
REF_PORT            1660         # Ports to connect to catalog servers
CDSCLIENT_EXEC     aclient       # CDSclient executable
ASTREF_CATALOG      2MASS        # NONE, FILE, USNO-A1, USNO-A2, USNO-B1,
                                # GSC-1.3, GSC-2.2, UCAC-1, UCAC-2,
                                # NOMAD-1, 2MASS, DENIS-3,
                                # SDSS-R3, SDSS-R5 or SDSS-R6
ASTREF_BAND         DEFAULT      # Photom. band for astr.ref.magnitudes
                                # or DEFAULT, BLUEST, or REDDEST
ASTREFCAT_NAME     astrefcat.cat # Local astrometric reference catalogs
ASTREFCENT_KEYS    X_WORLD,Y_WORLD # Local ref.cat.centroid parameters
ASTREFERR_KEYS     ERRA_WORLD,ERRB_WORLD,ERRTHETA_WORLD
                    # Local ref.cat.error ellipse parameters
ASTREFMAG_KEY       MAG          # Local ref.cat.magnitude parameter
SAVE_REFCATALOG    N            # Save ref catalogs in FITS-LDAC format?
REFOUT_CATPATH     .            # Save path for reference catalogs

#----- Merged output catalogs -----
MERGEDOUTCAT_NAME  CFHTLS-T0007-W1_SCamp_astr_ref.cat
                    # Merged output catalog filename
MERGEDOUTCAT_TYPE  FITS_LDAC   # NONE, ASCII_HEAD, ASCII, FITS_LDAC

#----- Pattern matching -----
MATCH               Y            # Do pattern-matching (Y/N) ?
MATCH_NMAX         0            # Max.number of detections for MATCHing
                                # (0=auto)
PIXSCALE_MAXERR   1.2          # Max scale-factor uncertainty
POSANGLE_MAXERR   5.0          # Max position-angle uncertainty (deg)
POSITION_MAXERR   1.0          # Max positional uncertainty (arcmin)
MATCH_RESOL        0            # Matching resolution (arcsec); 0=auto
MATCH_FLIPPED     N            # Allow matching with flipped axes?
MOSAIC_TYPE        SAME_CRVAL # UNCHANGED, SAME_CRVAL, SHARE_PROJAXIS,
                                # FIX_FOCALPLANE or LOOSE
FIXFOCALPLANE_NMIN 1            # Min number of dets for FIX_FOCALPLANE

#----- Cross-identification -----
CROSSID_RADIUS     2.0          # Cross-id initial radius (arcsec)

#----- Astrometric solution -----
SOLVE_ASTROM       Y            # Compute astrometric solution (Y/N) ?
ASTRINSTRU_KEY     FILTER,QRUNID # FITS keyword(s) defining the astrom
STABILITY_TYPE     INSTRUMENT   # EXPOSURE, GROUP, INSTRUMENT or FILE
CENTROID_KEYS      XWIN_IMAGE,YWIN_IMAGE
                    # Cat. parameters for centroiding
CENTROIDERR_KEYS   ERRAWN_IMAGE,ERRBWIN_IMAGE,ERRTHETAWN_IMAGE
                    # Cat. params for centroid err ellipse
```

```

DISTORT_KEYS          XWIN_IMAGE,YWIN_IMAGE # Cat. parameters or FITS keywords
DISTORT_GROUPS        1,1                  # Polynom group for each context key
DISTORT_DEGREES       3                   # Polynom degree for each group
ASTREF_WEIGHT         1.0                 # Relative weight of ref.astrom.cat.
ASTRCLIP_NSIGMA      3.0                 # Astrom. clipping threshold in sigmas
CORRECT_COLOURSHIFTS N                   # Correct for colour shifts (Y/N)?

#----- Photometric solution -----
SOLVE_PHOTOM          Y                   # Compute photometric solution (Y/N) ?
MAGZERO_OUT            30.0                # Magnitude zero-point(s) in output
MAGZERO_INTELL        0.01                # Internal mag.zero-point accuracy
MAGZERO_REFERRED      0.03                # Photom.field mag.zero-point accuracy
PHOTINSTRU_KEY         FILTER               # FITS keyword(s) defining the photom.
MAGZERO_KEY            PHOT_C               # FITS keyword for the mag zero-point
EXPOTIME_KEY           EXPTIME              # FITS keyword for the exposure time (s)
AIRMASS_KEY            AIRMASS              # FITS keyword for the airmass
EXTINCT_KEY            PHOT_K               # FITS keyword for the extinction coeff
PHOTOMFLAG_KEY         PHOTFLAG              # FITS keyword for the photometry flag
PHOTFLUX_KEY           FLUX_AUTO             # Catalog param. for the flux measurement
PHOTFLUXERR_KEY        FLUXERR_AUTO          # Catalog parameter for the flux error
PHOTCLIP_NSIGMA        3.0                 # Photom.clipping threshold in sigmas

#----- Check-plots -----
CHECKPLOT_CKEY         SCAMPCOL             # FITS keyword for PLPLOT field colour
CHECKPLOT_DEV           PNG                 # NULL, XWIN, TK, PS, PSC, XFIG, PNG,
                                         # JPEG, AQT, PDF or SVG
CHECKPLOT_RES           1600,1200            # Check-plot resolution (0 = default)
CHECKPLOT_ANTIALIAS     Y                   # Anti-aliasing using convert (Y/N) ?
CHECKPLOT_TYPE          DISTORTION,ASTR_INTELL,ASTR_REFERROR2D,
                        ASTR_REFERROR1D,ASTR_CHI2,PHOT_ERROR,PHOT_ERRORVSMAG,
                        PHOT_ZPCORR,PHOT_ZPCORR3D
CHECKPLOT_NAME          distort,astr_interror2d,astr_interror1d,astr_referror2d,
                        astr_referror1d,astr_chi2,psphot_error,phot_errorvsmag,
                        phot_zpcorr,phot_zpcorr3d
                                         # Check-plot filename(s)

#----- Check-images -----
CHECKIMAGE_TYPE          NONE                # NONE, AS_PAIR, AS_REFPAIR, or AS_XCORR
CHECKIMAGE_NAME          check.fits          # Check-image filename(s)

#----- Miscellaneous -----
SN_THRESHOLDS           10.0,100.0          # S/N thresholds (in sigmas) for all and
                                         # high-SN sample
FWHM_THRESHOLDS         0.0,100.0          # FWHM thresholds (in pixels) for sources
FLAGS_MASK              0x00f0              # Rejection mask on SEx FLAGS
WEIGHTFLAGS_MASK        0x00ff              # Rejection mask on SEx FLAGS_WEIGHT
IMAFLAGS_MASK           0x0                # Rejection mask on SEx IMAFLAGS_ISO
AHEADER_GLOBAL           /usr/share/scamp/megacam.ahead
                                         # Filename of the global INPUT header
AHEADER_SUFFIX           .ahead              # Filename extension for additional
                                         # INPUT headers
HEADER_SUFFIX            .head               # Filename extension for OUTPUT headers
HEADER_TYPE              NORMAL              # NORMAL or FOCAL_PLANE
VERBOSE_TYPE             LOG                 # QUIET, NORMAL, LOG or FULL
WRITE_XML                Y                  # Write XML file (Y/N)?
XML_NAME                CFHTLS-T0007-W1_SCamp_astr_ref.xml
                                         # Filename for XML output
XSL_URL                 scamp.xsl            # Filename for XSL style-sheet
NTHREADS                 0                  # Number of simultaneous threads for
                                         # the SMP version of SCAMP
                                         # 0 = automatic

```

SCAMP astrometric run using internal astrometric reference catalogue (W1) :

```

# Default configuration file for SCAMP 1.5.5
# EB 2009-04-10
# Last modified for CFHTLS-T0007-W1 (Megacam):
# YG 2010-12-14

#----- Field grouping -----

FGROUP_RADIUS      1.0          # Max dist (deg) between field groups

#----- Reference catalogs -----

REF_SERVER          cocat1.u-strasbg.fr # Internet addresses of catalog servers
REF_PORT             1660         # Ports to connect to catalog servers
CDSCCLIENT_EXEC     aclient       # CDSClient executable
ASTREF_CATALOG      FILE         # NONE, FILE, USNO-A1, USNO-A2, USNO-B1,
                                # GSC-1.3, GSC-2.2, UCAC-1, UCAC-2,
                                # NOMAD-1, 2MASS, DENIS-3,
                                # SDSS-R3, SDSS-R5 or SDSS-R6
ASTREF_BAND          DEFAULT      # Photom. band for astr.ref.magnitudes
                                # or DEFAULT, BLUEST, or REDDEST
ASTREFCAT_NAME       CFHTLS-T0007-W1_SCamp_astr_ref.cat
ASTREFCENT_KEYS     X_WORLD,Y_WORLD # Local ref.cat.centroid parameters
ASTREFERR_KEYS      ERRA_WORLD,ERRB_WORLD,ERRTHETA_WORLD
ASTREFMAG_KEY        MAG          # Local ref.cat.magnitude parameter
SAVE_REFCATALOG     N            # Save ref catalogs in FITS-LDAC format?
REFOUT_CATPATH      .            # Save path for reference catalogs

#----- Merged output catalogs -----

MERGEDOUTCAT_NAME   scamp.cat    # Merged output catalog filename
MERGEDOUTCAT_TYPE    NONE         # NONE, ASCII_HEAD, ASCII, FITS_LDAC

#----- Pattern matching -----

MATCH                Y            # Do pattern-matching (Y/N) ?
MATCH_NMAX           0            # Max.number of detections for MATCHing
                                # (0=auto)
PIXSCALE_MAXERR     1.2          # Max scale-factor uncertainty
POSANGLE_MAXERR     5.0          # Max position-angle uncertainty (deg)
POSITION_MAXERR      1.0          # Max positional uncertainty (arcmin)
MATCH_RESOL          0            # Matching resolution (arcsec); 0=auto
MATCH_FLIPPED        N            # Allow matching with flipped axes?
MOSAIC_TYPE          SAME_CRVAL # UNCHANGED, SAME_CRVAL, SHARE_PROJAXIS,
                                # FIX_FOCALPLANE or LOOSE
FIXFOCALPLANE_NMIN  1            # Min number of dets for FIX_FOCALPLANE

#----- Cross-identification -----

CROSSID_RADIUS       2.0          # Cross-id initial radius (arcsec)

#----- Astrometric solution -----

SOLVE_ASTROM         Y            # Compute astrometric solution (Y/N) ?
ASTRINSTRU_KEY       FILTER,QRUNID # FITS keyword(s) defining the astrom
INSTRUMENT           # EXPOSURE, GROUP, INSTRUMENT or FILE
CENTROID_KEYS        XWIN_IMAGE,YWIN_IMAGE
                                # Cat. parameters for centroiding
CENTROIDERR_KEYS     ERRAWN_IMAGE,ERRBWIN_IMAGE,ERRTHETAWIN_IMAGE
                                # Cat. params for centroid err ellipse
DISTORT_KEYS          XWIN_IMAGE,YWIN_IMAGE
                                # Cat. parameters or FITS keywords
DISTORT_GROUPS        1,1          # Polynom group for each context key
DISTORT_DEGREES       3            # Polynom degree for each group
ASTREF_WEIGHT         1.0          # Relative weight of ref.astrom.cat.

```

```

ASTRCLIP_NSIGMA      3.0          # Astrom. clipping threshold in sigmas
CORRECT_COLOURSHIFTS N           # Correct for colour shifts (Y/N)?

#----- Photometric solution -----
SOLVE_PHOTOM        Y           # Compute photometric solution (Y/N) ?
MAGZERO_OUT          30.0         # Magnitude zero-point(s) in output
MAGZERO_INERR        0.01         # Internal mag.zero-point accuracy
MAGZERO_REFERR       0.03         # Photom.field mag.zero-point accuracy
PHOTINSTRU_KEY       FILTER        # FITS keyword(s) defining the photom.
MAGZERO_KEY          PHOT_C        # FITS keyword for the mag zero-point
EXPOTIME_KEY         EXPTIME       # FITS keyword for the exposure time (s)
AIRMASS_KEY          AIRMASS       # FITS keyword for the airmass
EXTINCT_KEY          PHOT_K        # FITS keyword for the extinction coeff
PHOTOMFLAG_KEY       PHOTFLAG      # FITS keyword for the photometry flag
PHOTFLUX_KEY         FLUX_AUTO    # Catalog param. for the flux measurement
PHOTFLUXERR_KEY      FLUXERR_AUTO # Catalog parameter for the flux error
PHOTCLIP_NSIGMA      3.0          # Photom.clipping threshold in sigmas

#----- Check-plots -----
CHECKPLOT_CKEY       SCAMPCOL     # FITS keyword for PLPLOT field colour
CHECKPLOT_DEV         PNG          # NULL, XWIN, TK, PS, PSC, XFIG, PNG,
                                # JPEG, AQT, PDF or SVG
CHECKPLOT_RES         1600,1200   # Check-plot resolution (0 = default)
CHECKPLOT_ANTIALIAS  Y           # Anti-aliasing using convert (Y/N) ?
CHECKPLOT_TYPE        DISTORTION,ASTR_INTERRORED2D,ASTR_INTERRORED1D,ASTR_REFERROR2D,
                      ASTR_REFERROR1D,ASTR_CHI2,PHOT_ERROR,PHOT_ERRORVSMAG,
                      PHOT_ZPCORR,PHOT_ZPCORR3D
CHECKPLOT_NAME        distort,astr_interror2d,astr_interror1d,astr_referror2d,
                      astr_referror1d,astr_chi2,psphot_error,phot_errorvsmag,
                      phot_zpcorr,phot_zpcorr3d
                                # Check-plot filename(s)

#----- Check-images -----
CHECKIMAGE_TYPE        NONE         # NONE, AS_PAIR, AS_REFPAIR, or AS_XCORR
CHECKIMAGE_NAME        check.fits   # Check-image filename(s)

#----- Miscellaneous -----
SN_THRESHOLDS         10.0,100.0 # S/N thresholds (in sigmas) for all and
                                # high-SN sample
FWHM_THRESHOLDS       0.0,100.0 # FWHM thresholds (in pixels) for sources
FLAGS_MASK             0x00f0      # Rejection mask on SEx FLAGS
WEIGHTFLAGS_MASK      0x00ff      # Rejection mask on SEx FLAGS_WEIGHT
IMAFLAGS_MASK         0x0          # Rejection mask on SEx IMAFLAGS_ISO
AHEADER_GLOBAL         /usr/share/scamp/megacam.ahead
                                # Filename of the global INPUT header
AHEADER_SUFFIX         .ahead       # Filename extension for additional
                                # INPUT headers
HEADER_SUFFIX          .head        # Filename extension for OUTPUT headers
HEADER_TYPE            NORMAL       # NORMAL or FOCAL_PLANE
VERBOSE_TYPE           LOG          # QUIET, NORMAL, LOG or FULL
WRITE_XML              Y           # Write XML file (Y/N)?
XML_NAME               CFHTLS-T0007-W1_SCamp_astr_rz.xml
                                # Filename for XML output
XSL_URL                scamp.xsl    # Filename for XSL style-sheet
NTHREADS               0           # Number of simultaneous threads for
                                # the SMP version of SCAMP
                                # 0 = automatic

```

SCAMP astrometric run using external astrometric reference catalogue (W2,W3,W4) :

```

# Default configuration file for SCAMP 1.5.5
# EB 2009-04-10
# Last modified for CFHTLS-T0007-W2 (Megacam):
# YG 2010-10-22

#----- Field grouping -----

FGROUP_RADIUS      1.0          # Max dist (deg) between field groups

#----- Reference catalogs -----

REF_SERVER          cocat1.u-strasbg.fr # Internet addresses of catalog servers
REF_PORT            1660         # Ports to connect to catalog servers
CDSCCLIENT_EXEC     aclient       # CDSClient executable
ASTREF_CATALOG      2MASS        # NONE, FILE, USNO-A1, USNO-A2, USNO-B1,
                                # GSC-1.3, GSC-2.2, UCAC-1, UCAC-2,
                                # NOMAD-1, 2MASS, DENIS-3,
                                # SDSS-R3, SDSS-R5 or SDSS-R6
ASTREF_BAND         DEFAULT      # Photom. band for astr.ref.magnitudes
                                # or DEFAULT, BLUEST, or REDDEST
ASTREFCAT_NAME      astrefcat.cat # Local astrometric reference catalogs
ASTREFCENT_KEYS     X_WORLD,Y_WORLD # Local ref.cat.centroid parameters
ASTREFERR_KEYS      ERRA_WORLD,ERRB_WORLD,ERRTHETA_WORLD
                    # Local ref.cat.error ellipse parameters
ASTREFMAG_KEY       MAG          # Local ref.cat.magnitude parameter
SAVE_REFCATALOG    N             # Save ref catalogs in FITS-LDAC format?
REFOUT_CATPATH     .             # Save path for reference catalogs

#----- Merged output catalogs -----

MERGEDOUTCAT_NAME scamp.cat      # Merged output catalog filename
MERGEDOUTCAT_TYPE  NONE          # NONE, ASCII_HEAD, ASCII, FITS_LDAC

#----- Pattern matching -----

MATCH               Y             # Do pattern-matching (Y/N) ?
MATCH_NMAX          0             # Max.number of detections for MATCHing
                                # (0=auto)
PIXSCALE_MAXERR    1.2           # Max scale-factor uncertainty
POSANGLE_MAXERR    5.0           # Max position-angle uncertainty (deg)
POSITION_MAXERR    1.0           # Max positional uncertainty (arcmin)
MATCH_RESOL         0             # Matching resolution (arcsec); 0=auto
MATCH_FLIPPED       N             # Allow matching with flipped axes?
MOSAIC_TYPE         SAME_CRVAL   # UNCHANGED, SAME_CRVAL, SHARE_PROJAXIS,
                                # FIX_FOCALPLANE or LOOSE
FIXFOCALPLANE_NMIN 1             # Min number of dets for FIX_FOCALPLANE

#----- Cross-identification -----

CROSSID_RADIUS     2.0           # Cross-id initial radius (arcsec)

#----- Astrometric solution -----

SOLVE_ASTROM        Y             # Compute astrometric solution (Y/N) ?
ASTRINSTRU_KEY      FILTER,QRUNID # FITS keyword(s) defining the astrom
STABILITY_TYPE      INSTRUMENT   # EXPOSURE, GROUP, INSTRUMENT or FILE
CENTROID_KEYS        XWIN_IMAGE,YWIN_IMAGE
                    # Cat. parameters for centroiding
CENTROIDERR_KEYS    ERRAWN_IMAGE,ERRBWIN_IMAGE,ERRTHETAWN_IMAGE
                    # Cat. params for centroid err ellipse
DISTORT_KEYS         XWIN_IMAGE,YWIN_IMAGE
                    # Cat. parameters or FITS keywords
DISTORT_GROUPS      1,1           # Polynom group for each context key
DISTORT_DEGREES     3              # Polynom degree for each group
ASTREF_WEIGHT        1.0           # Relative weight of ref.astrom.cat.
ASTRCLIP_NSIGMA     3.0           # Astrom. clipping threshold in sigmas

```

```

CORRECT_COLOURSHIFTS N # Correct for colour shifts (Y/N) ?

#----- Photometric solution -----

SOLVE_PHOTOM Y # Compute photometric solution (Y/N) ?
MAGZERO_OUT 30.0 # Magnitude zero-point(s) in output
MAGZERO_INERR 0.01 # Internal mag.zero-point accuracy
MAGZERO_REFERR 0.03 # Photom.field mag.zero-point accuracy
PHOTINSTRU_KEY FILTER # FITS keyword(s) defining the photom.
MAGZERO_KEY PHOT_C # FITS keyword for the mag zero-point
EXPOTIME_KEY EXPTIME # FITS keyword for the exposure time (s)
AIRMASS_KEY AIRMASS # FITS keyword for the airmass
EXTINCT_KEY PHOT_K # FITS keyword for the extinction coeff
PHOTOMFLAG_KEY PHOTFLAG # FITS keyword for the photometry flag
PHOTFLUX_KEY FLUX_AUTO # Catalog param. for the flux measurement
PHOTFLUXERR_KEY FLUXERR_AUTO # Catalog parameter for the flux error
PHOTCLIP_NSIGMA 3.0 # Photom.clipping threshold in sigmas

#----- Check-plots -----

CHECKPLOT_CKEY SCAMPCOL # FITS keyword for PLPLOT field colour
CHECKPLOT_DEV PSC,PNG # NULL, XWIN, TK, PS, PSC, XFIG, PNG,
# JPEG, AQT, PDF or SVG
CHECKPLOT_RES 1600,1200 # Check-plot resolution (0 = default)
CHECKPLOT_ANTIALIAS Y # Anti-aliasing using convert (Y/N) ?
CHECKPLOT_TYPE DISTORTION,ASTR_INTERRORED2D,ASTR_INTERRORED1D,ASTR_REFERROR2D,
ASTR_REFERROR1D,ASTR_CHI2,PHOT_ERROR,PHOT_ERRORVSMAG,
PHOT_ZPCORR,PHOT_ZPCORR3D
CHECKPLOT_NAME distort,astr_interrror2d,astr_interrror1d,astr_referror2d,
astr_referror1d,astr_chi2,psphot_error,phot_errorvsmag,
phot_zpcorr,phot_zpcorr3d
# Check-plot filename(s)

#----- Check-images -----

CHECKIMAGE_TYPE NONE # NONE, AS_PAIR, AS_REFPAIR, or AS_XCORR
CHECKIMAGE_NAME check.fits # Check-image filename(s)

#----- Miscellaneous -----

SN_THRESHOLDS 10.0,100.0 # S/N thresholds (in sigmas) for all and
# high-SN sample
FWHM_THRESHOLDS 0.0,100.0 # FWHM thresholds (in pixels) for sources
FLAGS_MASK 0x00f0 # Rejection mask on SEx FLAGS
WEIGHTFLAGS_MASK 0x00ff # Rejection mask on SEx FLAGS_WEIGHT
IMAFLAGS_MASK 0x0 # Rejection mask on SEx IMAFLAGS_ISO
AHEADER_GLOBAL /usr/share/scamp/megacam.ahead
# Filename of the global INPUT header
AHEADER_SUFFIX .ahead # Filename extension for additional
# INPUT headers
HEADER_SUFFIX .head # Filename extension for OUTPUT headers
HEADER_TYPE NORMAL # NORMAL or FOCAL_PLANE
VERBOSE_TYPE LOG # QUIET, NORMAL, LOG or FULL
WRITE_XML Y # Write XML file (Y/N)?
XML_NAME CFHTLS-T0007-W2_SCamp_astr.xml
# Filename for XML output
XSL_URL scamp.xsl # Filename for XSL style-sheet
NTHREADS 0 # Number of simultaneous threads for
# the SMP version of SCAMP
# 0 = automatic

```

SCAMP photometric run (W1,W2,W3,W4) :

```

# Default configuration file for SCAMP 1.5.5
# EB 2009-04-10
# Last modified for CFHTLS-T0007-W4 (Megacam):
# YG 2010-10-27

#----- Field grouping -----

FGROUP_RADIUS      1.0          # Max dist (deg) between field groups

#----- Reference catalogs -----

REF_SERVER          cocat1.u-strasbg.fr # Internet addresses of catalog servers
REF_PORT            1660         # Ports to connect to catalog servers
CDSCCLIENT_EXEC    aclient       # CDSClient executable
ASTREF_CATALOG     2MASS        # NONE, FILE, USNO-A1, USNO-A2, USNO-B1,
                           # GSC-1.3, GSC-2.2, UCAC-1, UCAC-2,
                           # NOMAD-1, 2MASS, DENIS-3,
                           # SDSS-R3, SDSS-R5 or SDSS-R6
ASTREF_BAND         DEFAULT      # Photom. band for astr.ref.magnitudes
                           # or DEFAULT, BLUEST, or REDDEST
ASTREFCAT_NAME      astrefcat.cat # Local astrometric reference catalogs
ASTREFCENT_KEYS    X_WORLD,Y_WORLD # Local ref.cat.centroid parameters
ASTREFERR_KEYS     ERRA_WORLD,ERRB_WORLD,ERRTHETA_WORLD
                   # Local ref.cat.error ellipse parameters
ASTREFMAG_KEY       MAG          # Local ref.cat.magnitude parameter
SAVE_REFCATALOG   N             # Save ref catalogs in FITS-LDAC format?
REFOUT_CATPATH    .             # Save path for reference catalogs

#----- Merged output catalogs -----

MERGEDOUTCAT_NAME scamp.cat    # Merged output catalog filename
MERGEDOUTCAT_TYPE  NONE         # NONE, ASCII_HEAD, ASCII, FITS_LDAC

#----- Pattern matching -----

MATCH               N             # Do pattern-matching (Y/N) ?
MATCH_NMAX          0             # Max.number of detections for MATCHing
                           # (0=auto)
PIXSCALE_MAXERR    1.2          # Max scale-factor uncertainty
POSANGLE_MAXERR    5.0          # Max position-angle uncertainty (deg)
POSITION_MAXERR    1.0          # Max positional uncertainty (arcmin)
MATCH_RESOL         0             # Matching resolution (arcsec); 0=auto
MATCH_FLIPPED       N             # Allow matching with flipped axes?
MOSAIC_TYPE         UNCHANGED    # UNCHANGED, SAME_CRVAL, SHARE_PROJAXIS,
                           # FIX_FOCALPLANE or LOOSE
FIXFOCALPLANE_NMIN 1             # Min number of dets for FIX_FOCALPLANE

#----- Cross-identification -----

CROSSID_RADIUS     2.0          # Cross-id initial radius (arcsec)

#----- Astrometric solution -----

SOLVE_ASTROM        N             # Compute astrometric solution (Y/N) ?
ASTRINSTRU_KEY      FILTER,QRUNID # FITS keyword(s) defining the astrom
INSTRUMENT          INSTRUMENT   # EXPOSURE, GROUP, INSTRUMENT or FILE
CENTROID_KEYS       XWIN_IMAGE,YWIN_IMAGE
                   # Cat. parameters for centroiding
CENTROIDERR_KEYS   ERRAWN_IMAGE,ERRBWIN_IMAGE,ERRTHETAWIN_IMAGE
                   # Cat. params for centroid err ellipse
DISTORT_KEYS        XWIN_IMAGE,YWIN_IMAGE
                   # Cat. parameters or FITS keywords
DISTORT_GROUPS      1,1          # Polynom group for each context key
DISTORT_DEGREES     3             # Polynom degree for each group
ASTREF_WEIGHT       1.0          # Relative weight of ref.astrom.cat.
ASTRCLIP_NSIGMA    3.0          # Astrom. clipping threshold in sigmas

```

```

CORRECT_COLOURSHIFTS N # Correct for colour shifts (Y/N) ?

#----- Photometric solution -----
SOLVE_PHOTOM Y # Compute photometric solution (Y/N) ?
MAGZERO_OUT 30.0 # Magnitude zero-point(s) in output
MAGZERO_INERR 0.01 # Internal mag.zero-point accuracy
MAGZERO_REFERR 0.03 # Photom.field mag.zero-point accuracy
PHOTINSTRU_KEY FILTER # FITS keyword(s) defining the photom.
MAGZERO_KEY PHOT_C # FITS keyword for the mag zero-point
EXPOTIME_KEY EXPTIME # FITS keyword for the exposure time (s)
AIRMASS_KEY AIRMASS # FITS keyword for the airmass
EXTINCT_KEY PHOT_K # FITS keyword for the extinction coeff
PHOTOMFLAG_KEY PHOTFLAG # FITS keyword for the photometry flag
PHOTFLUX_KEY FLUX_AUTO # Catalog param. for the flux measurement
PHOTFLUXERR_KEY FLUXERR_AUTO # Catalog parameter for the flux error
PHOTCLIP_NSIGMA 3.0 # Photom.clipping threshold in sigmas

#----- Check-plots -----
CHECKPLOT_CKEY SCAMPCOL # FITS keyword for PLPLOT field colour
CHECKPLOT_DEV PNG # NULL, XWIN, TK, PS, PSC, XFIG, PNG,
# JPEG, AQT, PDF or SVG
CHECKPLOT_RES 1600,1200 # Check-plot resolution (0 = default)
CHECKPLOT_ANTIALIAS Y # Anti-aliasing using convert (Y/N) ?
CHECKPLOT_TYPE DISTORTION,ASTR_INTERRORED2D,ASTR_INTERRORED1D,ASTR_REFERROR2D,
ASTR_REFERROR1D,ASTR_CHI2,PHOT_ERROR,PHOT_ERRORVSMAG,
PHOT_ZPCORR,PHOT_ZPCORR3D
CHECKPLOT_NAME distort,astr_interror2d,astr_interror1d,astr_referror2d,
astr_referror1d,astr_chi2,psphot_error,phot_errorvsmag,
phot_zpcorr,phot_zpcorr3d
# Check-plot filename(s)

#----- Check-images -----
CHECKIMAGE_TYPE NONE # NONE, AS_PAIR, AS_REFPAIR, or AS_XCORR
CHECKIMAGE_NAME check.fits # Check-image filename(s)

#----- Miscellaneous -----
SN_THRESHOLDS 10.0,100.0 # S/N thresholds (in sigmas) for all and
# high-SN sample
FWHM_THRESHOLDS 0.0,100.0 # FWHM thresholds (in pixels) for sources
FLAGS_MASK 0x00f0 # Rejection mask on SEx FLAGS
WEIGHTFLAGS_MASK 0x00ff # Rejection mask on SEx FLAGS_WEIGHT
IMAFLAGS_MASK 0x0 # Rejection mask on SEx IMAFLAGS_ISO
AHEADER_GLOBAL /usr/share/scamp/megacam.ahead
# Filename of the global INPUT header
AHEADER_SUFFIX .ahead # Filename extension for additional
# INPUT headers
HEADER_SUFFIX .head # Filename extension for OUTPUT headers
HEADER_TYPE NORMAL # NORMAL or FOCAL_PLANE
VERBOSE_TYPE LOG # QUIET, NORMAL, LOG or FULL
WRITE_XML Y # Write XML file (Y/N)?
XML_NAME CFHTLS-T0007-W4_SCamp_phot.xml
# Filename for XML output
XSL_URL scamp.xsl # Filename for XSL style-sheet
NTHREADS 0 # Number of simultaneous threads for
# the SMP version of SCAMP
# 0 = automatic

```

A.3.3 SWarp stack configuration file for T0007 Wide

```

# Default configuration file for SWarp 2.17.6
# EB 2009-04-09
#
# Last modified for CFHTLS-T0007 (Megacam):
# YG 2010-11-02

#----- Output -----
IMAGEOUT_NAME      CFHTLS_W_z_022929-075600_T0007.fits
                   # Output filename
WEIGHTOUT_NAME     CFHTLS_W_z_022929-075600_T0007_weight.fits
                   # Output weight-map filename

HEADER_ONLY        N          # Only a header as an output file (Y/N)?
HEADER_SUFFIX      .head      # Filename extension for additional headers

#----- Input Weights -----
WEIGHT_TYPE        MAP_WEIGHT    # BACKGROUND,MAP_RMS,MAP_VARIANCE
                   # or MAP_WEIGHT
WEIGHT_SUFFIX      _weight.fits # Suffix to use for weight-maps
WEIGHT_IMAGE       _weight.fits # Weightmap filename if suffix not used
WEIGHT_THRESH      # (all or for each weight-map)
                   # Bad pixel weight-threshold

#----- Co-addition -----
COMBINE            Y          # Combine resampled images (Y/N)?
COMBINE_TYPE       MEDIAN     # MEDIAN,AVERAGE,MIN,MAX,WEIGHTED,CHI2
                   # or SUM
BLANK_BADPIXELS   N          # Set to 0 pixels having a weight of 0

#----- Astrometry -----
CELESTIAL_TYPE     NATIVE     # NATIVE, PIXEL, EQUATORIAL,
                   # GALACTIC,ECLIPTIC, or SUPERGALACTIC
PROJECTION_TYPE    TAN        # Any WCS projection code or NONE
PROJECTION_ERR     0.001      # Maximum projection error (in output
                   # pixels), or 0 for no approximation
CENTER_TYPE        MANUAL     # MANUAL, ALL or MOST
CENTER             02:29:29.14,-07:56:00 # Coordinates of the image center
PIXELSCALE_TYPE    MANUAL     # MANUAL,FIT,MIN,MAX or MEDIAN
PIXEL_SCALE        0.186      # Pixel scale
IMAGE_SIZE         19354,19354 # Image size (0 = AUTOMATIC)

#----- Resampling -----
RESAMPLE           Y          # Resample input images (Y/N)?
RESAMPLE_DIR       .
RESAMPLE_SUFFIX    .resamp.fits # filename extension for resampled images
RESAMPLING_TYPE   LANCZOS3  # NEAREST,BILINEAR,LANCZOS2,LANCZOS3
                   # or LANCZOS4 (1 per axis)
OVERSAMPLING       0          # Oversampling in each dimension
                   # (0 = automatic)
INTERPOLATE        Y          # Interpolate bad input pixels (Y/N)?
                   # (all or for each image)
FSCALASTRO_TYPE   VARIABLE   # NONE,FIXED, or VARIABLE
FSCALE_KEYWORD     FLXSCALE   # FITS keyword for the multiplicative
                   # factor applied to each input image
FSCALE_DEFAULT     1.0        # Default FSCALE value if not in header
GAIN_KEYWORD       GAIN       # FITS keyword for effect. gain (e-/ADU)
GAIN_DEFAULT       0.0        # Default gain if no FITS keyword found
                   # 0 = infinity (all or for each image)
SATLEV_KEYWORD     SATURATE  # FITS keyword for saturation level (ADU)
SATLEV_DEFAULT     50000.0   # Default saturation if no FITS keyword

```

```

#----- Background subtraction -----
SUBTRACT_BACK      Y          # Subtraction sky background (Y/N)?
                           # (all or for each image)
BACK_TYPE          AUTO       # AUTO or MANUAL
                           # (all or for each image)
BACK_DEFAULT        0.0       # Default background value in MANUAL
                           # (all or for each image)
BACK_SIZE           32        # Background mesh size (pixels)
                           # (all or for each image)
BACK_FILTERSIZE    7         # Background map filter range (meshes)
                           # (all or for each image)
BACK_FILTTHRESH   0.0       # Threshold above which the background-
                           # map filter operates

#----- Memory management -----
VMEM_DIR           .          # Directory path for swap files
VMEM_MAX            2047      # Maximum amount of virtual memory (MB)
MEM_MAX              128       # Maximum amount of usable RAM (MB)
COMBINE_BUFSIZE    400       # RAM dedicated to co-addition(MB)

#----- Miscellaneous -----
DELETE_TMPFILES    Y          # Delete temporary resampled FITS files
                           # (Y/N)?

COPY_KEYWORDS       FILTER,INSTRUME,TELESCOP,DETECTOR,OBSERVER,PHOT_C,PHOT_K,
                   OBJECT,DATE_OBS,ORIGIN,SEEING,REL_DATE
                           # List of FITS keywords to propagate
                           # from the input to the output headers
WRITE_FILEINFO      N          # Write information about each input
                           # file in the output image header?
WRITE_XML            Y          # Write XML file (Y/N)?
XML_NAME            CFHTLS_W_z_022929-075600_T0007_SWarp.xml
                           # Filename for XML output
XSL_URL              swarp.xsl # Filename for XSL style-sheet
VERBOSE_TYPE         NORMAL     # QUIET,NORMAL or FULL
NNODES                1         # Number of nodes (for clusters)
NODE_INDEX            0         # Node index (for clusters)

NTHREADS             0         # Number of simultaneous threads for
                           # the SMP version of SWarp
                           # 0 = automatic

```

A.3.4 SWarp chi2-image configuration file for T0007 Wide

```

# Default configuration file for SWarp 2.17.6
# EB 2009-04-09
#
# Last modified for CFHTLS-T0007 chi2 (Megacam):
# YG 2010-12-14

#----- Output -----
IMAGEOUT_NAME      CFHTLS_W_gri_022929-075600_T0007.fits
                   # Output filename
WEIGHTOUT_NAME     CFHTLS_W_gri_022929-075600_T0007_weight.fits
                   # Output weight-map filename

HEADER_ONLY        N          # Only a header as an output file (Y/N)?
HEADER_SUFFIX      .head      # Filename extension for additional headers

#----- Input Weights -----
WEIGHT_TYPE        MAP_WEIGHT    # BACKGROUND,MAP_RMS,MAP_VARIANCE
                   # or MAP_WEIGHT
WEIGHT_SUFFIX      _weight.fits # Suffix to use for weight-maps
WEIGHT_IMAGE       _weight.fits # Weightmap filename if suffix not used
                   # (all or for each weight-map)
WEIGHT_THRESH      # Bad pixel weight-threshold

#----- Co-addition -----
COMBINE            Y          # Combine resampled images (Y/N)?
COMBINE_TYPE       CHI2        # MEDIAN,AVERAGE,MIN,MAX,WEIGHTED,CHI2
                   # or SUM
BLANK_BADPIXELS   N          # Set to 0 pixels having a weight of 0

#----- Astrometry -----
CELESTIAL_TYPE     NATIVE     # NATIVE, PIXEL, EQUATORIAL,
                   # GALACTIC,ECLIPPTIC, or SUPERGALACTIC
PROJECTION_TYPE    TAN        # Any WCS projection code or NONE
PROJECTION_ERR     0.001      # Maximum projection error (in output
                   # pixels), or 0 for no approximation
CENTER_TYPE        MANUAL     # MANUAL, ALL or MOST
CENTER             02:29:29.14,-07:56:00 # Coordinates of the image center
PIXELSCALE_TYPE    MANUAL     # MANUAL,FIT,MIN,MAX or MEDIAN
PIXEL_SCALE        0.186      # Pixel scale
IMAGE_SIZE         19354,19354 # Image size (0 = AUTOMATIC)

#----- Resampling -----
RESAMPLE           Y          # Resample input images (Y/N)?
RESAMPLE_DIR       .
RESAMPLE_SUFFIX    .resamp.fits # filename extension for resampled images
RESAMPLING_TYPE   LANCZOS3   # NEAREST,BILINEAR,LANCZOS2,LANCZOS3
                   # or LANCZOS4 (1 per axis)
OVERSAMPLING       0          # Oversampling in each dimension
                   # (0 = automatic)
INTERPOLATE        Y          # Interpolate bad input pixels (Y/N)?
                   # (all or for each image)
FSCALASTRO_TYPE   VARIABLE   # NONE, FIXED, or VARIABLE
FSCALE_KEYWORD     FLXSCALE   # FITS keyword for the multiplicative
                   # factor applied to each input image
FSCALE_DEFAULT     1.0        # Default FSCALE value if not in header
GAIN_KEYWORD       GAIN       # FITS keyword for effect. gain (e-/ADU)
GAIN_DEFAULT       0.0        # Default gain if no FITS keyword found
                   # 0 = infinity (all or for each image)
SATLEV_KEYWORD     SATURATE  # FITS keyword for saturation level (ADU)
SATLEV_DEFAULT     50000.0    # Default saturation if no FITS keyword

```

```

#----- Background subtraction -----
SUBTRACT_BACK      Y          # Subtraction sky background (Y/N)?
                           # (all or for each image)
BACK_TYPE          AUTO       # AUTO or MANUAL
                           # (all or for each image)
BACK_DEFAULT        0.0       # Default background value in MANUAL
                           # (all or for each image)
BACK_SIZE           64        # Background mesh size (pixels)
                           # (all or for each image)
BACK_FILTERSIZE    3         # Background map filter range (meshes)
                           # (all or for each image)
BACK_FILTTHRESH   0.0       # Threshold above which the background-
                           # map filter operates

#----- Memory management -----
VMEM_DIR           .          # Directory path for swap files
VMEM_MAX            2047      # Maximum amount of virtual memory (MB)
MEM_MAX              4096      # Maximum amount of usable RAM (MB)
COMBINE_BUFSIZE    1024      # RAM dedicated to co-addition(MB)

#----- Miscellaneous -----
DELETE_TMPFILES    Y          # Delete temporary resampled FITS files
                           # (Y/N)?
COPY_KEYWORDS      OBJECT,FILTER,TELESCOP,INSTRUME,DETECTOR
                           # List of FITS keywords to propagate
                           # from the input to the output headers
WRITE_FILEINFO     Y          # Write information about each input
                           # file in the output image header?
WRITE_XML           Y          # Write XML file (Y/N)?
XML_NAME            CFHTLS_W_gri_022929-075600_T0007_SWarp_chi2.xml
                           # Filename for XML output
XSL_URL             swarp.xsl # Filename for XSL style-sheet
VERBOSE_TYPE        NORMAL     # QUIET,NORMAL or FULL
NNODES               1          # Number of nodes (for clusters)
NODE_INDEX           0          # Node index (for clusters)

NTHREADS             0          # Number of simultaneous threads for
                           # the SMP version of SWarp
                           # 0 = automatic

```

A.3.5 SExtractor .ldac catalogue configuration file for T0007 Wide

```

# Default configuration file for SExtractor 2.11.0
# EB 2010-02-11
#
# Last modified for SExtr stack.ldac MAG_APER(1):
# YG 2011-01-28

#----- Catalog -----
CATALOG_NAME      CFHTLS_W_r_141754+543031_T0007.ldac
                   # name of the output catalog
CATALOG_TYPE      FITS_LDAC
                   # NONE, ASCII, ASCII_HEAD, ASCII_SKYCAT,
                   # ASCII_VOTABLE, FITS_1.0 or FITS_LDAC
PARAMETERS_NAME   sextr-stack_APER1.param
                   # name of the file containing catalog contents

#----- Extraction -----
DETECT_TYPE        CCD
                   # CCD (linear) or PHOTO (with gamma correction)
DETECT_MINAREA    3
                   # min. number of pixels above threshold
DETECT_MAXAREA    0
                   # max. number of pixels above threshold (0=unlimited)
THRESH_TYPE        RELATIVE
                   # threshold type: RELATIVE (in sigmas)
                   # or ABSOLUTE (in ADUs)
DETECT_THRESH     1.0
                   # <sigmas> or <threshold>, <ZP> in mag.arcsec-2
ANALYSIS_THRESH   1.0
                   # <sigmas> or <threshold>, <ZP> in mag.arcsec-2
FILTER            Y
                   # apply filter for detection (Y or N)?
FILTER_NAME       default-auto.conv
                   # name of the file containing the filter
FILTER_THRESH     -
                   # Threshold[s] for retina filtering
DEBLEND_NTHRESH  32
                   # Number of deblending sub-thresholds
DEBLEND_MINCONT  0.002
                   # Minimum contrast parameter for deblending
CLEAN             Y
                   # Clean spurious detections? (Y or N)?
CLEAN_PARAM      1.0
                   # Cleaning efficiency
MASK_TYPE         CORRECT
                   # type of detection MASKing: can be one of
                   # NONE, BLANK or CORRECT

#----- WEIGHTing -----
WEIGHT_TYPE        MAP_WEIGHT
                   # type of WEIGHTing: NONE, BACKGROUND,
                   # MAP_RMS, MAP_VAR or MAP_WEIGHT
WEIGHT_IMAGE       CFHTLS_W_r_141754+543031_T0007_weight.fits
                   # weight-map filename
WEIGHT_GAIN        Y
                   # modulate gain (E/ADU) with weights? (Y/N)
WEIGHT_THRESH     -
                   # weight threshold[s] for bad pixels

#----- FLAGging -----
FLAG_IMAGE         flag.fits
                   # filename for an input FLAG-image
FLAG_TYPE          OR
                   # flag pixel combination: OR, AND, MIN, MAX
                   # or MOST

#----- Photometry -----
PHOT_APERTURES    34.853
                   # MAG_APER aperture diameter(s) in pixels
PHOT_AUTOPARAMS   2.5, 3.5
                   # MAG_AUTO parameters: <Kron_fact>, <min_radius>
PHOT_PETROPARAMS 2.0, 3.5
                   # MAG_PETRO parameters: <Petrosian_fact>,
                   # <min_radius>
PHOT_AUTOAPERS   0.0,0.0
                   # <estimation>, <measurement> minimum apertures
                   # for MAG_AUTO and MAG_PETRO
PHOT_FLUXFRAC    0.2,0.5,0.8
                   # flux fraction[s] used for FLUX_RADIUS
SATUR_LEVEL       50000.0
                   # level (in ADUs) at which arises saturation
SATUR_KEY         TOTO
                   # keyword for saturation level (in ADUs)
MAG_ZEROPPOINT   30.0
                   # magnitude zero-point
MAG_GAMMA         4.0
                   # gamma of emulsion (for photographic scans)
GAIN              0.0
                   # detector gain in e-/ADU
GAIN_KEY          GAIN
                   # keyword for detector gain in e-/ADU
PIXEL_SCALE       0
                   # size of pixel in arcsec (0=use FITS WCS info)

```

```

#----- Star/Galaxy Separation -----

SEEING_FWHM    0.9          # stellar FWHM in arcsec
STARNNW_NAME   default-auto.nnw # Neural-Network_Weight table filename

#----- Background -----

BACK_TYPE      AUTO         # AUTO or MANUAL
BACK_VALUE     0.0          # Default background value in MANUAL mode
BACK_SIZE       128          # Background mesh: <size> or <width>,<height>
BACK_FILTERSIZE 3            # Background filter: <size> or <width>,<height>
BACKPHOTO_TYPE GLOBAL        # can be GLOBAL or LOCAL
BACKPHOTO_THICK 24           # thickness of the background LOCAL annulus
BACK_FILTTHRESH 0.0          # Threshold above which the background-
                             # map filter operates

#----- Check Image -----

CHECKIMAGE_TYPE MINIBACKGROUND # can be NONE, BACKGROUND, BACKGROUND_RMS,
                             # MINIBACKGROUND, MINIBACK_RMS, -BACKGROUND,
                             # FILTERED, OBJECTS, -OBJECTS, SEGMENTATION,
                             # or APERTURES
CHECKIMAGE_NAME CFHTLS_W_r_141754+543031_T0007_mbkg.fits
                             # Filename for the check-image

#----- Memory (change with caution!) -----

MEMORY_OBJSTACK 3000         # number of objects in stack
MEMORY_PIXSTACK 300000        # number of pixels in stack
MEMORY_BUFSIZE 1024          # number of lines in buffer

#----- ASSOCiation -----

ASSOC_NAME      sky.list      # name of the ASCII file to ASSOCiate
ASSOC_DATA      2,3,4          # columns of the data to replicate (0=all)
ASSOC_PARAMS    2,3,4          # columns of xpos, ypos[,mag]
ASSOC_RADIUS    2.0           # cross-matching radius (pixels)
ASSOC_TYPE      NEAREST        # ASSOCiation method: FIRST, NEAREST, MEAN,
                             # MAG_MEAN, SUM, MAG_SUM, MIN or MAX
ASSOCSELEC_TYPE MATCHED       # ASSOC selection type: ALL, MATCHED or -MATCHED

#----- Miscellaneous -----

VERBOSE_TYPE    NORMAL        # can be QUIET, NORMAL or FULL
HEADER_SUFFIX   .head          # Filename extension for additional headers
WRITE_XML       Y              # Write XML file (Y/N)?
XML_NAME        CFHTLS_W_r_141754+543031_T0007_SExtr_ldac.xml
                             # Filename for XML output
XSL_URL         sextractor.xsl # Filename for XSL style-sheet
NTHREADS        1              # 1 single thread
FITS_UNSIGNED   N              # Treat FITS integer values as unsigned (Y/N)?
INTERP_MAXXLAG 16             # Max. lag along X for 0-weight interpolation
INTERP_MAXYLAG  16             # Max. lag along Y for 0-weight interpolation
INTERP_TYPE     ALL            # Interpolation type: NONE, VAR_ONLY or ALL

#----- Experimental Stuff -----

PSF_NAME        default.psf    # File containing the PSF model
PSF_NMAX        2              # Max. number of PSFs fitted simultaneously
PATTERN_TYPE   RINGS-HARMONIC # can RINGS-QUADPOLE, RINGS-OCTOPOLE,
                             # RINGS-HARMONICS or GAUSS-LAGUERRE
SOM_NAME        default.som    # File containing Self-Organizing Map weights

```

A.3.6 SExtractor DUAL MODE .cat catalogue configuration file for T0007 Wide

```

# Default configuration file for SExtractor 2.8.6
# EB 2009-04-09
#
# Last modified for CFHTLS-T0007 chi2 (Megacam):
# PH 2011-06-09

----- Catalog -----

CATALOG_NAME      CFHTLS_W_r_141754+543031_T0007.cat
                   # name of the output catalog
CATALOG_TYPE       ASCII_HEAD      # NONE,ASCII,ASCII_HEAD, ASCII_SKYCAT,
                   # ASCII_VOTABLE, FITS_1.0 or FITS_LDAC
PARAMETERS_NAME    sextr-chi2_APER27.param
                   # name of the file containing catalog contents

----- Extraction -----

DETECT_TYPE        CCD            # CCD (linear) or PHOTO (with gamma correction)
DETECT_MINAREA     3              # minimum number of pixels above threshold
THRESH_TYPE        ABSOLUTE      # threshold type: RELATIVE (in sigmas)
                           # or ABSOLUTE (in ADUs)
DETECT_THRESH      0.4           # <sigmas> or <threshold>,<ZP> in mag.arcsec-2
ANALYSIS_THRESH    0.4           # <sigmas> or <threshold>,<ZP> in mag.arcsec-2
FILTER             Y              # apply filter for detection (Y or N)?
FILTER_NAME        default-autochi2.conv
                   # name of the file containing the filter
FILTER_THRESH      # Threshold[s] for retina filtering
DEBLEND_NTHRESH   32             # Number of deblending sub-thresholds
DEBLEND_MINCONT   0.002          # Minimum contrast parameter for deblending
CLEAN              Y              # Clean spurious detections? (Y or N)?
CLEAN_PARAM        1.0             # Cleaning efficiency
MASK_TYPE          CORRECT        # type of detection MASKing: can be one of
                   # NONE, BLANK or CORRECT

----- WEIGHTing -----

WEIGHT_TYPE         MAP_WEIGHT,MAP_WEIGHT
                   # type of WEIGHTing: NONE, BACKGROUND,
                   # MAP_RMS, MAP_VAR or MAP_WEIGHT
WEIGHT_IMAGE        CFHTLS_W_gri_141754+543031_T0007_weight.fits,
                   CFHTLS_W_r_141754+543031_T0007_weight.fits
                   # weight-map filename
WEIGHT_GAIN          Y              # modulate gain (E/ADU) with weights? (Y/N)
WEIGHT_THRESH        # weight threshold[s] for bad pixels

----- FLAGging -----

FLAG_IMAGE          flag.fits      # filename for an input FLAG-image
FLAG_TYPE            OR             # flag pixel combination: OR, AND, MIN, MAX
                           # or MOST

----- Photometry -----

PHOT_APERTURES     10.,12.,14.,16.,18.,20.,22.,24.,26.,28.,30.,32.,34.,36.,38.,
                   40.,42.,44.,46.,48.,50.,52.,54.,56.,58.,60.,34.853
                   # MAG_APER aperture diameter(s) in pixels
PHOT_AUTOPARAMS    2.5, 3.5      # MAG_AUTO parameters: <Kron_fact>,<min_radius>
PHOT_PETROPARAMS   2.0, 3.5      # MAG_PETRO parameters: <Petrosian_fact>,
                           # <min_radius>
PHOT_AUTOAPERS     16.0,16.0     # <estimation>,<measurement> minimum apertures
                           # for MAG_AUTO and MAG_PETRO
PHOT_FLUXFRAC      0.2,0.5,0.8   # flux fraction[s] used for FLUX_RADIUS
SATUR_LEVEL         50000.0        # level (in ADUs) at which arises saturation
SATUR_KEY           TOTO           # keyword for saturation level (in ADUs)
MAG_ZEROPOINT       30.0            # magnitude zero-point

```

```

MAG_GAMMA      4.0          # gamma of emulsion (for photographic scans)
GAIN           0.0          # detector gain in e-/ADU
GAIN_KEY       GAIN         # keyword for detector gain in e-/ADU
PIXEL_SCALE    0            # size of pixel in arcsec (0=use FITS WCS info)

#----- Star/Galaxy Separation -----

SEEING_FWHM    0.9          # stellar FWHM in arcsec
STARNNW_NAME   default-autochi2.nnw
                           # Neural-Network_Weight table filename

#----- Background -----

BACK_TYPE      AUTO         # AUTO or MANUAL
BACK_VALUE     0.0          # Default background value in MANUAL mode
BACK_SIZE      256          # Background mesh: <size> or <width>,<height>
BACK_FILTERSIZE 9            # Background filter: <size> or <width>,<height>
BACKPHOTO_TYPE LOCAL        # can be GLOBAL or LOCAL
BACKPHOTO_THICK 30          # thickness of the background LOCAL annulus
BACK_FILTTHRESH 0.0         # Threshold above which the background-
                           # map filter operates

#----- Check Image -----

CHECKIMAGE_TYPE MINIBACKGROUND # can be NONE, BACKGROUND, BACKGROUND_RMS,
                           # MINIBACKGROUND, MINIBACK_RMS, -BACKGROUND,
                           # FILTERED, OBJECTS, -OBJECTS, SEGMENTATION,
                           # or APERTURES
CHECKIMAGE_NAME CFHTLS_W_r_141754+543031_T0007_mbkg_chi2.fits
                           # Filename for the check-image

#----- Memory (change with caution!) -----

MEMORY_OBJSTACK 5000         # number of objects in stack
MEMORY_PIXSTACK 1000000      # number of pixels in stack
MEMORY_BUFSIZE 1024          # number of lines in buffer

#----- ASSOCiation -----

ASSOC_NAME      sky.list      # name of the ASCII file to ASSOCiate
ASSOC_DATA      2,3,4          # columns of the data to replicate (0=all)
ASSOC_PARAMS    2,3,4          # columns of xpos,ypos[,mag]
ASSOC_RADIUS    2.0           # cross-matching radius (pixels)
ASSOC_TYPE      NEAREST       # ASSOCiation method: FIRST, NEAREST, MEAN,
                           # MAG_MEAN, SUM, MAG_SUM, MIN or MAX
ASSOCSELEC_TYPE MATCHED      # ASSOC selection type: ALL, MATCHED or -MATCHED

#----- Miscellaneous -----

VERBOSE_TYPE    NORMAL        # can be QUIET, NORMAL or FULL
WRITE_XML       Y             # Write XML file (Y/N)?
XML_NAME        CFHTLS_W_r_141754+543031_T0007_SExtr_chi2.xml
                           # Filename for XML output
XSL_URL        sextractor.xsl # Filename for XSL style-sheet
NTHREADS        0             # Number of simultaneous threads for
                           # the SMP version of SExtractor
                           # 0 = automatic
FITS_UNSIGNED   N             # Treat FITS integer values as unsigned (Y/N)?
INTERP_MAXXLAG 16            # Max. lag along X for 0-weight interpolation
INTERP_MAXYLAG 16            # Max. lag along Y for 0-weight interpolation
INTERP_TYPE     ALL           # Interpolation type: NONE, VAR_ONLY or ALL

#----- Experimental Stuff -----

PSF_NAME        default.psf   # File containing the PSF model
PSF_NMAX        9             # Max.number of PSFs fitted simultaneously
PSFDISPLAY_TYPE SPLIT        # Catalog type for PSF-fitting: SPLIT or VECTOR
PATTERN_TYPE    RINGS-HARMONIC # can RINGS-QUADPOLE, RINGS-OCTOPOLE,

```

```
SOM_NAME          # RINGS-HARMONICS or GAUSS-LAGUERRE
default.som       # File containing Self-Organizing Map weights
```

B CFHTLS T0007 Deep supplementary information

B.1 SCAMP configuration files for T0007 Deep

SCAMP internal astrometric reference catalogue run (D1,D2,D3,D4) :

```

# Default configuration file for SCAMP 1.5.5
# EB 2009-04-10
# Last modified for CFHTLS-T0007-D3 (Megacam):
# YG 2011-05-27

#----- Field grouping -----

FGROUP_RADIUS      1.0          # Max dist (deg) between field groups

#----- Reference catalogs -----

REF_SERVER          cocat1.u-strasbg.fr # Internet addresses of catalog servers
REF_PORT            1660         # Ports to connect to catalog servers
CDSCCLIENT_EXEC    aclient       # CDSClient executable
ASTREF_CATALOG     2MASS        # NONE, FILE, USNO-A1, USNO-A2, USNO-B1,
                           # GSC-1.3, GSC-2.2, UCAC-1, UCAC-2,
                           # NOMAD-1, 2MASS, DENIS-3,
                           # SDSS-R3, SDSS-R5 or SDSS-R6
ASTREF_BAND         DEFAULT      # Photom. band for astr.ref.magnitudes
                           # or DEFAULT, BLUEST, or REDDEST
ASTREFCAT_NAME     astrefcat.cat # Local astrometric reference catalogs
ASTREFCENT_KEYS    X_WORLD,Y_WORLD # Local ref.cat.centroid parameters
ASTREFERR_KEYS     ERRA_WORLD,ERRB_WORLD,ERRTHETA_WORLD
                   # Local ref.cat.error ellipse parameters
ASTREFMAG_KEY      MAG          # Local ref.cat.magnitude parameter
SAVE_REFCATALOG   N             # Save ref catalogs in FITS-LDAC format?
REFOUT_CATPATH    .             # Save path for reference catalogs

#----- Merged output catalogs -----

MERGEDOUTCAT_NAME CFHTLS-T0007-D3_SCamp_astr_ref.cat
                   # Merged output catalog filename
MERGEDOUTCAT_TYPE FITS_LDAC    # NONE, ASCII_HEAD, ASCII, FITS_LDAC

#----- Pattern matching -----

MATCH              Y             # Do pattern-matching (Y/N) ?
MATCH_NMAX         0             # Max.number of detections for MATCHing
                           # (0=auto)
PIXSCALE_MAXERR   1.2          # Max scale-factor uncertainty
POSANGLE_MAXERR   5.0          # Max position-angle uncertainty (deg)
POSITION_MAXERR   1.0          # Max positional uncertainty (arcmin)
MATCH_RESOL        0             # Matching resolution (arcsec); 0=auto
MATCH_FLIPPED     N             # Allow matching with flipped axes?
MOSAIC_TYPE       SAME_CRVAL  # UNCHANGED, SAME_CRVAL, SHARE_PROJAXIS,
                           # FIX_FOCALPLANE or LOOSE
FIXFOCALPLANE_NMIN 1             # Min number of dets for FIX_FOCALPLANE

#----- Cross-identification -----

CROSSID_RADIUS    2.0          # Cross-id initial radius (arcsec)

#----- Astrometric solution -----

SOLVE_ASTROM       Y             # Compute astrometric solution (Y/N) ?
ASTRINSTRU_KEY    FILTER,QRUNID # FITS keyword(s) defining the astrom
INSTRUMENT         # EXPOSURE, GROUP, INSTRUMENT or FILE
CENTROID_KEYS     XWIN_IMAGE,YWIN_IMAGE
                   # Cat. parameters for centroiding
CENTROIDERR_KEYS  ERRAWN_IMAGE,ERRBWIN_IMAGE,ERRTHETAWN_IMAGE
                   # Cat. params for centroid err ellipse

```

```

DISTORT_KEYS          XWIN_IMAGE,YWIN_IMAGE
                      # Cat. parameters or FITS keywords
DISTORT_GROUPS        1,1           # Polynom group for each context key
DISTORT_DEGREES       3              # Polynom degree for each group
ASTREF_WEIGHT         1.0            # Relative weight of ref.astrom.cat.
ASTRCLIP_NSIGMA      3.0            # Astrom. clipping threshold in sigmas
CORRECT_COLOURSHIFTS N              # Correct for colour shifts (Y/N)?

#----- Photometric solution -----
SOLVE_PHOTOM          Y              # Compute photometric solution (Y/N) ?
MAGZERO_OUT            30.0           # Magnitude zero-point(s) in output
MAGZERO_INTERR         0.01           # Internal mag.zero-point accuracy
MAGZERO_REFERR         0.03           # Photom.field mag.zero-point accuracy
PHOTINSTRU_KEY         FILTER          # FITS keyword(s) defining the photom.
MAGZERO_KEY             PHOT_C          # FITS keyword for the mag zero-point
EXPOTIME_KEY            EXPTIME         # FITS keyword for the exposure time (s)
AIRMASS_KEY             AIRMASS         # FITS keyword for the airmass
EXTINCT_KEY             PHOT_K          # FITS keyword for the extinction coeff
PHOTOMFLAG_KEY          PHOTFLAG         # FITS keyword for the photometry flag
PHOTFLUX_KEY            FLUX_AUTO        # Catalog param. for the flux measurement
PHOTFLUXERR_KEY         FLUXERR_AUTO    # Catalog parameter for the flux error
PHOTCLIP_NSIGMA         3.0             # Photom.clipping threshold in sigmas

#----- Check-plots -----
CHECKPLOT_CKEY         SCAMPCOL        # FITS keyword for PLPLOT field colour
CHECKPLOT_DEV           PNG             # NULL, XWIN, TK, PS, PSC, XFIG, PNG,
                                      # JPEG, AQT, PDF or SVG
CHECKPLOT_RES            1600,1200       # Check-plot resolution (0 = default)
CHECKPLOT_ANTIALIAS      Y              # Anti-aliasing using convert (Y/N) ?
CHECKPLOT_TYPE           DISTORTION,ASTR_INTERRORE2D,ASTR_INTERRORE1D,ASTR_REFERROR2D,
                        ASTR_REFERROR1D,ASTR_CHI2,PHOT_ERROR,PHOT_ERRORVSMAG,
                        PHOT_ZPCORR,PHOT_ZPCORR3D
CHECKPLOT_NAME           distort,astr_interrore2d,astr_interrore1d,astr_referror2d,
                        astr_referror1d,astr_chi2,psphot_error,phot_errorvsmag,
                        phot_zpcorr,phot_zpcorr3d
                                      # Check-plot filename(s)

#----- Check-images -----
CHECKIMAGE_TYPE          NONE            # NONE, AS_PAIR, AS_REFPAIR, or AS_XCORR
CHECKIMAGE_NAME           check.fits      # Check-image filename(s)

#----- Miscellaneous -----
SN_THRESHOLDS           10.0,100.0     # S/N thresholds (in sigmas) for all and
                                      # high-SN sample
FWHM_THRESHOLDS         0.0,100.0      # FWHM thresholds (in pixels) for sources
FLAGS_MASK               0x00ff          # Rejection mask on SEx FLAGS
WEIGHTFLAGS_MASK         0x0fff          # Rejection mask on SEx FLAGS_WEIGHT
IMAFLAGS_MASK            0x0             # Rejection mask on SEx IMAFLAGS_ISO
AHEADER_GLOBAL           /usr/share/scamp/megacam.ahead
                                      # Filename of the global INPUT header
AHEADER_SUFFIX            .ahead          # Filename extension for additional
                                      # INPUT headers
HEADER_SUFFIX             .head            # Filename extension for OUTPUT headers
HEADER_TYPE               NORMAL           # NORMAL or FOCAL_PLANE
VERBOSE_TYPE              LOG              # QUIET, NORMAL, LOG or FULL
WRITE_XML                 Y                # Write XML file (Y/N)?
XML_NAME                 CFHTLS-T0007-D3_SCamp_astr_ref.xml # Filename for XML output
XSL_URL                  scamp.xsl        # Filename for XSL style-sheet
NTHREADS                 0                # Number of simultaneous threads for
                                      # the SMP version of SCAMP
                                      # 0 = automatic

```

SCAMP astrometric run using internal astrometric reference catalogue (D1,D2,D3,D4) :

```

# Default configuration file for SCAMP 1.5.5
# EB 2009-04-10
# Last modified for CFHTLS-T0007-D3 (Megacam):
# YG 2011-02-21

#----- Field grouping -----

FGROUP_RADIUS      1.0          # Max dist (deg) between field groups

#----- Reference catalogs -----

REF_SERVER          cocat1.u-strasbg.fr # Internet addresses of catalog servers
REF_PORT            1660         # Ports to connect to catalog servers
CDSCCLIENT_EXEC     aclient       # CDSClient executable
ASTREF_CATALOG      FILE         # NONE, FILE, USNO-A1, USNO-A2, USNO-B1,
                                # GSC-1.3, GSC-2.2, UCAC-1, UCAC-2,
                                # NOMAD-1, 2MASS, DENIS-3,
                                # SDSS-R3, SDSS-R5 or SDSS-R6
ASTREF_BAND          DEFAULT      # Photom. band for astr.ref.magnitudes
                                # or DEFAULT, BLUEST, or REDDEST
ASTREFCAT_NAME       CFHTLS-T0007-D3_SCamp_astr_ref.cat
ASTREFCENT_KEYS     X_WORLD, Y_WORLD # Local ref.cat.centroid parameters
ASTREFERR_KEYS      ERRA_WORLD, ERRB_WORLD, ERRTHETA_WORLD
ASTREFMAG_KEY        MAG          # Local ref.cat.magnitude parameter
SAVE_REFCATALOG     N             # Save ref catalogs in FITS-LDAC format?
REFOUT_CATPATH      .             # Save path for reference catalogs

#----- Merged output catalogs -----

MERGEDOUTCAT_NAME   scamp.cat    # Merged output catalog filename
MERGEDOUTCAT_TYPE    NONE         # NONE, ASCII_HEAD, ASCII, FITS_LDAC

#----- Pattern matching -----

MATCH               Y             # Do pattern-matching (Y/N) ?
MATCH_NMAX          0             # Max.number of detections for MATCHing
                                # (0=auto)
PIXSCALE_MAXERR     1.2          # Max scale-factor uncertainty
POSANGLE_MAXERR     5.0          # Max position-angle uncertainty (deg)
POSITION_MAXERR     1.0          # Max positional uncertainty (arcmin)
MATCH_RESOL          0             # Matching resolution (arcsec); 0=auto
MATCH_FLIPPED        N             # Allow matching with flipped axes?
MOSAIC_TYPE          SAME_CRVAL # UNCHANGED, SAME_CRVAL, SHARE_PROJAXIS,
                                # FIX_FOCALPLANE or LOOSE
FIXFOCALPLANE_NMIN  1             # Min number of dets for FIX_FOCALPLANE

#----- Cross-identification -----

CROSSID_RADIUS      2.0          # Cross-id initial radius (arcsec)

#----- Astrometric solution -----

SOLVE_ASTROM         Y             # Compute astrometric solution (Y/N) ?
ASTRINSTRU_KEY       FILTER,QRUNID # FITS keyword(s) defining the astrom
INSTRUMENT           INSTRUMENT   # EXPOSURE, GROUP, INSTRUMENT or FILE
CENTROID_KEYS        XWIN_IMAGE, YWIN_IMAGE
                                # Cat. parameters for centroiding
CENTROIDERR_KEYS     ERRAWN_IMAGE,ERRBWN_IMAGE,ERRTHETAWN_IMAGE
                                # Cat. params for centroid err ellipse
DISTORT_KEYS          XWIN_IMAGE, YWIN_IMAGE
                                # Cat. parameters or FITS keywords
DISTORT_GROUPS        1,1          # Polynom group for each context key
DISTORT_DEGREES       3             # Polynom degree for each group
ASTREF_WEIGHT         1.0          # Relative weight of ref.astrom.cat.

```

```

ASTRCLIP_NSIGMA      3.0          # Astrom. clipping threshold in sigmas
CORRECT_COLOURSHIFTS N           # Correct for colour shifts (Y/N)?

#----- Photometric solution -----
SOLVE_PHOTOM        Y           # Compute photometric solution (Y/N) ?
MAGZERO_OUT          30.0         # Magnitude zero-point(s) in output
MAGZERO_INERR        0.01         # Internal mag.zero-point accuracy
MAGZERO_REFERR       0.03         # Photom.field mag.zero-point accuracy
PHOTINSTRU_KEY       FILTER        # FITS keyword(s) defining the photom.
MAGZERO_KEY          PHOT_C        # FITS keyword for the mag zero-point
EXPOTIME_KEY         EXPTIME       # FITS keyword for the exposure time (s)
AIRMASS_KEY          AIRMASS       # FITS keyword for the airmass
EXTINCT_KEY          PHOT_K        # FITS keyword for the extinction coeff
PHOTOMFLAG_KEY       PHOTFLAG      # FITS keyword for the photometry flag
PHOTFLUX_KEY         FLUX_AUTO    # Catalog param. for the flux measurement
PHOTFLUXERR_KEY      FLUXERR_AUTO # Catalog parameter for the flux error
PHOTCLIP_NSIGMA      3.0          # Photom.clipping threshold in sigmas

#----- Check-plots -----
CHECKPLOT_CKEY       SCAMPCOL     # FITS keyword for PLPLOT field colour
CHECKPLOT_DEV         PNG          # NULL, XWIN, TK, PS, PSC, XFIG, PNG,
                                # JPEG, AQT, PDF or SVG
CHECKPLOT_RES         1600,1200   # Check-plot resolution (0 = default)
CHECKPLOT_ANTIALIAS  Y           # Anti-aliasing using convert (Y/N) ?
CHECKPLOT_TYPE        DISTORTION,ASTR_INTERRORED2D,ASTR_INTERRORED1D,ASTR_REFERROR2D,
                      ASTR_REFERROR1D,ASTR_CHI2,PHOT_ERROR,PHOT_ERRORVSMAG,
                      PHOT_ZPCORR,PHOT_ZPCORR3D
CHECKPLOT_NAME        distort,astr_interror2d,astr_interror1d,astr_referror2d,
                      astr_referror1d,astr_chi2,psphot_error,phot_errorvsmag,
                      phot_zpcorr,phot_zpcorr3d
                                # Check-plot filename(s)

#----- Check-images -----
CHECKIMAGE_TYPE        NONE         # NONE, AS_PAIR, AS_REFPAIR, or AS_XCORR
CHECKIMAGE_NAME        check.fits   # Check-image filename(s)

#----- Miscellaneous -----
SN_THRESHOLDS         10.0,100.0 # S/N thresholds (in sigmas) for all and
                                # high-SN sample
FWHM_THRESHOLDS       0.0,100.0 # FWHM thresholds (in pixels) for sources
FLAGS_MASK             0x00f0      # Rejection mask on SEx FLAGS
WEIGHTFLAGS_MASK      0x00ff      # Rejection mask on SEx FLAGS_WEIGHT
IMAFLAGS_MASK         0x0          # Rejection mask on SEx IMAFLAGS_ISO
AHEADER_GLOBAL         /usr/share/scamp/megacam.ahead
                                # Filename of the global INPUT header
AHEADER_SUFFIX         .ahead       # Filename extension for additional
                                # INPUT headers
HEADER_SUFFIX          .head        # Filename extension for OUTPUT headers
HEADER_TYPE            NORMAL       # NORMAL or FOCAL_PLANE
VERBOSE_TYPE           LOG          # QUIET, NORMAL, LOG or FULL
WRITE_XML              Y           # Write XML file (Y/N)?
XML_NAME               CFHTLS-T0007-D3_SCamp_astr_g.xml
                                # Filename for XML output
XSL_URL                scamp.xsl    # Filename for XSL style-sheet
NTHREADS               0           # Number of simultaneous threads for
                                # the SMP version of SCAMP
                                # 0 = automatic

```

SCAMP photometric run (D1,D2,D3,D4) :

```

# Default configuration file for SCAMP 1.5.5
# EB 2009-04-10
# Last modified for CFHTLS-T0007-D3 (Megacam):
# YG 2011-06-10

#----- Field grouping -----

FGROUP_RADIUS      1.0          # Max dist (deg) between field groups

#----- Reference catalogs -----

REF_SERVER          cocat1.u-strasbg.fr # Internet addresses of catalog servers
REF_PORT            1660         # Ports to connect to catalog servers
CDSCCLIENT_EXEC     aclient       # CDSClient executable
ASTREF_CATALOG      FILE          # NONE, FILE, USNO-A1, USNO-A2, USNO-B1,
                                # GSC-1.3, GSC-2.2, UCAC-1, UCAC-2,
                                # NOMAD-1, 2MASS, DENIS-3,
                                # SDSS-R3, SDSS-R5 or SDSS-R6
ASTREF_BAND         DEFAULT      # Photom. band for astr.ref.magnitudes
                                # or DEFAULT, BLUEST, or REDDEST
ASTREFCAT_NAME      CFHTLS-T0007-D3_SCamp_astr_ref.cat
ASTREFCENT_KEYS     X_WORLD, Y_WORLD # Local ref.cat.centroid parameters
ASTREFERR_KEYS      ERRA_WORLD, ERRB_WORLD, ERRTHETA_WORLD
ASTREFMAG_KEY        MAG          # Local ref.cat.magnitude parameter
SAVE_REFCATALOG    N             # Save ref catalogs in FITS-LDAC format?
REFOUT_CATPATH     .             # Save path for reference catalogs

#----- Merged output catalogs -----

MERGEDOUTCAT_NAME  scamp.cat    # Merged output catalog filename
MERGEDOUTCAT_TYPE   NONE         # NONE, ASCII_HEAD, ASCII, FITS_LDAC

#----- Pattern matching -----

MATCH               N             # Do pattern-matching (Y/N) ?
MATCH_NMAX          0             # Max.number of detections for MATCHing
                                # (0=auto)
PIXSCALE_MAXERR    1.2           # Max scale-factor uncertainty
POSANGLE_MAXERR    5.0           # Max position-angle uncertainty (deg)
POSITION_MAXERR    1.0           # Max positional uncertainty (arcmin)
MATCH_RESOL         0             # Matching resolution (arcsec); 0=auto
MATCH_FLIPPED       N             # Allow matching with flipped axes?
MOSAIC_TYPE         UNCHANGED    # UNCHANGED, SAME_CRVAL, SHARE_PROJAXIS,
                                # FIX_FOCALPLANE or LOOSE
FIXFOCALPLANE_NMIN 1             # Min number of dets for FIX_FOCALPLANE

#----- Cross-identification -----

CROSSID_RADIUS      2.0          # Cross-id initial radius (arcsec)

#----- Astrometric solution -----

SOLVE_ASTROM        N             # Compute astrometric solution (Y/N) ?
ASTRINSTRU_KEY      FILTER,QRUNID # FITS keyword(s) defining the astrom
INSTRUMENT          # EXPOSURE, GROUP, INSTRUMENT or FILE
CENTROID_KEYS       XWIN_IMAGE,YWIN_IMAGE # Cat. parameters for centroiding
ERRAWIN_IMAGE,ERRBWIN_IMAGE,ERRTHETAWIN_IMAGE
                                # Cat. params for centroid err ellipse
DISTORT_KEYS        XWIN_IMAGE,YWIN_IMAGE # Cat. parameters or FITS keywords
DISTORT_GROUPS      1,1           # Polynom group for each context key
DISTORT_DEGREES     3              # Polynom degree for each group
ASTREF_WEIGHT        1.0           # Relative weight of ref.astrom.cat.
ASTRCLIP_NSIGMA     3.0           # Astrom. clipping threshold in sigmas
CORRECT_COLOURSHIFTS N             # Correct for colour shifts (Y/N)?

```

```

#----- Photometric solution -----
SOLVE_PHOTOM      Y          # Compute photometric solution (Y/N) ?
MAGZERO_OUT        30.0       # Magnitude zero-point(s) in output
MAGZERO_INTERR    0.01       # Internal mag.zero-point accuracy
MAGZERO_REFERR    0.03       # Photom.field mag.zero-point accuracy
PHOTINSTRU_KEY    FILTER     # FITS keyword(s) defining the photom.
MAGZERO_KEY        PHOT_C     # FITS keyword for the mag zero-point
EXPOTIME_KEY       EXPTIME    # FITS keyword for the exposure time (s)
AIRMASS_KEY        AIRMASS   # FITS keyword for the airmass
EXTINCT_KEY        PHOT_K     # FITS keyword for the extinction coeff
PHOTOMFLAG_KEY    PHOTFLAG   # FITS keyword for the photometry flag
PHOTFLUX_KEY       FLUX_AUTO # Catalog param. for the flux measurement
PHOTFLUXERR_KEY   FLUXERR_AUTO # Catalog parameter for the flux error
PHOTCLIP_NSIGMA   3.0        # Photom.clipping threshold in sigmas

#----- Check-plots -----
CHECKPLOT_CKEY    SCAMPCOL  # FITS keyword for PLPLOT field colour
CHECKPLOT_DEV      PNG        # NULL, XWIN, TK, PS, PSC, XFIG, PNG,
                           # JPEG, AQT, PDF or SVG
CHECKPLOT_RES      1600,1200 # Check-plot resolution (0 = default)
CHECKPLOT_ANTIALIAS Y          # Anti-aliasing using convert (Y/N) ?
CHECKPLOT_TYPE     DISTORTION,ASTR_INTERTERROR2D,ASTR_INTERTERROR1D,ASTR_REFERROR2D,
                   ASTR_REFERROR1D,ASTR_CHI2,PHOT_ERROR,PHOT_ERRORVSMAG,
                   PHOT_ZPCORR,PHOT_ZPCORR3D
CHECKPLOT_NAME     distort,astr_interror2d,astr_interror1d,astr_referror2d,
                   astr_referror1d,astr_chi2,psphot_error,phot_errorvsmag,
                   phot_zpcorr,phot_zpcorr3d
                           # Check-plot filename(s)

#----- Check-images -----
CHECKIMAGE_TYPE    NONE       # NONE, AS_PAIR, AS_REFPAIR, or AS_XCORR
CHECKIMAGE_NAME    check.fits # Check-image filename(s)

#----- Miscellaneous -----
SN_THRESHOLDS     10.0,100.0 # S/N thresholds (in sigmas) for all and
                           # high-SN sample
FWHM_THRESHOLDS   0.0,100.0 # FWHM thresholds (in pixels) for sources
FLAGS_MASK         0x00f0    # Rejection mask on SEx FLAGS
WEIGHTFLAGS_MASK  0x00ff    # Rejection mask on SEx FLAGS_WEIGHT
IMAFLAGS_MASK     0x0        # Rejection mask on SEx IMAFLAGS_ISO
AHEADER_GLOBAL    /usr/share/scamp/megacam.ahead
                           # Filename of the global INPUT header
AHEADER_SUFFIX     .ahead     # Filename extension for additional
                           # INPUT headers
HEADER_SUFFIX      .head      # Filename extension for OUTPUT headers
HEADER_TYPE        NORMAL    # NORMAL or FOCAL_PLANE
VERBOSE_TYPE       LOG       # QUIET, NORMAL, LOG or FULL
WRITE_XML          Y         # Write XML file (Y/N)?
XML_NAME          CFHTLS-T0007-D3_SCamp_phot_g.xml
                           # Filename for XML output
XSL_URL            scamp.xsl # Filename for XSL style-sheet
NTHREADS           0          # Number of simultaneous threads for
                           # the SMP version of SCAMP
                           # 0 = automatic

```

B.1.1 SWarp stack configuration file for T0007 Deep

```

# Default configuration file for SWarp 2.17.6
# EB 2009-04-09
#
# Last modified for CFHTLS-T0007 (Megacam):
# YG 2011-09-01

#----- Output -----
IMAGEOUT_NAME      CFHTLS_D-85_g_221531-174356_T0007.fits
                   # Output filename
WEIGHTOUT_NAME     CFHTLS_D-85_g_221531-174356_T0007_weight.fits
                   # Output weight-map filename

HEADER_ONLY        N          # Only a header as an output file (Y/N)?
HEADER_SUFFIX      .head      # Filename extension for additional headers

#----- Input Weights -----
WEIGHT_TYPE        MAP_WEIGHT    # BACKGROUND,MAP_RMS,MAP_VARIANCE
                   # or MAP_WEIGHT
WEIGHT_SUFFIX      _weight.fits # Suffix to use for weight-maps
WEIGHT_IMAGE       _weight.fits # Weightmap filename if suffix not used
WEIGHT_THRESH      # (all or for each weight-map)
                   # Bad pixel weight-threshold

#----- Co-addition -----
COMBINE            Y          # Combine resampled images (Y/N)?
COMBINE_TYPE       MEDIAN     # MEDIAN,AVERAGE,MIN,MAX,WEIGHTED,CHI2
                   # or SUM
BLANK_BADPIXELS   N          # Set to 0 pixels having a weight of 0

#----- Astrometry -----
CELESTIAL_TYPE     NATIVE     # NATIVE, PIXEL, EQUATORIAL,
                   # GALACTIC,ECLIPTIC, or SUPERGALACTIC
PROJECTION_TYPE    TAN        # Any WCS projection code or NONE
PROJECTION_ERR     0.001      # Maximum projection error (in output
                   # pixels), or 0 for no approximation
CENTER_TYPE        MANUAL     # MANUAL, ALL or MOST
CENTER             22:15:31,-17:43:56 # Coordinates of the image center
PIXELSCALE_TYPE    MANUAL     # MANUAL,FIT,MIN,MAX or MEDIAN
PIXEL_SCALE        0.186      # Pixel scale
IMAGE_SIZE         19354,19354 # Image size (0 = AUTOMATIC)

#----- Resampling -----
RESAMPLE           Y          # Resample input images (Y/N)?
RESAMPLE_DIR       .
RESAMPLE_SUFFIX    .resamp.fits # filename extension for resampled images
RESAMPLING_TYPE   LANCZOS3   # NEAREST,BILINEAR,LANCZOS2,LANCZOS3
                   # or LANCZOS4 (1 per axis)
OVERSAMPLING       0          # Oversampling in each dimension
                   # (0 = automatic)
INTERPOLATE        Y          # Interpolate bad input pixels (Y/N)?
                   # (all or for each image)
FSCALASTRO_TYPE   VARIABLE   # NONE,FIXED, or VARIABLE
FSCALE_KEYWORD     FLXSCALE   # FITS keyword for the multiplicative
                   # factor applied to each input image
FSCALE_DEFAULT     1.0        # Default FSCALE value if not in header
GAIN_KEYWORD       GAIN       # FITS keyword for effect. gain (e-/ADU)
GAIN_DEFAULT       0.0        # Default gain if no FITS keyword found
                   # 0 = infinity (all or for each image)
SATLEV_KEYWORD     SATURATE  # FITS keyword for saturation level (ADU)
SATLEV_DEFAULT     50000.0    # Default saturation if no FITS keyword

```

```

#----- Background subtraction -----
SUBTRACT_BACK      Y          # Subtraction sky background (Y/N)?
                           # (all or for each image)
BACK_TYPE          AUTO       # AUTO or MANUAL
                           # (all or for each image)
BACK_DEFAULT        0.0       # Default background value in MANUAL
                           # (all or for each image)
BACK_SIZE           128       # Background mesh size (pixels)
                           # (all or for each image)
BACK_FILTERSIZE     3         # Background map filter range (meshes)
                           # (all or for each image)
BACK_FILTTHRESH    0.0       # Threshold above which the background-
                           # map filter operates

#----- Memory management -----
VMEM_DIR           .          # Directory path for swap files
VMEM_MAX            2047      # Maximum amount of virtual memory (MB)
MEM_MAX              128       # Maximum amount of usable RAM (MB)
COMBINE_BUFSIZE     400       # RAM dedicated to co-addition(MB)

#----- Miscellaneous -----
DELETE_TMPFILES     Y          # Delete temporary resampled FITS files
                           # (Y/N)?

COPY_KEYWORDS       FILTER,INSTRUME,TELESCOP,DETECTOR,OBSERVER,PHOT_C,PHOT_K,
                   OBJECT,DATE_OBS,ORIGIN,SEEING,REL_DATE
                           # List of FITS keywords to propagate
                           # from the input to the output headers
WRITE_FILEINFO      N          # Write information about each input
                           # file in the output image header?
WRITE_XML            Y          # Write XML file (Y/N)?
XML_NAME            CFHTLS_D-85_g_221531-174356_T0007_SWarp.xml
                           # Filename for XML output
XSL_URL              swarp.xsl # Filename for XSL style-sheet
VERBOSE_TYPE         NORMAL     # QUIET,NORMAL or FULL
NNODES                1          # Number of nodes (for clusters)
NODE_INDEX            0          # Node index (for clusters)
NTHREADS              0          # Number of simultaneous threads for
                           # the SMP version of SWarp
                           # 0 = automatic

```

B.1.2 SWarp chi2-image configuration file for T0007 Deep

```

# Default configuration file for SWarp 2.17.6
# EB 2009-04-09
#
# Last modified for CFHTLS-T0007 chi2 (Megacam):
# YG 2011-09-22

#----- Output -----
IMAGEOUT_NAME      CFHTLS_D-85_gri_221531-174356_T0007.fits
                   # Output filename
WEIGHTOUT_NAME     CFHTLS_D-85_gri_221531-174356_T0007_weight.fits
                   # Output weight-map filename

HEADER_ONLY        N          # Only a header as an output file (Y/N)?
HEADER_SUFFIX      .head      # Filename extension for additional headers

#----- Input Weights -----
WEIGHT_TYPE        MAP_WEIGHT    # BACKGROUND,MAP_RMS,MAP_VARIANCE
                   # or MAP_WEIGHT
WEIGHT_SUFFIX      _weight.fits # Suffix to use for weight-maps
WEIGHT_IMAGE       _weight.fits # Weightmap filename if suffix not used
WEIGHT_THRESH      # (all or for each weight-map)
                   # Bad pixel weight-threshold

#----- Co-addition -----
COMBINE            Y          # Combine resampled images (Y/N)?
COMBINE_TYPE       CHI2        # MEDIAN,AVERAGE,MIN,MAX,WEIGHTED,CHI2
                   # or SUM
BLANK_BADPIXELS   N          # Set to 0 pixels having a weight of 0

#----- Astrometry -----
CELESTIAL_TYPE     NATIVE     # NATIVE, PIXEL, EQUATORIAL,
                   # GALACTIC,ECLIPPTIC, or SUPERGALACTIC
PROJECTION_TYPE    TAN        # Any WCS projection code or NONE
PROJECTION_ERR     0.001      # Maximum projection error (in output
                   # pixels), or 0 for no approximation
CENTER_TYPE        MANUAL     # MANUAL, ALL or MOST
CENTER             22:15:31,-17:43:56 # Coordinates of the image center
PIXELSCALE_TYPE    MANUAL     # MANUAL,FIT,MIN,MAX or MEDIAN
PIXEL_SCALE        0.186      # Pixel scale
IMAGE_SIZE         19354,19354 # Image size (0 = AUTOMATIC)

#----- Resampling -----
RESAMPLE           Y          # Resample input images (Y/N)?
RESAMPLE_DIR       .
RESAMPLE_SUFFIX    .resamp.fits # filename extension for resampled images
RESAMPLING_TYPE   LANCZOS3   # NEAREST,BILINEAR,LANCZOS2,LANCZOS3
                   # or LANCZOS4 (1 per axis)
OVERSAMPLING       0          # Oversampling in each dimension
                   # (0 = automatic)
INTERPOLATE        Y          # Interpolate bad input pixels (Y/N)?
                   # (all or for each image)
FSCALASTRO_TYPE   VARIABLE   # NONE, FIXED, or VARIABLE
FSCALE_KEYWORD     FLXSCALE   # FITS keyword for the multiplicative
                   # factor applied to each input image
FSCALE_DEFAULT     1.0        # Default FSCALE value if not in header
GAIN_KEYWORD       GAIN       # FITS keyword for effect. gain (e-/ADU)
GAIN_DEFAULT       0.0        # Default gain if no FITS keyword found
                   # 0 = infinity (all or for each image)
SATLEV_KEYWORD     SATURATE  # FITS keyword for saturation level (ADU)
SATLEV_DEFAULT     50000.0    # Default saturation if no FITS keyword

```

```

#----- Background subtraction -----
SUBTRACT_BACK      Y          # Subtraction sky background (Y/N)?
                           # (all or for each image)
BACK_TYPE          AUTO       # AUTO or MANUAL
                           # (all or for each image)
BACK_DEFAULT        0.0       # Default background value in MANUAL
                           # (all or for each image)
BACK_SIZE           64        # Background mesh size (pixels)
                           # (all or for each image)
BACK_FILTERSIZE    3         # Background map filter range (meshes)
                           # (all or for each image)
BACK_FILTTHRESH   0.0       # Threshold above which the background-
                           # map filter operates

#----- Memory management -----
VMEM_DIR           .          # Directory path for swap files
VMEM_MAX            2047      # Maximum amount of virtual memory (MB)
MEM_MAX              4096      # Maximum amount of usable RAM (MB)
COMBINE_BUFSIZE    1024      # RAM dedicated to co-addition(MB)

#----- Miscellaneous -----
DELETE_TMPFILES    Y          # Delete temporary resampled FITS files
                           # (Y/N)?
COPY_KEYWORDS      OBJECT,FILTER # List of FITS keywords to propagate
                           # from the input to the output headers
WRITE_FILEINFO     Y          # Write information about each input
                           # file in the output image header?
WRITE_XML           Y          # Write XML file (Y/N)?
XML_NAME            CFHTLS_D-85_gri_221531-174356_T0007_SWarp_chi2.xml
                           # Filename for XML output
XSL_URL             swarp.xsl # Filename for XSL style-sheet
VERBOSE_TYPE        NORMAL     # QUIET,NORMAL or FULL
NNODES               1          # Number of nodes (for clusters)
NODE_INDEX           0          # Node index (for clusters)
NTHREADS             0          # Number of simultaneous threads for
                           # the SMP version of SWarp
                           # 0 = automatic

```

B.1.3 SExtractor .ldac catalogue configuration file for T0007 Deep

```

# Default configuration file for SExtractor 2.11.0
# EB 2010-02-11
#
# Last modified for SExtr stack.ldac MAG_APER(1):
# YG 2011-01-28

#----- Catalog -----
CATALOG_NAME CFHTLS_D-85_y_100028+021230_T0007.ldac
# name of the output catalog
CATALOG_TYPE FITS_LDAC
# NONE, ASCII, ASCII_HEAD, ASCII_SKYCAT,
# ASCII_VOTABLE, FITS_1.0 or FITS_LDAC
PARAMETERS_NAME sextr-stack_APER1.param
# name of the file containing catalog contents

#----- Extraction -----
DETECT_TYPE CCD # CCD (linear) or PHOTO (with gamma correction)
DETECT_MINAREA 3 # min. number of pixels above threshold
DETECT_MAXAREA 0 # max. number of pixels above threshold (0=unlimited)
THRESH_TYPE RELATIVE # threshold type: RELATIVE (in sigmas)
# or ABSOLUTE (in ADUs)
DETECT_THRESH 1.0 # <sigmas> or <threshold>, <ZP> in mag.arcsec-2
ANALYSIS_THRESH 1.0 # <sigmas> or <threshold>, <ZP> in mag.arcsec-2
FILTER Y # apply filter for detection (Y or N)?
FILTER_NAME default-auto.conv # name of the file containing the filter
FILTER_THRESH # Threshold[s] for retina filtering
DEBLEND_NTHRESH 32 # Number of deblending sub-thresholds
DEBLEND_MINCONT 0.002 # Minimum contrast parameter for deblending
CLEAN Y # Clean spurious detections? (Y or N)?
CLEAN_PARAM 1.0 # Cleaning efficiency
MASK_TYPE CORRECT # type of detection MASKing: can be one of
# NONE, BLANK or CORRECT

#----- WEIGHTing -----
WEIGHT_TYPE MAP_WEIGHT # type of WEIGHTing: NONE, BACKGROUND,
# MAP_RMS, MAP_VAR or MAP_WEIGHT
WEIGHT_IMAGE CFHTLS_D-85_y_100028+021230_T0007_weight.fits
# weight-map filename
WEIGHT_GAIN Y # modulate gain (E/ADU) with weights? (Y/N)
WEIGHT_THRESH # weight threshold[s] for bad pixels

#----- FLAGging -----
FLAG_IMAGE flag.fits # filename for an input FLAG-image
FLAG_TYPE OR # flag pixel combination: OR, AND, MIN, MAX
# or MOST

#----- Photometry -----
PHOT_APERTURES 27.7139 # MAG_APER aperture diameter(s) in pixels
PHOT_AUTOPARAMS 2.5, 3.5 # MAG_AUTO parameters: <Kron_fact>, <min_radius>
PHOT_PETROPARAMS 2.0, 3.5 # MAG_PETRO parameters: <Petrosian_fact>,
# <min_radius>
PHOT_AUTOAPERS 0.0,0.0 # <estimation>, <measurement> minimum apertures
# for MAG_AUTO and MAG_PETRO
PHOT_FLUXFRAC 0.2,0.5,0.8 # flux fraction[s] used for FLUX_RADIUS
SATUR_LEVEL 50000.0 # level (in ADUs) at which arises saturation
SATUR_KEY TOTO # keyword for saturation level (in ADUs)
MAG_ZEROPPOINT 30.0 # magnitude zero-point
MAG_GAMMA 4.0 # gamma of emulsion (for photographic scans)
GAIN 0.0 # detector gain in e-/ADU
GAIN_KEY GAIN # keyword for detector gain in e-/ADU
PIXEL_SCALE 0 # size of pixel in arcsec (0=use FITS WCS info)

```

```

#----- Star/Galaxy Separation -----
SEEING_FWHM      0.9          # stellar FWHM in arcsec
STARNNW_NAME     default-auto.nnw # Neural-Network_Weight table filename

#----- Background -----
BACK_TYPE        AUTO         # AUTO or MANUAL
BACK_VALUE       0.0          # Default background value in MANUAL mode
BACK_SIZE        128          # Background mesh: <size> or <width>,<height>
BACK_FILTERSIZE  3             # Background filter: <size> or <width>,<height>
BACKPHOTO_TYPE   GLOBAL        # can be GLOBAL or LOCAL
BACKPHOTO_THICK  24            # thickness of the background LOCAL annulus
BACK_FILTTHRESH 0.0           # Threshold above which the background-
                                # map filter operates

#----- Check Image -----
CHECKIMAGE_TYPE  MINIBACKGROUND # MINIBACKGROUND, MINIBACK_RMS, -BACKGROUND,
                                # FILTERED, OBJECTS, -OBJECTS, SEGMENTATION,
                                # or APERTURES
CHECKIMAGE_NAME   CFHTLS_D-85_y_100028+021230_T0007_mbkg.fits
                                # Filename for the check-image

#----- Memory (change with caution!) -----
MEMORY_OBJSTACK  3000          # number of objects in stack
MEMORY_PIXSTACK  300000         # number of pixels in stack
MEMORY_BUFSIZE   1024          # number of lines in buffer

#----- ASSOCiation -----
ASSOC_NAME       sky.list       # name of the ASCII file to ASSOCiate
ASSOC_DATA       2,3,4          # columns of the data to replicate (0=all)
ASSOC_PARAMS     2,3,4          # columns of xpos, ypos[,mag]
ASSOC_RADIUS     2.0            # cross-matching radius (pixels)
ASSOC_TYPE       NEAREST        # ASSOCiation method: FIRST, NEAREST, MEAN,
                                # MAG_MEAN, SUM, MAG_SUM, MIN or MAX
ASSOCSELEC_TYPE MATCHED        # ASSOC selection type: ALL, MATCHED or -MATCHED

#----- Miscellaneous -----
VERBOSE_TYPE     NORMAL         # can be QUIET, NORMAL or FULL
HEADER_SUFFIX    .head          # Filename extension for additional headers
WRITE_XML        Y              # Write XML file (Y/N)?
XML_NAME         CFHTLS_W_r_021021-104400_T0007_SExtr_ldac.xml
                                # Filename for XML output
XSL_URL          sextractor.xsl # Filename for XSL style-sheet
NTHREADS         1              # 1 single thread
FITS_UNSIGNED    N              # Treat FITS integer values as unsigned (Y/N)?
INTERP_MAXLAG   16             # Max. lag along X for 0-weight interpolation
INTERP_MAXYLAG  16             # Max. lag along Y for 0-weight interpolation
INTERP_TYPE      ALL            # Interpolation type: NONE, VAR_ONLY or ALL

#----- Experimental Stuff -----
PSF_NAME          default.psf    # File containing the PSF model
PSF_NMAX          2              # Max. number of PSFs fitted simultaneously
PATTERN_TYPE     RINGS-HARMONIC # can RINGS-QUADPOLE, RINGS-OCTOPOLE,
                                # RINGS-HARMONICS or GAUSS-LAGUERRE
SOM_NAME          default.som    # File containing Self-Organizing Map weights

```

B.1.4 SExtractor DUAL MODE .cat catalogue configuration file for T0007 Deep

```

# Default configuration file for SExtractor 2.8.6
# EB 2009-04-09
#
# Last modified for CFHTLS-T0007 chi2 (Megacam):
# YG 2011-09-24

#----- Catalog -----
CATALOG_NAME      CFHTLS_D-25_g_022559-042940_T0007.cat
                   # name of the output catalog
CATALOG_TYPE       ASCII_HEAD      # NONE,ASCII,ASCII_HEAD, ASCII_SKYCAT,
                   # ASCII_VOTABLE, FITS_1.0 or FITS_LDAC
PARAMETERS_NAME    sextr-chi2_APER27.param
                   # name of the file containing catalog contents

#----- Extraction -----
DETECT_TYPE        CCD            # CCD (linear) or PHOTO (with gamma correction)
DETECT_MINAREA     3              # minimum number of pixels above threshold
THRESH_TYPE        ABSOLUTE      # threshold type: RELATIVE (in sigmas)
                   # or ABSOLUTE (in ADUs)
DETECT_THRESH      0.4           # <sigmas> or <threshold>,<ZP> in mag.arcsec-2
ANALYSIS_THRESH    0.4           # <sigmas> or <threshold>,<ZP> in mag.arcsec-2
FILTER             Y              # apply filter for detection (Y or N)?
FILTER_NAME        default-autochi2.conv
                   # name of the file containing the filter
FILTER_THRESH      # Threshold[s] for retina filtering
DEBLEND_NTHRESH   32             # Number of deblending sub-thresholds
DEBLEND_MINCONT   0.002          # Minimum contrast parameter for deblending
CLEAN              Y              # Clean spurious detections? (Y or N)?
CLEAN_PARAM        1.0             # Cleaning efficiency
MASK_TYPE          CORRECT        # type of detection MASKing: can be one of
                   # NONE, BLANK or CORRECT

#----- WEIGHTing -----
WEIGHT_TYPE         MAP_WEIGHT,MAP_WEIGHT
                   # type of WEIGHTing: NONE, BACKGROUND,
                   # MAP_RMS, MAP_VAR or MAP_WEIGHT
WEIGHT_IMAGE        CFHTLS_D-25_gri_022559-042940_T0007_weight.fits,
                   CFHTLS_D-25_g_022559-042940_T0007_weight.fits
                   # weight-map filename
WEIGHT_GAIN         Y              # modulate gain (E/ADU) with weights? (Y/N)
WEIGHT_THRESH       # weight threshold[s] for bad pixels

#----- FLAGging -----
FLAG_IMAGE          flag.fits      # filename for an input FLAG-image
FLAG_TYPE           OR             # flag pixel combination: OR, AND, MIN, MAX
                   # or MOST

#----- Photometry -----
PHOT_APERTURES     10.,12.,14.,16.,18.,20.,22.,24.,26.,28.,30.,32.,34.,36.,38.,
                   40.,42.,44.,46.,48.,50.,52.,54.,56.,58.,60.,26.471
                   # MAG_APER aperture diameter(s) in pixels
PHOT_AUTOPARAMS    2.5, 3.5      # MAG_AUTO parameters: <Kron_fact>,<min_radius>
PHOT_PETROPARAMS   2.0, 3.5      # MAG_PETRO parameters: <Petrosian_fact>,
                   # <min_radius>
PHOT_AUTOAPERS     16.0,16.0     # <estimation>,<measurement> minimum apertures
                   # for MAG_AUTO and MAG_PETRO
PHOT_FLUXFRAC      0.2,0.5,0.8   # flux fraction[s] used for FLUX_RADIUS
SATUR_LEVEL         50000.0        # level (in ADUs) at which arises saturation
SATUR_KEY           TOTO           # keyword for saturation level (in ADUs)
MAG_ZEROPOINT       30.0            # magnitude zero-point

```

```

MAG_GAMMA      4.0          # gamma of emulsion (for photographic scans)
GAIN           0.0          # detector gain in e-/ADU
GAIN_KEY       GAIN         # keyword for detector gain in e-/ADU
PIXEL_SCALE    0            # size of pixel in arcsec (0=use FITS WCS info)

#----- Star/Galaxy Separation -----

SEEING_FWHM   0.9          # stellar FWHM in arcsec
STARNNW_NAME  default-autochi2.nnw
                           # Neural-Network_Weight table filename

#----- Background -----

BACK_TYPE     AUTO          # AUTO or MANUAL
BACK_VALUE    0.0          # Default background value in MANUAL mode
BACK_SIZE     256          # Background mesh: <size> or <width>,<height>
BACK_FILTERSIZE 9            # Background filter: <size> or <width>,<height>
BACKPHOTO_TYPE LOCAL        # can be GLOBAL or LOCAL
BACKPHOTO_THICK 30          # thickness of the background LOCAL annulus
BACK_FILTTHRESH 0.0         # Threshold above which the background-
                           # map filter operates

#----- Check Image -----

CHECKIMAGE_TYPE MINIBACKGROUND # can be NONE, BACKGROUND, BACKGROUND_RMS,
                           # MINIBACKGROUND, MINIBACK_RMS, -BACKGROUND,
                           # FILTERED, OBJECTS, -OBJECTS, SEGMENTATION,
                           # or APERTURES
CHECKIMAGE_NAME CFHTLS_D-25_g_022559-042940_T0007_mbkg_chi2.fits
                           # Filename for the check-image

#----- Memory (change with caution!) -----

MEMORY_OBJSTACK 5000         # number of objects in stack
MEMORY_PIXSTACK 1000000      # number of pixels in stack
MEMORY_BUFSIZE 1024          # number of lines in buffer

#----- ASSOCiation -----

ASSOC_NAME     sky.list      # name of the ASCII file to ASSOCiate
ASSOC_DATA     2,3,4          # columns of the data to replicate (0=all)
ASSOC_PARAMS   2,3,4          # columns of xpos,ypos[,mag]
ASSOC_RADIUS   2.0           # cross-matching radius (pixels)
ASSOC_TYPE     NEAREST        # ASSOCiation method: FIRST, NEAREST, MEAN,
                           # MAG_MEAN, SUM, MAG_SUM, MIN or MAX
ASSOCSELEC_TYPE MATCHED      # ASSOC selection type: ALL, MATCHED or -MATCHED

#----- Miscellaneous -----

VERBOSE_TYPE   NORMAL        # can be QUIET, NORMAL or FULL
WRITE_XML      Y             # Write XML file (Y/N)?
XML_NAME       CFHTLS_D-25_g_022559-042940_T0007_SExtr_chi2.xml
                           # Filename for XML output
XSL_URL        sextractor.xsl # Filename for XSL style-sheet
NTHREADS       0             # Number of simultaneous threads for
                           # the SMP version of SExtractor
                           # 0 = automatic
FITS_UNSIGNED  N             # Treat FITS integer values as unsigned (Y/N)?
INTERP_MAXXLAG 16            # Max. lag along X for 0-weight interpolation
INTERP_MAXYLAG 16            # Max. lag along Y for 0-weight interpolation
INTERP_TYPE    ALL           # Interpolation type: NONE, VAR_ONLY or ALL

#----- Experimental Stuff -----

PSF_NAME       default.psf    # File containing the PSF model
PSF_NMAX       9              # Max.number of PSFs fitted simultaneously
PSFDISPLAY_TYPE SPLIT         # Catalog type for PSF-fitting: SPLIT or VECTOR
PATTERN_TYPE   RINGS-HARMONIC # can RINGS-QUADPOLE, RINGS-OCTOPOLE,

```

```
SOM_NAME          # RINGS-HARMONICS or GAUSS-LAGUERRE  
default.som      # File containing Self-Organizing Map weights
```

Acronyms & Abbreviations

ASCII	American Standard Code for Information Interchange (ASCII) table format
CADC	The Canadian Astronomy Data Center
CCD	Charge Couple Device
CFHT	Canada-France-Hawaii Telescope
CFHT-Elixir	?
CFHTLS	Canada-France-Hawaii Telescope Legacy Survey
COSMOS	Cosmological Evolution Survey
FITS	Flexible Image Transport System (FITS) file format
FoV	Field of View
FWHM	Full Width at Half Maximum
LDAC	Leiden Data Analysis Center (LDAC) catalogue format
MAG_AUTO	?
MAG_SNLS	?
MEF	Multi-Extension FITS (MEF) file format
MegaCam	CFHT wide-field imager
PI(s)	Principle Investigator(s)
PSF	Point Spread Function
PSFEx	PSF Extractor
QA	Quality Assessment
QC	Quality Control
QualityFITS	?
QSO flag	Queued Service Observations (QSO) flag
SCAMP	Software for Calibrating AstroMetry and Photometry
SDSS	Sloan Digital Sky Survey
SDSS-DR8	SDSS 8th Data Release
SExtractor	Source-Extractor
SLR	Stellar Locus Regression
SkyMaker	?
SNLS	SuperNova Legasy Survey
SNR	Signal to Noise Ratio
STIFF	?
SWarp	?
T0006	CFHTLS 6th Data Release
T0007	CFHTLS 7th Data Release

Acronyms & Abbreviations (cont.)

USNO	United States Naval Observatory
VIMOS	Visible MultiObject Spectrograph
VIPERS	VIMOS Public Extra Galactic Observation Survey
WeightWatcher	?
XML	Extensible Markup Language (XML) table format
Youpi	“YOUpi is your processing PIpline”
ZP(s)	Zero Point(s)
2MASS	The Two Micron All Sky Survey

References

- Astier, P., et al. 2006, A&A, 447, 31
- Bahcall, J. N., & Soneira, R. M. 1981, ApJS, 47, 357
- Bertin, E. 2006, in ASP Conference Series, Vol. 351, ADASS XV, ed. C. Gabriel, C. Arviset, D. Ponz, & S. Enrique, 112
- Bertin, E. 2009, in Memorie della Società Astronomica Italiana, Vol. 80, 422
- Bertin, E. 2011, in ASP Conference Series, Vol. 442, ADASS XX, ed. I. N. Evans, A. Accomazzi, D. J. Mink, & A. H. Rots, 435
- Bertin, E., Mellier, Y., Radovich, M., Missonnier, G., Didelon, P., & Morin, B. 2002, in ASP Conference Series, Vol. 281, ADASS XI, ed. D. A. Bohlender, D. Durand, & T. H. Handley, 228
- Boulade, O., et al. 2000, in SPIE Conference Series, ed. M. Iye & A. F. Moorwood, Vol. 4008, 657
- Capak, P., et al. 2007, ApJS, 172, 99
- Kron, R. G. 1980, ApJS, 43, 305
- Magnier, E. A., & Cuillandre, J.-C. 2004, PASP, 116, 449
- Marmo, C., & Bertin, E. 2008, in ASP Conference Series, Vol. 394, ADASS XVII, ed. R. W. Argyle, P. S. Bunclark, & J. R. Lewis, 619
- Oke, J. B. 1974, ApJS, 27, 21
- Pickles, A. J. 1998, PASP, 110, 863
- Regnault, N., et al. 2009, A&A, 506, 999
- Schlegel, D. J., Finkbeiner, D. P., & Davis, M. 1998, ApJ, 500, 525
- Schltheis, M., Robin, A. C., Reylé, C., McCracken, H. J., Bertin, E., Mellier, Y., & Le Fèvre, O. 2006, A&A, 447, 185
- Sesar, B., Jurić, M., & Ivezić, Ž. 2011, ApJ, 731, 4
- Skrutskie, M. F., et al. 2006, AJ, 131, 1163
- Smith, J. A., et al. 2002, AJ, 123, 2121
- Szalay, A. S., Connolly, A. J., & Szokoly, G. P. 1999, AJ, 117, 68
- Westera, P., Lejeune, T., Buser, R., Cuisinier, F., & Bruzual, G. 2002, A&A, 381, 524